

STATE BANK OF INDIA
LOCAL HEAD OFFICE, GUWAHATI
PREMISES & ESTATE DEPARTMENT
GUWAHATI, ASSAM.

ADMINISTRATIVE OFFICE, SHILLONG

Estimate for Supply, Installation, Testing and Commissioning of Air-conditioners at DGM chamber

Sl.No.	Description	UOM	Qty.	Rate (Rs.) (Exclusive of GST)	Amount (Rs.) (Exclusive of GST)
1	Supply, testing, commisioning & Installation of Hot and Cold 2.0 TR 3 Star Cassette type Inverter Ac having ISEER more than 3.5 with cordless remote, Copper Condensor Coil, outdoor frame / stands to withstand the full load of outdoor units. AC Make, Voltas/Bluestar/Carrier/Daikin /LG/Godrej /Hitachi	No.	2		
2	For 2.0 TR Cassette type air conditioners: Supply and laying of copper pipes, drain pipes (covered with GI pipes wherever necessary), copper wiring in GI conduits neatly drawn in professional manner from power points to outdoor / indoor units complete with all necessities and making good all the damages.	RM	20		
3	Supply and Installation of 5 KVA Stabilizer for 2.0 TR cassette ACs	Nos.	2		
4	Supply and Installation of additional drain water UPVC pipe for properly conecting to the drain point	RM	20		
	TOTAL- (Excluding GST)				
GST will be extra as applicable.		Grand Total			