

STATE BANK OF INDIA

LOCAL HEAD OFFICE : MAHARASHTRA

AIRCONDITIONING WORKS OF BHOOM BRANCH, OSMANABAD

ES

Sl.No.	Item Description	Qty.	Unit	Rate
1	Supply, Installation, Testing and commissioning of CASSETE Inverter type split air conditioners with first fill of refrigerant (R32 or R 410A) & electrical wiring between indoor and outdoor units complete. Indoor unit ceiling hung comprising cooling coil, evaporator fan with motor, filters, insulated drain pan, drain pump, expansion valve, refrigerant filter drier with codeless remote control unit, etc. Outdoor unit comprising single phase hermetically sealed scroll / rotary compressors , condenser coil with fan & motor, starters / controls / cutouts / relays etc., mounted inside a powder coated sheet metal cabinet of 2mm thick, duly treated for corrosion protection complete, mounted on ribbed rubber pads. (Excluding copper pipe) Capacity 2.0TR Minimum 3 star Inverter Cassette AC (Single phase) or Three Phase with scroll/rotary/swing Compressor (Banking Hall)	6	Set	
2	Supply and erection of copper piping using copper (1mm thick) refrigeration pipe complete with bends, Elbows, Supports, Insulation etc. interconnecting indoor and outdoor units (both suction and discharge lines) along with necessary electrical copper wiring including earthing conductor in rigid PVC conduit. (insulation using 19mm thick nitrile rubber sleeve insulation)	130	m	
3	Supply and erection of angle/channel support for the condenser unit to be mounted on the wall. (For cassette AC)	6	Set	
4	Supply and erection of 25mm dia PVC drain water piping (4kg/sq.cm.) upto just above ground level for all ACs including Split ACs and its insulation using 4 mm thick nitrile rubber sleeve insulation.	100	m	
5	Supply and Installation of 1 TR Capacity Hi Wall mounting 5 Star rated Inverter Split AC with cordless remote and other accessories complete with ID and OD unit with copper condensing unit, R-410 refrigeartnt etc complete as reqd. (with copper piping upto 3metre) (High Wall Split AC). Insulation using nitrile rubber insulation with Teflon taping.	1	Nos.	
6	Supply and Installation of 4 kVA V-Guard Stabiliser with metallic enclosure.	1	Nos.	
7	Less: Buyback price for existing Window & Split Airconditioners in "as is where is" condition. The air conditioners (ODU, IDU and piping) has to be dismantled and cleared from Bank's premises by the successful tenderer at their own cost.	-7	Tonne	
8	Supply and erection of angle/channel support for the condenser unit to be mounted on the wall. (For Split AC)	1	Set	
GRAND TOTAL : (COST OF AIRCONDITIONING WORKS) & EXCLUDING GST				

TIMATE

[illegible]