

**STATE BANK OF INDIA**  
**LHO, MAHARASHTRA**

**AIRCONDITIONING WORKS OF BALSUR BRANCH, DHARASHIV**

SN	Item Description	Qty	Unit	Rate
1	Supply and Installation of 1.5 Tonne Capacity Hi Wall mounting 5 Star rated Inverter Split AC with cordless remote and Copper Condensor Coil. (with copper piping upto 3metre) (High Wall Split AC) with Insulation of refrigerant lines using nitrile rubber insulation with Teflon taping. (Banking Hall)	2	Nos.	
2	Supply and Installation of 1.0 Tonne Capacity Hi Wall mounting 5 Star rated Inverter Split AC with cordless remote and Copper Condensor Coil. (with copper piping upto 3metre) (High Wall Split AC). Insulation using nitrile rubber insulation with Teflon taping. (BM-1, ATM-2, Server-2)	1	Nos.	
3	Supply and installation of powder coated ready made metallic stand for mounting ODU of Split Airconditioners.	3	Nos.	
4	Supply and laying of additional length of copper refrigerant line (double circuit) beyond 3 Metre for each AC unit.	50	Mtr.	
5	Supply and Installation of 4 kVA V-Guard /OEM make Stabiliser with metallic enclosure.	3	Nos.	
6	<b>Drain water piping work out of 25/32 mm PVC/HDPE hard pipes</b> covered with 4 mm thick nitrile rubber sleeve insulation, complete with fittings, bends, elbows, tees flanges, tappings, wall sleeves, hangers, supports, anchors	30	Mtr	
<b>TOTAL AMOUNT FOR THE AIRCONDITIONING WORKS</b>				

Amount