

STATE BANK OF INDIA
LOCAL HEAD OFFICE, GUWAHATI
PREMISES & ESTATE DEPARTMENT
GUWAHATI, ASSAM.

JESSAMI BRANCH, RBO IMPHAL EAST, MANIPUR

Estimate for Supply, Installation, Testing and Commissioning of Air-conditioners (New Branch)

Sl.No.	Description	UOM	Qty.	Rate (Rs.) (Exclusive of GST)	Amount (Rs.) (Exclusive of GST)
A High Side work: Supply of Machines					
1	Supply of 1.5 TR Capacity Hi Wall mounting 5-star rated Inverter Split Ac having ISEER more than 4.5 with cordless remote and Copper Condensor Coil. AC Make, Voltas/Bluestar /Carrier/ Daikin /LG/Godrej /Hitachi (For Banking hall)	No.	1		
2	Supply of 2.0 TR 5 Star Cassette type Inverter Ac having ISEER more than 4.5 with cordless remote and Copper Condensor Coil. AC Make, Voltas/Bluestar /Carrier/ Daikin /LG/Godrej /Hitachi (For Banking hall)	No.	4		
TOTAL-A (Excluding GST)					
B Low Side Work: Installation & Commissioning work					
1	Installation charges of the 1.5 TR Hi-Wall Split AC including outdoor frame / stands to withstand the full load of outdoor units and making good all the damage.	No.	1		
2	Installation charges of the 2.0 TR cassette AC including outdoor frame / stands to withstand the full load of outdoor units and making good all the damage.	No.	4		
3	For 1.5 TR hi wall split type air conditioners: Supply and laying of copper pipes, drain pipes (covered with GI pipes wherever necessary), copper wiring in GI conduits neatly drawn in professional manner from power points to outdoor / indoor units complete with all necessaries and making good all the damages.	RM	10		
4	For 2.0 TR Cassette type air conditioners: Supply and laying of copper pipes, drain pipes (covered with GI pipes wherever necessary), copper wiring in GI conduits neatly drawn in professional manner from power points to outdoor / indoor units complete with all necessaries and making good all the damages.	RM	40		
5	Supply and Installation of 4 KVA Stabilizer for 1.0/1.5 TR Split Acs	Nos.	1		
6	Supply and Installation of 5 KVA Stabilizer for 2.0 TR cassette Acs Acs	Nos.	4		
7	Supply and Installation of additional drain water UPVC pipe for properly connecting to the drain point	RM	40		
TOTAL-B (Excluding GST)					
GST will be extra as applicable.		Total: A+B (In Rupees)			
		Grand Total			