

BOQ FOR INTERIOR FURNISHING WORK FOR THE NEW PREMISES OF SBI M.P NAGAR BRANCH LOCATED AT E-2,67, ARERA COLONY BHOPAL

SNo.	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
1	FALSE CEILING				
	Note : i) Rate to be included for all kinds of profiles and cut outs required for light fixtures, Speakers, Smoke detector, trap doors and AC grill in the ceiling. Provision for light fittings, AC grills and diffusers have to be made at no extra cost supported with tees, Angles, etc. suitably fixed all complete as per drawing and direction. The area of these cutouts which is less than 0.5 sqmt for one unit will not be deducted while measuring the ceiling area. ii) The contractor must co-ordinate with electrical & AC contractor for working out various levels for the false ceiling & make the marking on the walls / columns before starting the false ceiling work. (The test certificate from the manufacture for all theplywood/board/laminate/mica shall be submitted at the time of dilivery at the site address needs to be included)				
1.1	Mineral Fibre Grid Tile Ceiling :				
	Mineral Fibre Acoustic Ceiling Tiles : Providing, making & Fixing at all heights & in spirit level, Acoustical Ceiling System @ Office areas with Armstrong make mineral fibre acoustical suspended ceiling system as per Manufacturer's specification with pin-hole tiles, tegular edge with 24 mm exposed grid. The tiles should have Colour White, in module size of 600mm x 600mm x 15mm. with providing and fixing Hot dipped galvanized Steel suspension system Grid frame with butterfly clips, for laying of Acoustical Ceiling Tiles as per manufacturer's specifications. The grid should be laid on Armstrong/Gyproc stitched True lock 24 TL exposed grid systems with 24 mm wide T-section flanges color white, the tile will be laid on frame work made of Armstrong Prelude 32 with 24 mm wide T - section flanges or of equivalent make, colour white having rotary stitching on all T sections i.e. the Main Runner, 1200 mm & 600 mm Cross Tees with a web height of 32 mm and 27mm ,25 mm respectively. The cost shall include all fittings and materials complete ... contd...	Sqm	213.66		
	...contd... including proper installation and provisioning etc. The work is to be completed as per manufacturer's specification. (Make: Armstrong / Diamond / USG Boral)				
1.2	Gypsum Board False Ceiling :				
	Providing, making and fixing Gypsum Board False Ceiling straight or curve any profile of reputed make which includes G.I. Perimeter Channels of size 0.55mm thick (having One Flange of 20mm and another flange of 30mm and a web of 27mm) along with perimeter of ceiling, screw fixed to brick wall / partition with the help of Nylon sleeves and screws at 610mm centres. Then suspending G.I. intermediate channels of size 45mm (0.9 mm thick with two flanges of 15mm each) from the soffit at 900mm centres with ceiling angle of width 25mm X 10mm X 0.55mm thick fixed to soffit with G.I. cleat and steel expansion fasteners. Ceiling section of 0.55mm thick having knurled web of 51.5mm and two flanges of 26mm each with lips of 10.5mm are then fixed to the intermediate channel with the help of connecting clips and in direction perpendicular to the intermediate channel at 457 mm centres. The grid should be laid on Armstrong/Gyproc stitched True lock 24 TL exposed grid systems with 24 mm wide T-section flanges color white, the tile will be laid on frame work made of Armstrong Prelude 12.5mm tapered edge Gypsum board (conforming to IS 2095-1982) is then screw fixed to ceiling section with 25mm dry wall screws at ... contd..	Sqm	208.97		

SNo.	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
	... contd... 230mm centres. Screw fixing is done mechanically with drilling machine with suitable attachment. Finally tapered edges of the Gypsum boards are to be jointed and finished so as to have a flush look which includes filling and finishing with jointing compound, joint paper/fibre tape and two coats of dry wall top coat suitable for Gypsum board etc. complete as per the recommended practices / specifications of the manufacturer. Including two coats of primer suitable for gypsum board two or more coats of plastic emulsion paint of approved shade and also including making necessary openings for light fittings, grills, diffusers, cutouts made with frame of perimeter channels suitable fixed all complete as per drawing and specification and direction. Rate to be inclusive of shadow profile at the junction of wall & ceiling, in between of ceiling, etc. complete. (Make: Gyproc/ Saint Gobain / Gold Bond)				
1.3	Cove in ceiling	Rm	165.35		
	Same as above but providing, making and fixing Gypsum cove (inside height 150 - 200 mm and border 75 mm) to hide strip/cove light in ceiling or to act as pelmet for roller blinds on windows or for projector screen, etc.				
2	Full Height Partly Glazed (With etching) Partly Wooden Double Skin Plywood Partitions :	Sqm	124.88		
(a)	Providing and fixing full height partly wooden, partly glazed double skin partition with following specifications				
(b)	Providing and fixing full height partly glazed double skin partitions made out of Frame work to be 50mm X 50mm X 1.60 mm thick aluminum section weight not less than 0.836 kg/rmt with maximum distance of 450mm c/c both ways (Horizontal/Vertical) or as directed, firmly fixed to floor or slab with 65 to 75 mm long screw or as directed by the Bank's Engineer as per site conditions with necessary grooves and cuts etc. including anti-termite treatment to all wooden members wherever used. The partition to be sandwiched with 9 mm thick commercial plywood (Make: Century/Archid/ Green ply) from both the sides and finished with 1.0 mm thick approved shades of laminated finish and match the panelling pattern. Additional wooden members to be provided wherever door is to be provided. Wood shall be treated with antitermite chemicals. The cost shall include all labor, materials, strictly as per the given design & drawing etc. in complete.				
©	The partition will be provided with 8 mm thick float glass fixed at 900 -1200 mm above the floor level with teak wood beading fixed on both sides of the glass finished with polishing as directed. The float glass to be etched as per approved design (film etching to be paid separately). The beading for fixing glass to be fixed on both sides of the partition in such a way that it would be projected from the partition.				
(d)	The top panel (above glass panel) and side panels shall be provided with 9.00 mm thick commercial plywood (Make: Century/ Archid/ -) double skin partition as per specification of a) & b) upto ceiling/top support. Making provision for items like softboards, white boards, electrical points, switchboards, telephone/ electrical/ data cables, etc. as & where required (including the cost for items). All finishes shall be done as per details and as per instructions of Bank's engineer. The rate to include all materials, labour, transport, etc. complete.				
(e)	Providing 75mm - 150 mm high skirting having 9.00 mm thick ethick commercial plywood fixed on both sides of the partition finished with 1.00 mm thick lamination of approved make and shade(Make: Century/Green ply/ Archid). All wooden structures are to be painted with anti-termite/borer paint as per manufacturer's specification.				
(f)	Providing and making suitable door frame with rebate for door shutters using approved quality seasoned full-length Teak Wood having finished sectional size 75mm x 20mm to the door perimeter complete as per detailed Architectural drawing and as directed at site.				
(g)	Applying 2 or more coats of approved matching shade and finish, melamine polish to all exposed edges of partitions including those in door openings, cutouts etc. complete.				

SNo.	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
(h)	The rate shall include cost of required hardware, necessary transportation, execution of work at all heights and locations including all lead, lift, wastage, statutory liabilities etc. complete.				
3	Low Height partitions With/Without Glass (With etching):	Sqm	40.83		
	P/F low ht. double skin glazed wooden partition approx. 1200 mm to 1450mm. High including float glass, with following specifications:				
	Providing and fixing low height partly glazed double skin partitions made out of Frame work to be 50mm X 50mm X 1.60 mm thick aluminum section weight not less than 0.836 kg/rmt with maximum distance of 450mm c/c both ways (Horizontal/Vertical) or as directed, firmly fixed to floor or slab with 65 to 75 mm long screw or as directed by the Architect/ Bank's Engineer as per site conditions with necessary grooves and cuts etc. including anti-termite treatment to all wooden members wherever used. The partition to be sandwiched with 9.00 mm thick commercial plywood from both the sides and finished with 1.0mm thick approved shades and make (Make: Formica / Sunmica / Archid) of laminated finish & match the panelling pattern. The borders/edges to be laminated finish. The cost shall include all labor, materials, strictly as per the given design & drawing etc. in complete. One additional section 50 x 50 mm shall be placed at 700 mm level from floor to fix the table. Additional wooden members to be provided wherever door is to be provided. Wood shall be treated with antitermite chemicals				
	P & F 12 mm thick (approx.) etched glass (with etching) as per design and shape fixed with stainless steel glass fixing brackets/crews etc. of length varying from 750 to 1550 mm and height appx. 300 - 400 mm. etc. complete as directed.				
	P & F wicket gate wherever required with required SS hinges, SS tower bolts, automatic surface mounted spring door closer, Godrej Night latch, etc. Rubber wood capping made out of sect. 65 x 15 mm fixed at edges incl. natural polish / painting etc. complete as directed.				
	Making provision for items like softboards, white boards, electrical points, switchboards, telephone/ electrical/ data cables, etc. as & where required (but excluding the cost for items). All finishes shall be done as per details and as per instructions of Bank's engineer. The rate to include all materials, labour, transport etc complete. Further the partitions should have provision for fixing/embedding of vertical toughened glass partition and also toughened glass in vertical/horizontal position on SWO counter top, which will be measured separately.				
4	Full Height Cement Board Double Skin Partition :	Sqm	8.63		
	Providing and Fixing full height cement board double skin partition made out of 65X65X3 mm thick aluminium section and 10 mm thick cement board of Bison or equivalent make. Alum. section to be fixed at maximum 600 mm centre to centre for verticle members and at 0', 900 mm, 2100 mm and ceiling levels for horizontal member fixed with wooden screws, Painting will be paid seperately.				
5	12mm toughned glass with etching work (as required)	Sqm	15.77		
	Providing & Fixing 12mm thk. Toughned Glass Panels with SS glass connectors of 304 Grade, fixed in position, with etching / filming, as per interior details/instruction of the Achitect/SBI Engineer				
6	12mm Glass work	sqm	5.17		
	Providing, making and fixing in position 12mm thick clear float glass in the front side, vertically of height 400 mm and to place & fix another float glass of 12 mm thickness with round edged to be placed horizontally (of width 400 mm) above the vertical glass of length, equal to the length of the counter.				

SNo.	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
	Above this horizontal glass, a glass of 12 mm thickness of approx. 300 mm height will be placed vertically above the horizontal glass. The top glass to have a arch type, semi circular opening of dia 150 mm. All the edges of the glass to be polished for a smooth finish and the glass is to be embedded in half partitions and fixed with " D " brackets/SS fittings. Etching of glass with film to be done as directed (measured separately). The cost to include all materials, labour, hardware etc., for a neat finished job as per drawings and directions etc., complete.(Make : Modi float, Triveni Float , Saint Gobian)				
	Providing, making and fixing 10mm thick clear float glass of reputed brands like Modi, Saint Gobain or equivalent as approved as glazing, glass shutters in displays, table tops etc. & of size as instructed, edge polished. Glass to be fixed from top and bottom in ply partitions or all four sides inside partitions or shutters with beadings, SS fittings, etc. complete.	Sqm	22.41		
7	Glass partition on SS props (ATM)				
	Providing & fixing 12 mm frosted glass 0.90 m x 0.90 m at a height of 0.90 m and rising upto 1.80 m supported by stainless steel props / legs. SS props to be of 50 mm diameter hollow pipes with SS D brackets to hold glass. 150 mm Diameter circular plate at the base of the pipes and anchored to ground with three anchor bolts.	Sqm	3.66		
8	MAIN ENTRANCE DOOR WITH 12.0MM TOUGHNED GLASS & Patch Fittings	Sqm	4.47		
	Fully glazed Door- Providing and fixing frameless fully glazed 12mm thk toughened glass door fixed with necessary patch fittings (Dorma or equivalent make) including cutting, making holes, cutouts in the glass of required shape and size to accommodate fittings and fixing the fittings in floors, soffits, jambs including necessary fixtures, screws, sealant wherever required and SS cover over patch fittings. Rate shall include necessary etching film / LOGO, approved patch fitting locking systems, 1 pair of 600mm long S. S. (H Shape) Handles of approved make, floor springs, and any necessary hardware items. (DORMA MAKE Top Pivot - PT 24, Top Patch Fittings - PT 20, Bottom Patch fittings - PT 10, Floor Spring - BTS 75 V, Corner lock with strike plate and Euro Profile Cylinder - US 10, Handle - TG DIH600 - 600mm length) Measurement will be taken only upto solid partition level above.(Make : Modi float, Triveni Float , Saint Gobian)				
9	Partly Glazed Door : (Partly Glazed Door on Floor Spring)	Sqm	20.94		
	Providing, making & Fixing of partly Glass door at site, door shall be of 32 mm thk flush door with 1 mm lamination on both sides and central portion to have 8 mm plain float glass, to be fixed to existing partition with heavy duty 4" hinges and shall have cylindrical lock.To be provided with necessary lipping, beading, etc. The cost shall also include providing and applying paint/polish on all surfaces including lippings etc. wherever instructed of approved shade and finish including thorough cleaning, rubbing and surface preparation, application of primer, sealers, etc. as required. The door shall be fixed, provisioning of locking system, with 2 Nos. of 450 mm S.S. brush finish handles (H type), providing "PUSH" * "PULL" sticker lables of approved design & make, outside Aldrop, its fittings and fixtures, etc. complete all of approved make. The rate to include all materials, labour, transport, taxes, delivered and placed in position at site of work.(Make : Modi float, Triveni Float , Saint Gobian)				
10	PANELLING ON WALL	Sqm	134.90		

SNo.	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
	Providing and fixing panelling on walls front facia, boxing for rolling shutter, and/or columns and/or glazing soffits at various parts of the premises as required with framework of 50 mm X 25 mm - 18 gauge section un anodised Aluminium (as per requirement) frame work @ 16" to 24" c/c for levelling and 10 mm thick prelaminated pre laminated HDHMR board board ply of approved ISI grade, and/or limited use o f 6mm Flexible ply for panelling of circular columns etc. including fixing as per pattern and style as directed, with covered with 8 mm thick fixed vertically and horizontally 600 mm c/c or less as per site condition and 6 mm thick HD MR plywood shall be fixed over the frame (either in one plane or at different levels) finished with 1mm thick decorative laminate of approved made and shade (in one or multi colour) shall be fixed with proper adhesive as directed. Top of the paneling / edges is to be provided lamination or with teak wood decorative beading of 50mm x 20 mm finished with polish/painting as directed.(Make: Archid / Century/ Green Ply)(The test certificate from the manufacture for all the plywood/board/laminate/mica shall be submitted at the time of dilivery at the site address needs to be included)				
11	ACP Panelling (Interior Grade) ATM & shutter box	Sqm	81.99		
	ACP Panelling in ATM room & exteriors and Shutter boxing with trap door : Providing and fixing in position Aluminium Composite Panel (ACP) on wall, boxing, shutter panelling with framing of M.S. Tube sections of min. 50 mm x 25 mm and 16 gauge, (OR Aluminium tubular section of same sectional dimensions if required) of good quality, fixed/fabricated @ 600 mm c/c or less as per site requirement or members recommended by the manufacturer and in accordance with the specifications and recommendations of the manufacturer. The structure shall be fitted in place on walls/ beams/columns/ceilings/ MS fabricated structures etc. as instructed using recommended fixing method, with 3M or equivalent adhesive and with mirror screws, joints to be finished with silicon based sealant, etc. complete. ..contd..				
	..contd.. ACP to be in 600 mm width panels or distributed equally. it shall be of thickness of 3 mm minimum. Alubond / Eurobond / Fujibond / Alcobond or equivalent ISI brands to be used. Bright silver / shaden to be as per bank's approval. Additional sections to be provided to fix the indoor AC units. The AC units to be installed near the machine area at the highest position. Shutter Trap door will be of 12 mm MR ply finished with ACP. The cost shall include all scaffoldings, chase making, lifting, cutting, on site adjustments, plaster repairing, etc. complete.				
12	Cabinet for Electric Panel:	Sqm	1.37		
	Providing and fixing Electric panel cabinet using 19 mm thick facotry made wpc board for frame sides verticle and shelves and front shutters with aluminium framing of 50x25x1.5mm thick with 6mm thick panel on both side finished CNC jali with 1.0 mm thick laminate on all exposed surface and fire proof paint & synthetic enamel paint on all internal surface. Shutter with approved make lock handle, hinges, ball catchers, CNC jali shall be provided in shutter for ventilation, complete as directed, depth of panel 1'-3". Shutter height as required and above area fixed .Make: Archid / Century / -)(The test certificate from the manufacture for all theplywood/board/laminate/mica shall be submitted at the time of dilivery at the site address needs to be included)				
13	TABLES:				
	OFFICER'S TABLES WITHOUT SIDE CREDEENZA				
	(a) Providing and fixing at site Officer's table made of 19mm th. commercial block board with 1mm thick laminate of desired shade, design and gloss on outer visible surfaces; single color on horizontal surface & two color on vertical surfaces. . The front of the table top shall be projected and curved as per drawing. Provision for 3" dia. Round/3" square stainless steel of grade 304 cable manager for computer / electrical cables at appropriate place, will be made in the top surface of the table. Esteem Biege wood lipping will be provided on all the edges of the table, including bottom touching the floor and the drawers.				

SNo.	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
	The counter shall have a wooden keyboard rest of size 600mm x 270mm made with 19mm ply fixed with sliding telescopic channels of ebco/godrej/hettich make. The work shall also include provision of foot rest made with wooden member of section 3" x 5" along the leg space.				
	(b) There shall be provision of one storage cabinet 1'3" wide. The frame shall be made with 19mm thick commercial board. The cabinet shall have one lockable drawer running on side mounting drawer slides (channels) of EBCO make & one cupboard with shutter beneath the drawer, made of 19mm thick commercial block board with 1mm thick laminate of desired shade, design and gloss on front face, handle / knob and magnetic catcher shall be provided on one side of the table as per layout. The sides of the drawer shall be made of 12mm thick plywood, bottom of 6mm thick plywood & front of 19mm thick block board.				
	All other surfaces i.e. inside / legsapce of table, inside of drawer / cupboard shall be provided with 0.8mm thick laminate of desired shade/design and gloss, and wood lipping / beading shall be PU polished with matching pigment/deco painted in desired colour. The table shall have a CPU ledge made of 19mm thick block board on one side, complete as per drawing.				
13.1.1	Branch Head: TABLE 7'0" X 3'0"	Nos.	1.00		
13.1.2	Officer / Relationship Manager/ Auditor Tables : TABLE 5'0" X 2'6"	Nos.	18.00		
14	CONFERENCE TABLE (5.50 x1.37)	Rmt	4.80		
	CONFERENCE TABLE:- Providing & Fixing Conference Table Made from 18mm commercial Ply ISI Mark as per approved makes with 4mm thick Royal bottom nut Veneer of Make Green ply/ Archidlam duly Melamine Polished Veneer to be fix on all exposed surface of table with inside liner also. Pedestal of table as per drawing. foot rest to be fix with raceway for electrical Cabling complete as per drawing, design & Instruction at Engineer in charge etc complete.(Rate analysis sheet is enclosed) 18 PERSONS SITTING				
15	CENTER TABLE (size 0.90 X 0.60)	Nos	4.00		
	providing & fixing center tables made out of teak wood members 40mm x 75mm with proper joinery & hardware as per drg. all woodwork to be finished with 3 coats of melamine polish.the top to be finished with 12 mm thick tinted glass with bevelled edges. item to include all types of hardwares, screws, lock, hinges, ss handles, Tower bolts, ball catches, wooden lipping, bedding, inlay patti & moulding etc. the measurement of the item shall be on nos. basis.(Make: Archid / Century / Green ply)				
16	SIDE TABLE (size : 0.60X 0.60, 0.30 X 0.30)	Nos	5.00		
	Providing in position side units made of 18mm thick pre laminated HDHMR board board with 1mm th laminate on The top, side and sliding shutter shall be made of 18mm thick pre laminated HDHMR board Board finished with 1mm thick laminate with an adjustable shelf with lock facility with necessary hardware with PVC tape.				
	All exposed veneer / teak surfaces shall be finished with approved colour of melamine.(Make: Archid / Century /Green ply)				
17	Lunch Area Table :	Sq.Mt	0.96		
	.. same as item no. 6.1 and providing & placing in position circular / oval / rectangular / square type design, lunch room table of dimensions L mm x B mm x 750 mm ht. or as specified in laminated board construction, with 12mm thick glass top and wooden members of size 75 mm x 75 mm for base frame & vertical supoorts as per design provided. The glass shall be bevelled edged. The table edges shall be double thick and all visible surfaces shall be finished with laminate including inlay etc. if required and as directed and all hidden areas finished with putty and synthetic enamel and the cost shall be complete with lippings, mouldings, accessories, etc as per specifications. The cost shall include providing and applying putty sealers and fillers on all exposed lipping/ wooden surfaces etc. and finishing with melamine polish of approved shade and finish including thorough cleaning, rubbing and surface preparation, application of primer, sealers, colour tone, and final coat as required. (Measurement = Top usable surface area of the table).				
18	SINGLE WINDOW COUNTER	Rmt	7.97		

SNo.	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
	(a) Providing and fixing at site SWO counters as per the new design and drawings. SWO counters to be made of 19mm thick commercial block board with 1mm thick laminate of desired shade, design and gloss on outer visible surfaces; single color on horizontal surface & two colors on vertical surfaces. The counter shall have a curved front made with flexible 19mm ply and provision of kobe lighting as per the drawings. Provision for 3" dia. Round /3" square stainless steel of grade 304 cable manager for computer / electrical cables at appropriate place, will be made in the top surface of the counter. Teak wood lipping will be provided on all the remaining edges of the counter, including bottom touching the floor and the drawers. The counter shall have wooden keyboard rest of size 600mmx 270mm fixed on sliding telescopic channels of ebco/hettich/godrej. The work shall also include provision of foot rest made with wooden member of section 3" x 5" along the leg space.				
	(b) The counters shall have three self lockable drawers running on side mounting drawer slides (channels) of EBCO/godrej/Hettich make, made of 19mm thick commercial block board with 1mm thick laminate of desired shade, design and gloss on front face & 3 nos. self locking drawer locks be provided on one side of the counter as per layout. The sides of the drawers shall be made of 12mm thick plywood, bottom of 6mm thick plywood & front of 19mm thick block board. All other surfaces i.e. inside / legsapce of table, inside of drawer/Cupboard shall be provided with 0.8mm thick laminate of desired shade, design and gloss, and wood lipping / beading shall be PU polished with matching pigment/deco painted in desired colour. The drawers shall have partitions for keeping currency notes as per drawing, complete in all respects including the required stainless steel hardware like handles, hinges etc. The counter shall have a CPU ledge made of 19mm thick commercial block board on one side, complete as per drawing.				
19	Officer Storage/Side Credenza :	Sqm	18.05		
	Providing, making and placing in position low height storage cabinets as storage and/or runners from 350mm to 500 mm depth, height of 750 to 900 and length as per site requirement, and 18 mm commercial plywood construction with 6mm thk. commercial plywood backing complete. It shall have 2 no. of 125 mm deep drawers, equal size (min. 400 mm) wide on upper side and below to drawers, the cupboard unit shall be with openable shutter & adjustable shelf all along the full width of the credenza. All drawers shall be fitted with telescopic channels and locking arrangement and cupboards shall have locking arrangement and all exposed edges of plywood shall be fitted with lamination / PVC beading . shall have polish/painted of matching color.				
	..contd.. middle made of 18 mm commercial plywood with teak wood lipping with melamine polish on exposed edges duly polished. Two equal side hung shutters of 18 mm th commercial plywood with PVC tape of size 2mm on all edges for each compartment. .. contd..				
	.. contd .. No vertical edge of the storage units should be left sharp. The rate to include for necessary hardware fittings (all SS brush finish) like shutters will be on ebco self closing hinges and drawers shall be on ebco plain slides, SS handle to drawers & shutters, one no. of brass magnetic ball catcher for each shutter, one no. 75 mm long SS tower bolt to relevant shutter and one "Godrej" made lock for each compartment & drawers with common key, etc. complete. All the edges of the plywood in contact with floor also to be provided with teak wood lipping of size 20 x 6 mm. Nylon Buffers of suitable size to be provided under the storage units fixed with screws, wherever required.(Measurement area = Length x Height).(Make: Archid / Century / -) (The test certificate from the manufacture for all the plywood/board/laminate/mica shall be subbmited at the time of dilivery at the site address needs to be included)				

SNo.	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
20	BACK CREDENZA : 18 mm commercial ply Providing and fabrication of 2'-6" high and 1'-3" wide side cabinet with cabinet body of 18mm and back 6 mm thick commercial plywood. The drawer shall be made with 12mm & 6mm thick plywood. The door of cabinet to be fixed with EBCO hinges. Drawer shall be made from 12mm and back shall be made from 6mm ply. All the external exposed surfaces of the cabinet must be covered with 1mm thick laminate of approved brand and shade of Formica or equivalent All the internal / hidden surfaces to be finished with 0.6 mm thick backer lamination. All the edges/ corners of the plywood must be protected with 6 mm thick plain teak wood lipping. Multipurpose lock and handle to be fixed to shutters and. (Measurement area = Length x Height).(Make: Archid / Century / Green ply)	Sqm	36.65		
21	GRAHAK MITRA TABLE ... same as item no. 6.1.2 but providing, making and placing in position arch shape 1650mm long Grahak Mitra Table of approximate size 1650mm x 800mm - 900mm x 750mm with the following specifications and per dimensions specified. Grahak mitra table with transaction top of 370mm wide and height 150 mm made out of 12mm glass with blue laquered to be fixed with SS studs.. Exposed faces would be finished with 1 mm thick laminate on external surfaces and 0.7 mm thick lamination on internal surfaces of approved made and shades.". The table shall have provision only for concealed LED strip lighting (cove type).	Nos.	1.00		
22	Drop & Complaint Box : Providing & fixing at site drop & complaint box of size 300 mm x 400 mm to be made up of 1st class steam beach wood frame of size 25 mm x 25 mm wooden section, front 6 mm thk plain glass. The boxes shall have 12 mm py with approved shade of laminate and lockable shutter as per design 7 drawing, etc. complete.	No	1.00		
23	NOTICE BOARD : Size of Notice board shall be 1200x600 & 150 mm deep. Providing and fixing Notice Board with 18mm BWP board frame & sides finished with 1.0 mm thk Decorative texture laminate, Box to have 75 x 35mm teak wood shutters with 6mm clear glass. The back to have 5-6 mm thick BWP board and 12mm soft Ply covered with cloth of approved shade. The item shall include polishing the wood surfaces etc. complete to the satisfaction of Architect/ Bank's Engineer.(Make: Archid / Century / Green ply).	Nos	2.00		
24	PIN UP BOARDS : Providing and fixing Pin-up boards of 12mm thk. pin board covered with plain matt/cotton fabric as per approval, the fabric stuck with rubber based adhesive to the board as instructed. Cost shall include all tw lippings, base preparation required and joints on fabric shall not be approved.(Make: Archid / Century / Green ply)	Nos	2.00		
25	Zebra Blinds : Providing, supplying & fixing Zebra Blinds of approved (make - Bali, Vista, Johnson) shade etc as per the directions of the Bank at the predetermined locations. The fabric used should be dust, moisture resistant and the vendor to get the sample approved from the Bank before supplying the item. The work includes 40mm / required roller tube / round channel and mechanism and other fitting fixed in position as per manufacture's specification, including all required hardwarw & Scaffolding, complete in all respects to the satisfaction of Architect and SBI engineer.	Sqm	151.03		

SNo.	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
	Specification details of Zebra Blinds are Minimum width 500 mm, Minimum drop 500 mm, Maximum width 2400 mm, Maximum drop 2600 mm, Roller tube Aluminium, Bottom details Round and oval bottom rail to match cassette, Control Chain operation, Control side Right hand side and left hand side, Chain options 10 mm ABS beads with nylon cord, Fabric position Standard roll and reverse roll, Safety device Safety clip, Cassette height 78 mm, Cassette depth 76 mm, Cassette width 84 mm with pelmet, Fabric colour and texture As per the choice of user, Fabric thickness 1.2 to 1.8 mm, Fabric and sunscreen, width 70 mm and 70 mm. Fabric type Shear sunscreen (> 2mm mesh) and solid weave fabric. Operation Operation of the blind should be through a chain system located. (Make: Johnson Window Blinds, Vista Fashions, Vishak)				
26	Plastic Emulsion Paint :	Sqm	288.20		
	Providing & applying Plastic emulsion paint on walls, ceiling, etc. Removing, scrapping & cleaning the existing color wash/ distem-per/oil bond distemper / plastic/ luster etc. paint by scrapping, washing and scrubbing and applying Birla putty nor equivalent. The surface shall then be allowed to dry for atleast 24 hours. It shall be then sand papered to give a smooth & even surface. Holes shall be filled with BIRLA putty, made with plaster of paris.				
27	Corian Marble surface : Providing and fixing 8mm Corian marble surface on furniture/Partition (Rate has been considered after deduction of mica)	Sqm	5.96		
	Supplying, Fabrication and Installation of Dupont/Corian Quartz of 6 to 12mm thk. Applied on table Top, Sides and any where wall, Logo etc in place of 1mm thick laminate. To minimis material usage and facilitate installation a corner block of corian should be made square(Butt) rather than mitred. The edges to be joined should be straight, smooth and clean. Joints should only be made with joint Adhesive for Dupont Corian. All corners of a cutout must be rounded to 5mm radius and the edges smoothed, both on top & bottom, all around a cutout. "L" & "U" shaped corners need smooth 5mm radius inside corner. All works done to the satisfaction of the Architect/Project Manager. Note:- Work done including labour, material wastage, time limits, required hardware etc. Note:- Corian Sheet use in - Salt(Translucent series), Azure & Diamond Blue, preferably on BM's table, SWO counter, as directed.				
28	Aluminium sliding Windows/Ventilators (with frame): as per design	Sqm	20.25		
	Providing and fixing in position aluminium sliding window of extruded builtup standard sections and power coated aluminium section of Jindal, Hindalco, Mann or equivalent approved make and of size, fixing with dash fastners of required size, including filling up the gaps at junctions i.e. top, bottom & sides with required EPDM rubber / neoprene / polysulphide sealant etc. Alluminium section shall be smooth, rust free, straight and jointed mechanically wherever required, including cleat angle, alluminium snap beading for glazing / paneling, stainless steel screws all complete.. The window to have extra sliding track window with MS mosquito mesh fitted to it. 5 mm Glass panes shall be fixed with approved EPDM gasket ting, beading, to be free from settling. Bottom rail shall be with self cleaning gutter section. Rate to be inclusive of cost of all fittings, fixtures, locking arrangement, handles, pegstays, gaskets, screws, hinges etc. complete.				
	modular and anodised aluminium section of approved make and of size 122.2 mm * 45 mm*1.3 mm thick (1.829 kgper running meter for bottom. 122.2 mm * 31.75mm *1.2 mm tick (1.093 kg per running meter for top and sides) comprising of bearing bottom and top of size 40 mm * 18 mm * 1.2 mm thick (weight 0.417 kg per running meter). Interlocking section of size 40 mm *26.70 mm*1.1 mm tick (weight 0.469 kg per running meter). And hand side of 40 mm*18 mm*1.25 mm tick (weight 0.417 kg per running meter) with 5 mm tick plane clear glass of make Asahi/ Saint Gobin. Fixed in Shutter, including approved quality of neoprene gasket, fixtures, fastenings and accessories likes PVC Rollers of make Swastik or equivalent approved, Locks of Starlocks, and stainless screws etc. complete as directed by engineer in-charge.				
	TOTAL ESTIMATED COST OF INTERIOR FURNISHING WORK				

SNo.	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
------	-------------	------	-----	------	--------

Note:- The rates quoted includes all other taxes,duties, loading, unloading, transportation, other expenses etc to site.

GST will be paid additionally as applicable