

Date:

SBI, SME, PRODDUTUR BRANCH
ESTIMATE FOR AIR CONDITIONING WORKS

Sl. No.	Description	UOM	Qty.	Rate (Rs.)	Amount (Rs.)
Part A:					
1	Supply of inverter type Cassettee type split type air conditioner units indoor & outdoor complete with cordless remote control, of required capacity. 5 star rating				
	4.0 TR Capacity	Set	3		
2	Supply of inverter type Hiwall mounted split type air conditioner units indoor & outdoor complete with cordless remote control, of required capacity. Only 5 star rating				
	1.5 TR capacity	Set	4		
	Sub Total Part A				
Part B:					
1	Installation, testing and commissioning of Cassettee and hi wall mounted split type air conditioner units indoor & outdoor complete with in all aspects of required capacity.				
a	Cassettee type	Set	3		
B	1.5 TR capacity HWM type	Set	4		
2	Supply and erection of suitable size of MS stand for outdoor units	Set	7		
3	Supply , installation ,testing and commissioning of Softdrawn copper piping with 9 mm thick Nitrile rubber insulation including all necessary fittings between indoor and out door air cooled condensers of the following sizes				
a	Suction line & liquid line for Cassettee units	RM	45		
B	Suction line & liquid line for high wall mounted units	RM	30		
4	Drain line from indoor to outdoor machines as per standards	RM	100		
5	Supply, laying, testing and commissioning of flexible cable of suitable size for casette units	RM	60		
6	Supply, laying, testing and commissioning of flexible cable of suitable size for HWM units	RM	45		
7	supply, installation, testing and commissioning of 24 hrs duty timer for cyclic operation of Acs installed at ATM room	set	1		
	Sub Total Part B				
	Grand Total (Part A + Part B)				

+GST as applicable