

Sl.No.	Description	UOM	Qty.
Part A:			
1	Supply of inverter type Cassette and Hi-wall mounted split type air conditioner units indoor & outdoor complete with cordless remote control, of required capacity. Only 5 star rating		
a	2.0 TR capacity Cassette type	Set	4
b	1.5 TR capacity HWM type	Set	4
Part B:			
1	Installation, testing and commissioning of Cassette and hi wall mounted split type air conditioner units indoor & outdoor complete with in all aspects of required capacity.		
a	1.5 TR capacity HWM type	Set	4
b	2 TR capacity Cassette type	Set	4
2	Supply and erection of suitable size of MS stand for outdoor units	Set	8
3	Supply , installation ,testing and commissioning of Softdrawn copper piping with 9 mm thick Nitrile rubber insulation including all necessary fittings between indoor and out door air cooled condensers of the following sizes		
a	Suction line & liquid line for hi-wall mounted units	RM	40
b	Suction line & liquid line for cassette units	RM	60
4	Drain line from indoor to outdoor machines as per standards	RM	120
5	Supply, laying, testing and commissioning of flexible cable of suitable size for		
a	HWM units	RM	40
b	Cassette units	RM	60
6	Supply, installation,testing and commissioning of timer for AC units of ATM	Set	1