

Sl.No	Description	UOM	Qty.
Part A:			
1	Supply of inverter type Hi-wall mounted split type air conditioner units indoor & outdoor complete with cordless remote control, of required capacity. Only 5 star rating		
A	2.0 TR capacity	Set	5
B	1.5 TR capacity	Set	4
Part B:			
1	Installation, testing and commissioning of Cassette and hi wall mounted split type air conditioner units indoor & outdoor complete with in all aspects of required capacity.		
	1.5,2 TR capacity HWM type	Set	9
2	Supply and erection of suitable size of MS stand for outdoor units	Set	9
3	Supply, installation, testing and commissioning of Softdrawn copper piping with 9 mm thick Nitrile rubber insulation including all necessary fittings between indoor and outdoor air cooled condensers of the following sizes		
a	Suction line & liquid line for hi-wall mounted units	RM	100
4	Drain line from indoor to outdoor machines as per standards	RM	120
5	Supply, laying, testing and commissioning of flexible cable of suitable size for HWM units	RM	130
6	SUPPLY, installation, testing and commissioning of 24 hrs duty timer for cyclic operation of Acs installed at ATM	Set	1