

Sl.No.	Description	UOM	Qty.
<b>Part A:</b>			
<b>1</b>	Supply of inverter type Hi-wall mounted split type air conditioner units indoor & outdoor complete with cordless remote control, of required capacity. Only 5 star rating		
<b>a</b>	2.0 TR capacity HWM type	Set	5
<b>b</b>	1.5 TR capacity HWM type	Set	4
	Sub Total Part A		
<b>Part B:</b>			
<b>1</b>	Installation, testing and commissioning of hi wall mounted split type air conditioner units indoor & outdoor complete with in all aspects of required capacity.		
<b>a</b>	1.5, 2 TR capacity HWM type	Set	9
<b>2</b>	Supply and erection of suitable size of MS stand for outdoor units	Set	9
<b>3</b>	Supply , installation ,testing and commissioning of Softdrawn copper piping with 9 mm thick Nitrile rubber insulation including all necessary fittings between indoor and out door air cooled condensers of the following sizes		
<b>a</b>	Suction line & liquid line for hi-wall mounted units	RM	90
<b>4</b>	Drain line from indoor to outdoor machines as per standards	RM	110
<b>5</b>	Supply, laying, testing and commissioning of flexible cable of suitable size for		
<b>a</b>	HWM units	RM	90
<b>6</b>	Supply, installation,testing and commissioning of timer for AC units of ATM	Set	1
	Sub Total Part B		