

N.O.W. - FURNISHING OF STATE BANK OF INDIA**KHAMANU BRANCH****PRICE BID FOR THE CIVIL WORKS.**

S.No.	DSR REF.	Item	Quantity	Units	Rate
1		<u>VITRIFIED TILE FLOORING 600MM X 1200MM</u>			
	11.41	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm with 3mm thick groves all around including grouting the joints with epoxy of matching pigments etc., complete. (Italian Marble Shade Digital Tiles from Johnson and Johnson, Kajaria, Somany etc)	204.46	SQM	
	11.41.2	Size 600mm x 1200mm			
		MAKES:			
		VITRIFIED TILES: KAJARIA, JOHNSON AND JOHNSON, ORIENT AND EQUIVALENT.			
		CEMENT: ULTRATECH/ACC/AMBUJA			
2		<u>VITRIFIED TILE FLOORING 400MM X 400MM</u>			
	11.41	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joints with white cement and matching pigments etc., complete. (PAVER ANTISKID ROUGH TEXTURE 12MM THCIK Tiles from Johnson and Johnson, Kajaria, Somany etc)	40.89	SQM	
	11.41.2	Size 400mm x 400mm			
		MAKES:			
		VITRIFIED TILES: KAJARIA, JOHNSON AND JOHNSON, ORIENT AND EQUIVALENT.			
		CEMENT: ULTRATECH/ACC/AMBUJA			
		-			
3		<u>EXCAVATION</u>			

	2.6	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in charge.			
	2.6.1	All kinds of soil	Cum	9.29	
		-			
4		<u>HALF BRICK MASONRY</u>			
	6.12	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure :			
	6.12.2	cement mortar 1:4 (1 cement : 4 coarse sand)	54.32	SQ.M	
		MAKES:			
		BRICKS: FIRST CLASS BRICKS			
		CEMENT: ULTRATECH/ACC/AMBUJA			
5		<u>FULL BRICK MASONRY</u>			
	6.4	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in FOUNDATIONS BELOW plinth(including the cost of back-filling as required) in all shapes and sizes in :			
	6.4.2	Cement mortar 1:6 (1 cement : 6 coarse sand)	7.61	cu.m	
		MAKES:			
		BRICKS: FIRST CLASS BRICKS			
		CEMENT: ULTRATECH/ACC/AMBUJA			
6		<u>FULL BRICK MASONRY</u>			
	6.4	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level and in foundations (including the cost of back-filling as required) in all shapes and sizes in :			
	6.4.2	Cement mortar 1:6 (1 cement : 6 coarse sand)	2.55	cu.m	
		MAKES:			
		BRICKS: FIRST CLASS BRICKS			
		CEMENT: ULTRATECH/ACC/AMBUJA			
7		<u>PLASTERING</u>			
	13.1	12 mm cement plaster of mix :			
	13.1.1	1:4 (1 cement: 4 fine sand)	65.48	SQ.M	
		MAKES:			

		CEMENT: ULTRATECH/ACC/AMBUJA			
8	13.2	15 mm cement plaster on the rough side of single or half brick wall of mix :			
	13.2.1	1:4 (1 cement: 4 fine sand)	65.48	SQ.M	
		MAKES:			
		CEMENT: ULTRATECH/ACC/AMBUJA			
9		<u>WALL/FLOOR TILES</u>			
	11.36	Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer- in-Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm, including pointing in white cement mixed with pigment of matching shade complete. SIZE 1'0" X 2'0"	56.13	SQ.M	
		MAKES:			
		VITRIFIED TILES: KAJARIA, JOHNSON AND JOHNSON, ORIENT AND EQUIVALENT.			
		CEMENT: ULTRATECH/ACC/AMBUJA			
10	11.37	Providing and laying Ceramic glazed floor tiles of size 300x300 mm (thickness to be specified by the manufacturer) of 1st quality conforming to IS : 15622 of approved make in colours such as White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick cement mortar 1:4 (1 Cement : 4 Coarse sand), Jointing with grey cement slurry @ 3.3 kg/sqm including pointing the joints with white cement and matching pigment etc., complete.	9.34	SQM	
		MAKES:			
		VITRIFIED TILES: KAJARIA, JOHNSON AND JOHNSON, ORIENT AND EQUIVALENT.			
		CEMENT: ULTRATECH/ACC/AMBUJA			
11		<u>PUBLIC HEALTH</u>			

	17.78	Providing and fixing white vitreous china single body (cistern and seat attached) with dual flush fitting, of flushing capacity 3 litre/ 6 litre (adjustable to 4 litre/ 8 litres), including seat cover, and cistern fittings, nuts, bolts and gasket etc complete.	3.00	NO.	
		MAKES:			
		WC : KEROVIT/HINDWARE/CERA			
		KEROVIT KUPA- KS709			
12	NS	Providing and fixing UPVC pipes 6kg pressure for soil and waste water pipes with required specials like bends/tees/union etc. Including making the base and covering the same with cement concrete 1:3:6 as per the direction of the engineer-in-charge.			
		75mm dia pipes	27.44	M	
		MAKES:			
		UPVC PIPES : SUPREME/ASTRAL/PRINCE OR EQUIVALENT			
13	NS	100mm dia pipes	39.63	M	
		MAKES:			
		UPVC PIPES : SUPREME/ASTRAL/PRINCE OR EQUIVALENT			
14	NS	Providing and fixing vitreous china wash basin with pedestal including the CP waste complete with required brackets/rawl plugs etc.	3.00	EACH	
		MAKES:			
		WC : KEROVIT/HINDWARE/CERA			
		KEROVIT CASINO- KS283			
15	17.28	Providing and fixing P.V.C. waste pipe for sink or wash basin including PVC. waste fittings complete.			
	17.28.1	Semi rigid pipe			
	17.28.1.1	32 mm dia	5.00	EACH	
16	18.11	Providing & Fixing CPVC pipes complete with fittings and clamps including making good the walls etc. concealed pipe including jointing with the chemical/adhesive, cutting chases and making good the wall:			
	18.11.1	20 mm dia nominal bore	67.07	RM	
		MAKES:			

		UPVC PIPES : SUPREME/ASTRAL/PRINCE OR EQUIVALENT			
17	18.11.2	25 mm dia nominal bore	39.63	RM	
		MAKES:			
		UPVC PIPES : SUPREME/ASTRAL/PRINCE OR EQUIVALENT			
18	18.53	Providing and fixing C.P. brass angle valve for basin mixer and geyser points of approved quality conforming to IS:8931			
	18.53.1	15 mm nominal bore	19.00	EACH	
		MAKES:			
		WC : KEROVIT/HINDWARE/JAQUAR OR EQUIVALENT			
		KEROVIT HYDRUS PLUS			
19	NS	Providing and fixing C. P. Brass Center Hole Mixture/ SINK MIXTURE of approved quality conforming to IS:8931	4.00	EACH	
		MAKES:			
		WC : KEROVIT/HINDWARE/JAQUAR OR EQUIVALENT			
		KEROVIT HYDRUS PLUS			
20	NS	Providing and fixing the CP Brass connections for the connections from angle valve to the wash basin mixture. The pipe shall have brass ends complete with rubber gaskets etc.	19.00	EACH	
21	NS	Providing and fixing 100mm dia. Floor traps complete with the CP. Brass grating both normal grating and grating below the wash basins with and hole for the waste pipe.	11.00	EACH	
		MAKES:			
		FLOOR TRAP : SUPREME/ASTRAL/PRINCE OR EQUIVALENT			
		JALI: 304A STAINLESS STEEL			
22	NS	providing and fixing of complete CP brass accessories set for toilets (towel rail, hand towel rail, paper holder, tooth paste stand, soap dishes for wb's and bathing area etc) as per the direction of the Architect.	3.00	EACH	
23	NS	Providing and fixing the CP brass hand Jet for ablution complete with the PVC connection etc.	3.00	EACH	

		MAKES:			
		WC : KEROVIT/HINDWARE/JAQUAR OR EQUIVALENT			
24	18.5	Providing and fixing C.P. brass bib cock of approved quality conforming to IS standards and weighing not less than 810 gms.			
	18.50.1	15 mm nominal bore	3.00	EACH	
		MAKES:			
		WC : KEROVIT/HINDWARE/JAQUAR OR EQUIVALENT			
		KEROVIT HYDRUS PLUS			
25		Providing and fixing urinal in the Gent's toilet with complete fittings and hardware. The cost shall include providing and fixing of one ceramic partition also. (of approved make)	1.00	EACH	
		MAKES:			
		WC : KEROVIT/HINDWARE/CERA			
		KEROVIT ARUSA- KO512W			
26	NS	Providing and fixing handmade stainless steel sink with sink mixture and all accessories including the cost of cutting of the granite/slab/tiles. Single Bowl 230 mm deep.	1.00	EACH	
		MAKES:			
		SINK: NIRALI, KOHLER, AMERICAN STANDARD			
		NIRALI ELOR SMALL			
27	NS	Providing and fixing Black Granite for the counters/outer verandahs /flooring/skirting etc including the cost of providing single moulding and polishing the same. The cost shall also include the cost of making the sub-base and fixing the granite with neat cement slurry and filling the joints with grout of desired shade as per the direction of the Engineer-in-charge.	39.41	SQ.M	
28	4.1.5	PCC 1:3:6 (1 Cement : 3 coarse sand (zone-III) : 6 graded stone aggregate 20 mm nominal size)	36.83	CU.M	
29	NS	Providing and laying RCC lintel for the doors of 150mm x 150mm in RCC with mix 1:1.5:3 (one cement: 1.5 sand: 3 aggregate) including cost of 4-12mm dia bars and rings of 8mm dia placed @ 5"c/c. The work shall include the cost of required shuttering or any other sundries.	6.71	RM	

30	NS	Providing and laying RCC lintel for the doors of 230mm x 230mm in RCC with mix 1:1.5:3 (one cement: 1.5 sand: 3 aggregate) including cost of 6-12mm dia bars and rings of 8mm dia placed @ 5"c/c. The work shall include the cost of required shuttering or any other sundries.	1.37	RM	
31	NS	Dismantling the existing walls/rcc/floor/ and other civil items etc. complete, providing the required supports in terms of steel girders/rcc beams and making good the surfaces damaged or as per the direction of the engineer-in-charge. The work shall also include removal of the same to an appropriate location as permissible to the local authorities or as per the direction of the Engineer in-charge. (Note: The amount is expected after deduction of amount to be deducted for the buyback of the existing CIVIL ITEMS)	1.00	LS	
32	NS	<u>Plastic Emulsion paint</u>			
		Providing and applying Plastic Emulsion paint three coats to give an even shade after preparation of surface for painting by scrapping etc. & filling including applying 2 coat of P.O.P to give a smooth surface, complete in all respects (Colour to approval) applicable to old or new.	180.00	SQ.M	
		MAKES:			
		PAINTS : ASIAN/NEROLAC/DULUX/BERGER			
33	NS	<u>External Emulsion paint</u>			
		Providing and applying External Emulsion paint three coats to give an even shade after preparation of surface for painting by scrapping etc. & filling including one primer coat, complete in all respects (Colour to approval) applicable to old or new.	60.00	SQ.M	
		MAKES:			
		PAINTS : ASIAN/NEROLAC/DULUX/BERGER			
34	NS	<u>ENAMEL PAINT</u>			
		Providing and applying Enamel paint three coats to give an even shade after preparation of surface for painting by scrapping etc. & filling including one primer coat, complete in all respects (Colour to approval) applicable to old or new.	80.00	SQ.M	
		MAKES:			

		PAINTS : ASIAN/NEROLAC/DULUX/BERGER			
35		<u>DAMP PROOF COURSE</u>			
		Providing and laying damp-proof course 40mm thick with cement concrete 1:2:4 (1 cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 12.5mm nominal size derived from natural sources)	3.10	SQM	
		Total Value of Works			
		Note: GST extra as per applicable			