

**BOQ FOR AC WORKS AT RBO-I LUCKNOW WEST IST FLOOR LCPC BUILDING LUCKNOW
DISTRICT:- LUCKNOW (U.P.)**

S. No.	Item Description	Unit	Qty	Rate	Amount
1	Supply of ceiling suspended energy efficient 4 way air-flow Cooling type single phase 2 Tr, BEE rated 5 star inverter technology Cassette type split air conditioner in recessed manner in false ceiling with full function wireless remote and auto restart feature, Copper condenser coils and Copper cooling coils , company provided copper refrigerant, fan and fan motor drain pan and cordless Remote controller pipe complete in all respects with indoor/ outdoor unit, gas charge etc. Acceptable makes of AC: Daikin/ Carrier/ Voltas/ Blue Star/ Hitachi/ Mitsubishi/Toshiba.(Main Hall)	Set	7		
2	Supply of 2.0 Tr hi wall type BEE rated 5 star inverter technology split air conditioner with full function wireless remote and auto restart feature, with indoor/outdoor unit, gas charge, Copper condenser coils and Copper cooling coils company provided copper refrigerant pipe complete in all respects. Acceptable makes AC: Daikin/Toshiba/O General /Carrier/Blue Star/Voltas/Hitachi/Mitsubishi (Hall)	Set	5		
3	Supply of 1.5 Tr hi wall type BEE rated 5 star inverter technology split air conditioner with full function wireless remote and auto restart feature, with indoor/outdoor unit, gas charge, Copper condenser coils and Copper cooling coils company provided copper refrigerant pipe complete in all respects. Acceptable makes AC: Daikin/Toshiba/O General/Carrier/Blue Star/Voltas/Hitachi/Mitsubishi (One each for BM Chamber)	Set	1		
4	Installation, testing and commissioning of 4/2 TR cassette type air-conditioner with wall cutting/ mounting including making good of damages complete in all respects.	Set	7		
5	Installation, testing and commissioning of 2/ 1.5/ 1 TR Hi wall type split/window air conditioner with wall cutting/ mounting, stabiliser and making good of damages complete in all respects. For old AC dismantling also to be done.	Set	6		

6	Supply, installation, testing and commissioning of insulated copper refrigerant piping set (suction and discharge) duly insulated by nitrile rubber for 4/2 TR cassette AC. Size (thickness and dia) of both Copper pipe should as per recommendation of AC manufacturer's technical specification. (Old pipe dismantled from branch is also to be used) Makes: Totaline/ Met Tube/ Diamond/ Star/ Camipro.	Mtr	140		
7	Supply, installation, testing and commissioning of insulated copper refrigerant piping set (suction and discharge) duly insulated by nitrile rubber for 2/ 1.5/ 1 TR hi wall split AC. Size (thickness and diameter) of both Copper pipes should be as per recommendation of AC manufacturer's technical specification. (Old pipe dismantled from branch is also to be used) Makes: Totaline/ Met Tube/ Diamond/ Star/ Camipro.	Mtr	90		
8	Supply, installation, testing and commissioning of inter connecting wiring/ cabling between indoor and outdoor of Cassette type split AC (power supply will be made available at the outdoor unit, please quote accordingly).	Mtr	150		
9	Supply, installation, testing and commissioning of inter connecting wiring/ cabling between indoor and outdoor of hi wall split AC (power supply will be made available at the outdoor unit, please quote accordingly).	Mtr	100		
10	Supply, installation, testing and commissioning of PVC 25 mm water pipe with accessories and taking care to prevent leakages, for water drainage in concealed manner either on wall or under floor including making good of damages.	Mtr	100		
11	Supply, installation, testing and commissioning of PVC 32 mm water pipe with accessories and taking care to prevent leakages, for water drainage in concealed manner either on wall or under floor including making good of damages.	Mtr	60		
12	Supply and installation of robust MS angle, MS flat fabricated floor/ wall mounting stand suitable for outdoor units of Split /Cassette ACs, painted with one coat of primer and two coats of synthetic enamel outdoor type paint including its grouting and making good of damages, complete in all respects.	Nos.	13		

13	Supply of 5 KVA, wall mounted hi lo cut off stabiliser with TDR, voltage range 140-280V, complete in all respects. Stabilizer: Servel/ V Gaurd/ Marc/Sen & Pandit/ Stambh/ Inmag/Microtek	Set	12		
14	Supply of 4 KVA, wall mounted hi lo cut off stabiliser with TDR, voltage range 140-280V, complete in all respects. Stabilizer: Servel/ V Gaurd/ Marc/Sen & Pandit/ Stambh/ Inmag/Microtek	Set	1		
15	Core cutting/ wall/floor chiseling upto 75mm width and 50 mm depth for concealing the copper pipe, drain pipe and conduit either on wall or under floor including making good of damages with plaster, putti and paint.	Mtr	75		
SUB TOTAL (A):					
					Including GST

Note: Rates are considered inclusive of all including GST. However invoice is to be raised showing GST

