

Sl.No.	Description	UOM	Qty.
Part A:			
1	Supply of inverter type Hi-wall mounted split type air conditioner units indoor & outdoor complete with cordless remote control, of required capacity. Only 5 star rating		
A	2 TR capacity	Set	7
B	1.5 TR capacity	Set	4
		Sub Total Part A	
Part B:			
1	Installation, testing and commissioning of hi wall mounted split type air conditioner units indoor & outdoor complete with in all aspects of required capacity.		
A	1.5 TR,2 TR capacity HWM type	Set	11
2	Supply and erection of suitable size of MS stand for outdoor units	Set	11
3	Supply , installation ,testing and commissioning of Softdrawn copper piping with 9 mm thick Nitrile rubber insulation including all necessary fittings between indoor and out door air cooled condensers of the following sizes		
A	Suction line & liquid line for hi-wall mounted units	RM	100
4	Drain line from indoor to outdoor machines as per standards	RM	130
5	Supply, laying, testingand commissioning of flexible cable of suitable size for HWM units	RM	100
6	Supply, installation,testing and commissioning of timer for AC units of ATM	Set	1
		Sub Total Part B	
		Grand Total (Part A + Part B)	