

## ESTIMATE FOR INTERIOR WORKS -IN THE NEW PREMISES OF TANAKALLU NEW BRANCH , DHARMAVARAM RBO, KURNOOL AO.

Banks Uniform Layout Policy Colour Scheme to be followed.

## GENERAL INSTRUCTIONS TO BIDDERS (TO BE FOLLOWED AS PER SITE CONDITIONS):

- i.) All contractors are requested to understand the uniform layout policy colour scheme and the specifications of the SBI before quoting the rates. They are also advised to see and understand some branches where Interior already done and approved by the bank.
- ii) All exposed faces of Teak Wood beadings should be melamine polished and tinted to required shade as directed by the Client/ Architect.
- iii) Anit-Termite treatment shall be done for all wooden and ply members.
- iv) All the Carpentry work must be executed only in site after getting the Materials approved from Client/Architect.
- v) Modular Type of Furniture work is not acceptable.

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
1	<b>SINGLE WINDOW COUNTERS WITH CORIAN SOLID SURFACES</b>	No	4.00		
	Single Window Counters: Providing & fixing 5ft-5 1/2 ft. wide Single Window Counters : Counter top and side unit top to have 25mm Block Board with double thickness at edges with 1mm thick laminate on all horizontal surfaces (such as counter top, etc., ) and the front fascia and remaining all exposed vertical faces to have 1mm Glossy Laminate as specified. The 1mm thick laminate to continue in the front side with curvature from the front table top to the modesty panel. All other members to be made with 18mm MDF Exterior Grade Board of banks approved brand and variant. Complete as per the layout and as per the standard design. Drawers, ready made keyboard tray and ready made MS CPU stand of heavy duty / high quality in ivory colour is included. The front glass shall be 12 mm thick up to 5 ft. height from the floor level. A 15" wide horizontal side unit consist of 4' long, 16" wide and 30" height made out of 18mm ply and external surfaces 1mm thick with shelve and drawer arrangement along with necessary hardware to be done. Glass of same thickness shall be provided at 3'-6" level. The rate to include for back doors with 'Godrej' night latch. Special locks to be fixed which can opened with single key. Counter top, curved surface top, side unit top should be covered with 6mm thick Corian slid surfaces of DOPONT make Corian sheets. The edges to be neatly covered to look decent and good looking. Cash counter will have Dural make cash closing door (booking counter door closure). Side unit consisting of 4' long, width 16" and height 30" with top two drawers and bottom shelf arrangement to be fixed for each counter. Table and side unit all internal area of the drawers, leg rooms to be finished with 0.8 mm thick half white laminate. (Low height partitions shall be paid for separately). side unit, table should be separatable and laminated all over including leaning side of the partitions.				
	A vertical glass 12mm toughened should be fixed as per the design between the counters on front with suitable beadings/supporting structures. The counters front curved part ply to be done using flexible plywood. One foot rest 100MMX40MM made of teak wood and polished fixed at appropriate location to full length of 3' long. Banks Uniform layout policy scheme to be implemented strictly without any deviation hence the contractors are requested to understand in detail before quoting the rate. (clear inside to side the length of counter shall be measured).				
2	<b>LOW HEIGHT PARTITIONS WITH EDGES COVERED WITH CORIAN BEADINGS</b>	Sqm	28.00		
	Providing and fixing metal stud low hight partitions with following specifications. a) Support system comprising of best locally available make 51x35mm metal studs at 600mm c/c and 51x32mm metal tracks at floor, middle and at 1200mm level with joints staggered. The rate should include necessary strengthening with studs/ tracks or channels at openings. b) 11mm MDF of banks approved brand and variant grade with 1mm laminate as per banks uniform color scheme on both sides. c) 12mm glass of 12" height on top of low height partition (total height to be 4'6" to 5" with necessary CP brass "D" brackets and etching work wherever required also to be fixed. Anti termite solution to be sprayed before using wood in the work. A pin-up board of size about 2'x18" vertical or viceversa to be made on low height partition one side (nearer to sitting stations), with soft board and lenin cloth of superior quality with elegant beading airound, one for each work station. Wicket gate consisting of same construction of low height partitions of approved shade on both sides with all necessary hardware such as hinges, lower bolt etc complete. Each wicket gate must be provided with necessary hardware of CP brass aldop, lower bolt, automatic mortice latch of bank's approved make and model. The edges shall be finished with teak wood beading polished. Its cost to be included in the quoted rate of low height partition.				
3	<b>FULL HEIGHT FULLY GLAZED PARTITIONS:( CM CABIN)</b>	Sqm	24.00		
	Providing & fixing in position 12MM TOUGHENED GLASS with approved brand patch fittings including fixing in position as directed by Engineer-in-charge. Glass should be up to false or roof height (single piece) fixed using Patch Fittings. No wooden or plywood cantles runners to be used for fixing the glass up to false ceiling height. Suitable supporting structure if required may be build with best quality wooden members above false ceiling level. (The rate quoted should be inclusive of this supporting system)				
	The glass to be finished with designer film with elipse design as per the direction of the bank. The designer film is of Harmony/ 3M or equivalent approved make.				

Tanakallu INT-EST

4	<b>FULL HEIGHT PARTLY GLAZED PARTITIONS: CO CABIN</b>	Sqm	25.00		
	Providing & fixing in position metal stud dry wall partition with the following specifications: a)Frame work: Supporting system comprising of best locally available make 51 X 35 X 0.55 mm thick metal studs @ 600 mm c/c and 51 X 32 mm metal tracks at floor, middle, door and ceiling level with joints staggered. The verticals should touch the ceiling with horizontal ceiling channel at slab/beam bottom. The rate should include necessary strengthening with studs / tracks or channel at doors and other openings.b) 11 mm Exterior grade MDF plywood of banks approved brand, fixed on both sides of the framework with 25 mm dry wall screws. c) Finishing: 1 mm laminate on both sides (Banks uniform colour layout colour scheme) up to false ceiling level. d) 6 mm thick clear float glass with etching design as directed between 1200 X 2000 mm level in specified areas fixed with 85 X 15 mm teak wood jamb and 12 X 12 mm teak wood beading.				
	Length x Height up to false ceiling will measured for payment. Plywood area all over to be sprayed with an to termite solution before use in the work.				
5	<b>FULL HEIGHT SOLID PARTITIONS : DOCUMENT ROOM</b>	Sqm	22.00		
	Same as the specification for Full height partly glazed partition but the entire height of partition is to be provided with 11mm exterior grade MDF board/ Cement Fibre board finished with laminate of 1mm thick glossy laminate on both sides.				
6	<b>DOORS IN PARTITION</b>	Sqm	15.00		
	Doors in partitions wherever required as per drawing to be provided with 35 mm thick solid core ISI approved allround teak wood lipping, allround fixed in a concealed door frame of best quality teak wood three sides of sections size of 75x75 mm or as advised by the engineer in charge. Flush door shutters to be fixed with 1 mm laminate (banks uniform layout colour scheme) on both sides and 8 mm clear float glass with etching design as directed with 50 X 15 mm teak wood jamb allround the glass opening and 12 X 12 mm teak wood beading for fixing of glass on both sides including necessary hardware viz: door stopper, door silencer, Door set lock, handles, brass hinges of approved make & quality, melamine spray polish finish to all teak wood members etc. complete as directed.Door Closer of heavy duty 'Godrej' make heavy duty or equivalent to be fixed.				
7	<b>FIRE DOORS- UPS, DOCUMENT AND RECORD ROOMS</b>	Sqm	10.00		
	Supply and installation of 2-hr fire rated doors specifications/criteria as per IS 3614:2021 (Part 2) for UPS room and record room. Certificate for the same to be provided by the company.				
8	<b>PLAIN FALSE CEILING</b>	Sqm	70.00		
	Providing and fixing Concealed Grid suspended ceiling system of 12.5mm La Gyp / Boral Plaster Boards fixed to Frame Work / Rondo / Boral Metal System concealed grid key lock suspended ceiling system consisting of 5mm suspension rod, adjustable spring loaded suspension clip, top cross rail of 3000mm long of 0.55BMT and furring channel 4000mm long made of 0.5mm BMT the top cross rail to be suspended from ceiling at every 1200mm and furring channel to be fixed to top cross rail at every 600mm to make a grid of 1200 x 600m. All the above components are to be made of galvanized steel. The rates to include cut-outs for lighting fixtures / AC grilles / Fire Alarm Detectors etc., along with necessary strengthening and supports for fixing of these. The board joints are to be flush finished with jointing compound and paper tape etc., complete as directed. All legroom internal area and drawer internal area to be finished with 0.8 mm thick half white laminate after spraying anti termite solutions. Rate to be quoted should include charges for dismantling the existing false ceiling neatly and disposing off the unserviceable materials.				
9	<b>GRID TYPE FALSE CEILING (Including e-Corner)</b>	Sqm	220.00		
	<b>SILHOUTE Grid False Ceiling:-</b> Providing and fixing in true horizontal level false ceiling grid system (SILHOUTE) of Armstrong World Industries/ Daikin / CEPro etc. The suspension system shall be silhouette revealed profile grid system with 15mm wide flanges incorporating a 3mm or 6mm central recess colour, black or white revealed. Silhouette main runners and cross tees to have mitered ends with "birds mouth " notches to provide mitered cruciform junctions. Main runners to be spaced at 120mm c/c fixed by using 2mm pre-straightened GI wire. Main tee, rotary stitched of size 15mm x 44mm x 3600mm at every 1200mm c/c maximum and 1200mm cross tee of size 15mm x 44mm x 1200mm at every 600mm c/c maximum and 600mm cross tee of size 15mm x 44mm x 600mm at every 1200mm c/c maximum and 19mm x 19mm x 3000mm wall angle all-round the wall to form grid size of 600mm x 600mm and suspending the grid using 2mm pre-straightened GI wire and 6mm nylon rawl plug at every 1200mm intervals at the main tee and laying of dunne premier micro look mineral fiber tiles manufactured by Armstrong World Industries of size 600mm x 600mm x 15mm over the formed grid etc., complete as directed. Rate to be quoted should include charges for dismantling the existing false ceiling neatly and disposing off the unserviceable materials.				

10	OFFICER TABLES WITH SIDE UNITS WITH CORIAN TOP	EACH	6.00		
	OTHER TABLES (Size 1200 X 750 X 750 mm, with Side table): Providing, making & placing in position executive table and side table with the following specifications: a) Table top and all over /other members to be made in 18/19 mm of banks approved MDF and covered with 6mm thick Corian slid surfaces of DOPONT make Corian sheets. b) One drawer cum shutter unit with necessary hardware viz. drawer channels, handles, locks etc. c) One ready made mobile CPU pedestal, drawer channel, of heavy duty and ivory colour. d) One ready made heavy-duty ivory coloured with channels to be provided e) One foot rest 100MMX40MM made of teak wood and polished fixed at appropriate location to full length of 3' long f) No side table is required. All tables shall have necessary hardware viz., cabinet hinges, handles, locks, tower bolts, etc. and 25 X 40 mm teak wood beading and 20 X 6 mm teak wood lipping etc. g) All the exposed surfaces to have covered with 6mm thick Corian solid surfaces of DOPONT make Corian sheets. With other parts of the cabin of approved shade and brand. 6mm thick lacquered glass for the modesty panel with specified itching with Blue colour with studs. All wooden members to have melamine polish. All internal area of the drawers, leg rooms to be finished with 0.8 mm thick half white laminate. Special locks to be fixed which can opened with single key.				
11	BRANCH MANAGER TABLE WITH SIDE UNITS	EACH	1.00		
	BRANCH MANAGER TABLE (Size 1800 X 900 X 750 mm, Side table 1200X450X750mm): Providing, making & placing in position executive table and side table with the following specifications: a) Table top and all over /other members to be made in 18/19 mm of banks approved MDF and 4 MM OST OF NATURAL TEAK VENEERED PLY, (basic rate shall be Rs 100-120 / sft plus GST shall be selected) all edges to have 20 X 6 mm teak wood lipping. b) One drawer cum shutter unit with necessary hardware viz. drawer channels, handles, locks etc. c) One ready made mobile CPU pedestal, drawer channel, of heavy duty and ivory colour. d) One ready made heavy-duty ivory coloured drawer pedestal unit with channels to be provided e) One foot rest 100MMX40MM made of teak wood and polished fixed at appropriate location to full length of 3' long f) Side table made with 18 mm MDF of banks approved brand and exposed surfaces finished with 4 MM OST OF NATURAL TEAK VENEERED PLY and exposed members with necessary hardware viz., cabinet hinges, handles, locks, tower bolts, etc. and 25 X 40 mm teak wood beading and 20 X 6 mm teak wood lipping etc. g) 6mm thick lacquered glass fixed with cp studs for the modesty panel with specified itching with Blue colour with studs. All wooden members to have melamine polish. All internal area of the drawers, leg rooms to be finished with 0.8 mm thick half white laminate. Special locks to be fixed which can opened with single key. Dismantling and shifting out/away the old tables/side tables in phased manner to be done and its charges to be included in the quoted rate.				
12	STORAGE UNITS: WITH 4MM OST PLY(BM CABIN)	Sqm	5.00		
	Storage Units: WITH 4MM OST PLY(BM CABIN) A) Providing, making and placing in position low height storage units up to 750 mm height or height as directed and 450 mm deep made with 18/19 mm MDF front sides and middle shelf and back side with 9 mm MDF of banks approved brand and variant ply covered with 4 MM OST NATURAL TEAK VENEERD PLY at all exposed surfaces. The top shall have 25 mm MDF Board 'post-formed' edge with pf lamination, Inner/unexposed surfaces to painted with two or more coats of enamel paint with putty finish including melamine polish finish for all wooden members. The rate to include cost of all necessary hardware viz., cabinets hinges, locks, handles, tower bolts etc. The unit should have teak wood beading 25 X 40 mm at top and edge lipping 20 X 6 mm complete. All internal areas to be sprayed with anti termite solution and finished with 0.8 mm thick laminate of half white shade.				
13	SERVICE TABLES FOR HEAVY CASH, CROSS SELING, MESSENGER) WITH OUT SIDE UNIT BUT WITH CORIAN TOP; 1200 MM X 750 MM X750 MM	Sqm	2.00		
	OTHER TABLES (Size 1200 X 750 X 750 mm, with out Side table): Providing, making & placing in position executive table and side table with the following specifications: a) Table top and all over /other members to be made in 18/19 mm of banks approved MDF and covered with 6mm thick Corian slid surfaces of DOPONT make Corian sheets. b) One drawer cum shutter unit with necessary hardware viz. drawer channels, handles, locks etc. c) One ready made mobile CPU pedestal, drawer channel, of heavy duty and ivory colour. d) One ready made heavy-duty ivory coloured with channels to be provided e) One foot rest 100MMX40MM made of teak wood and polished fixed at appropriate location to full length of 3' long f) No side table is required. All tables shall have necessary hardware viz., cabinet hinges, handles, locks, tower bolts, etc. and 25 X 40 mm teak wood beading and 20 X 6 mm teak wood lipping etc. g) All the exposed surfaces to have covered with 6mm thick Corian solid surfaces of DOPONT make Corian sheets. With other parts of the cabin of approved shade and brand. 6mm thick lacquered glass for the modesty panel with specified itching with Blue colour with studs. All wooden members to have melamine polish. All internal area of the drawers, leg rooms to be finished with 0.8 mm thick half white laminate. Special locks to be fixed which can opened with single key. Dismantling and shifting out/away the old tables/side tables in phased manner to be done and its charges to be included in the quoted rate				

Tanakallu INT-EST

14	<b>VOUCHER WRITING TABLE</b>	EACH	1.00		
	<p>Voucher Writing Table:- Supplying &amp; fixing cheque writing table as per the standard design.(1) Floor mounted type-circular type with 12mm toughened glass on top and 8 pigeon hole racks, standing type, top dia 90cm, ht 36"-42" white/blue laminated over 18mm ply work as per banks standard design. (2) Wall mounted type- 3' long, 1' width 6 nos of vouches racks, ht 3'+6', top with 12mm toughened glass as per banks standards with white and blue laminated over 18mm ply wood as per banks standards.(please quote average rate of circular and rectangular type. Ply wood to be MDF of banks approved brand and variant.: 1- circular, 1- wall standing, : TOAL 2 NOS)</p>				
15	<b>TABLE FOR GRAHAK MITRA OR TECH MITRA OR SEVASARATHI</b>	EACH	1.00		
	<p>Table for 'Grahak &amp; Tech. Mitra' :- Providing table for grahak Mitra in curve shape as per the standards. Size 1500X680X750 with a drawer unit. Corian solid surfaces materials 6mm thick (DOPONT) make to be used to cover the front, top and sides instead of laminate.</p>				
16	<b>LOW HEIGHT STORAGE UNITS</b>	Sqm	22.00		
	<p>Storage Units: A) Providing, making and placing in position low height storage units up to 750 mm height or height as directed and 450 mm deep made with 18/19 mm MDF front sides and middle shelf and back side with 9 mm MDF of banks approved brand and variant ply covered with 6 MM THICK CORIAN SOLID SURFACES (dark for bands and light for body) at all exposed surfaces. The top shall have 25 mm mdf board 'post-formed' edge with pf lamination, Inner/unexposed surfaces to painted with two or more coats of enamel paint with putty finish including melamine polish finish for all wooden members. The rate to include cost of all necessary hardware viz., cabinets hinges, locks, handles, tower bolts etc. The unit should have teak wood beading 25 X 40 mm at top and edge lipping 20 X 6 mm complete. All internal areas to be sprayed with anti termite solution and finished with 0.8 mm thick laminate of half white shade. STORAGES SHOULD NOT BE FIXED TO WALLS/FLOORS AND TO BE PLACEABLE ANY WHERE ELSE SO, LENGTH TO BE DONE NOT EXCEEDING 5' EACH.</p>				
17	<b>COLUMN / WALL PANELLING</b>	Sqm	260.00		
	<p>Wall Panelling with ply and 1mm laminate: Providing &amp; fixing metal stud wall panelling with the following specification: a) Supporting system comprising of best locally available make 51 X 35 X 0.55 mm thick metal studs @ 600 mm c/c and 51 X 32 mm metal tracks at floor, middle, door level and ceiling level with joints staggered. The verticals should touch the ceiling with horizontal ceiling channel at slab/beam bottom. b) 11 mm MDF panels fixed on one side with 25 mm dry wall screws for the entire height of panelling. c) 1 mm laminate (dark for bands, light for body, in designs) up to false ceiling level. e) All teak wood members to have melamine polish finish. Length X height up to false ceiling will be measured for payment. plywood to be used in the work to be sprayed with anti termite solution. banks uniform layout policy colour scheme to be followed. Aspecail panel of size about 8' long and 5' height to be made consisting of allround boarder 6" width and 3" projected from wall blue laminated, internal panel area plane while laminted, a SBI LOGO blue laminate of 3' dia projected 3" above and a write up of 'BANK TO EVERY INDIAN' as big size as possible with in the panel with vinyl cut/flex etc as directed by the engineer in charge. The extra costs of th same to be added in the quoted rate. Wall panelling should not be done behind the side units, back units, sides of tables if leaning against walls, since will not be paid.</p>				
18	<b>CM CABIN PANELLING</b>	Sqm	21.00		
	<p>Same as the specification as above but use 4mm thick veneered ply. Design shall be as directed by the bank.</p>				
19	<b>TOUGHENED GLASS DOOR</b>	Sq.m	14.00		
	<p>PROVIDING AND FIXNG 12MM THICK TOUGHENED GLASS FOR BM CABIN DOOR, MAIN ENTRANCE DOORS AND ATM AS PER BANKS STANDARD SPECIFICATIONS</p>				
	<p>Providing and fixing in position frameless glass door shutter made using 12mm thick toughened float glass fixed with necessary patch fittings including cutting, making holes, cut-outs in the glass of required shape and size to accommodate fittings and fixing the fittings in the floors, soffits, jams including necessary fixtures, screws, sealant wherever required and SS cover over patch fittings. Include necessary etching film/LOGO patch fitting locking systems, 1 pair of 600mm long SS(SS 304) handles of approved make, floor springs and any necessary hardware items. Top Pivot- PT 24, Top Patch Fittings- PT 20, Bottom Patch fittings- PT 10, Floor Spring- BTS 75 V, Corner lock with strike plate and Euro Profile Cylinder- US 10, Handle- TG 9300 EQ- S 25mm diameter x 300mm length Mode of Measurement: Door opening size shall be Good to its original position including all necessary Patch fittings of approved make and fixtures &amp; hardwares. All complete as directed by bank.</p>				

20	<b>DINING TABLE</b>	EACH	1.00		
	Supply and installation of Dining table of size 6'-0" length and 3' width & 2'-6" height made of 18mm thick HDHMR Board for top & finished with 1mm thick decorative laminate. The top to be supported by 3" x 3" paint quality TW frames on four sides with TW frame work of size 3" x 1½" connecting them at the top and bottom. The frames to be finished with 2 coats of approved colour of synthetic enamel paint over a primer coat.				
21	<b>ROLLER BLINDS VISTA MAKE SCREEN WHITE 111 SHADE )</b>	Sqm	31.00		
	Roller Blinds:- Supplying & fixing in position of Roller Blinds of "Vista" shade model- screen white 111 model etc. complete. Window opening sizes shall be measured and the blind must extend up to 3" beyond the edges of opening on all the four sides. SBI LOGO AS PER BANKS STANDARD SPECIFICATION TO BE PRINTED AS DIRECTED.				
22	<b>SUGGESTION BOX</b>	EACH	1.00		
	Suggestion box as per banks standard size, model in blue/ green laminate with locking arrangement.				
23	<b>SHOWCASE BOXING</b>	NOS	2.00		
	Providing and fixing Showcase Boxing to detail (app. Size 1'6"x6"x1'6"), 18mm thick HDHMR Board finished with 1mm laminate of approved colour and shade with necessary grooves and beading, 3 nos of intermediate Glass shelves with D brackets				
24	<b>ACP WORK WITH 3MM THICK AND FRAME WORK</b>	Sqm	30.00		
	ACP CLADDING WORKS: Providing and fixing ACP cladding white or Blue suiting to Banks uniform colour policy including fixing with suitable frame etc complete of standard quality and brand. Cost of Logo to be included wherever required. 3mm thick ACP sheets of banks approved quality and brand with supporting aluminium sections of 1.0MM thick banks approved aluminium partitions to be fixed at 3' center to centre and vertically and horizontally and suitably covering the edges. The work must include fixing a 3" thick embossed SBI LOGO of banks standard dimensions in a box frame as directed				
25	<b>PAINTING</b>				
	Providing and applying Synthetic Enamel Paint on doors / windows frame, shutters, railing, grills, gates etc. in two or more coat of approved brand and shade including a priming coat as per manufacturers' specifications, after necessary preparation of surface with scrapping, sand paper rubbing, applying putty, including necessary scaffolding etc. complete as directed by the Engineer-in charge. Paint: Asian, Nerolac, Berger, Dulux	Sqm	200.00		
26	<b>BUY BACK</b>	LS	-1.00		
	Buy back of old furnitures and partitions in the existing premises. Dismantling existing SWC counter along with partitions, Labels, Storage, Partition, False ceiling, blinds, wall paneling, . etc complete and removing all the debris away from the site or stacking as directed by the Bank. While removing and stacking at site care to be taken not to cause damages to floors, walls and dismantling items. Dismantling to be done as advised by the bank.				
	<b>e-CORNER WORKS</b>				
27	<b>FIXED GLAZING</b>				
	Providing & Fixing 12 mm thk. Toughened Clear Glass partition on aluminium "C" channel of 25x25x1mm size with Silicon Sealant filling as approved, including making groove of 25 mm x 25mm in floor with floor cutting machine, fixing aluminium "C" channel in the groove with suitable screws and fasteners and work to be completed as directed by Bank	Sq.m	11.00		
28	<b>SOLID PARTITION WITH DOOR -ONE SIDE ACP &amp; ONE SIDE BISON BOARD</b>				
	Supporting system comprising of 51mm / 50mm x 35mm / 34mm x 0.5mm metal studs at 600mm c/c and 51mm / 50mm x 32mm x 0.5mm metal tracks at floor, middle, door and ceiling level with joints staggered to avoid through joints. The vertical members should touch the ceiling with horizontal ceiling channel at slab / beam bottom. The rate should also include necessary strengthening with studs / tracks or channels at doors and other openings. 10mm Bison Board fixed on one side & other side 3mm thick ACP side with 25mm dry wall screws for the entire height of the partition. Partition to have Finished with painting or laminations on one side as per availability. The partition also to have a solid door shutter fixed with ACP and necessary hardware. The other side of the partition need be finished.	Sq m	8.00		

## Tanakallu INT-EST

<b>29</b>	<b>WALL PANELLING</b>				
	Providing & fixing in position 3mm thick Fire Resistant Interior Grade Aluminium Composite Panel (ACP) with framing of Aluminium hollow sections of min 38mm x 25.4mm and 0.81mm @ 600mm c/c bothways. ACP to be in 600mm wide panels or distributed equally. Panels to be fixed to the frame with 3M or equivalent adhesive. Joints to be finished with Silicone based sealant. Aluminium foil thickness to be min. 0.20 mm on both sides. Sunrise Silver Metallic 600 of Alucobond or equivalent from Alstrong or ISI certified or approved brands to be used. Additional sections to be provided to fix the Indoor AC units. ACP wall panelling should follow Ink Blue{ L481-105899/RGB: 40 0 113/ HEX: #280071/ CMYK: 97 100 0 25} of Alucobond or equivalent from Alstrong to be used.	Sq.m	21.00		
<b>30</b>	<b>ROLLING SHUTTER BOX</b>				
	Supplying and fixing Rolling Shutter box of aluminium composite cladding with skin material 0.5 mm thick aluminium sheet cover material natural polyethylene aluminium cladding panel fixed with extruded aluminium basis frame (50x25x1.5mm), plywood boardsangle cleats, weather sealants, rivets, GI brackets all as approved, using suitable bolts on structural steel work including necessary accessories complete in all respects including all labour charges, scaffolding, tools and plants etc., complete for finished item of work , if any. ACP Cladding - 3 mm thick.	Sq.m	10.00		
<b>31</b>	<b>DOOR CREATIVES</b>				
	Providing and fixing See Through artwork on the fixed glasses & doors as per the instruction of the bank.	Sq.m	13.00		
<b>32</b>	<b>SANDWITCH ACRYLIC DISPLAY BOARDS</b>				
	Providing and fixing sandwich acrylic display boards with SS studs of size 900mm x 1200 mm	Nos.	2.00		
<b>33</b>	<b>EXTERNAL SIGNAGE</b>				
	Providing Acrylic backlit SBI Logo, letter height shall be 1.5 feet as per the direction of the Bank	Nos.	1.00		
<b>34</b>	<b>TOUGHENED GLASS DIVIDERS FOR E-CORNER:</b>				
	Providing and fixing in position 8mm toughened lacquered glass (colour - blue) for glass partition. The work to include making necessary template for all the glasses and then cutting the glass to correct size, making all the necessary holes, cuts etc., and then toughening the same. The cost to include all hardware required viz., single corner patch, bracket etc., The approximate size of each glass will be 1950mm x 450mm to 1200mm as per site conditions. The rate is for a finished item of work etc., complete as directed.	Sq.m	5		
<b>TOTAL( EXCLUDING GST)</b>					
Note: GST applicable will be paid extra					