

PRICE BID FOR SITC OF AIR CONDITIONING WORK AT SBI VOTF AT JAMMU					
S.No	Description	Quantity	Units	Rate (in INR)	Amount (in INR)
1	Supply, erection, testing and commissioning of <b>2TR 3 star ceiling Mounted Cassette AC</b> units with cordless remote complete with all necessary wiring duly insulated with 9mm thickness Nitrite rubber pipe insulation with (evaporate coil-copper only_ fan and fan motor, machine control panel improved refrigerant joints. Air conditioners shall be fitted with hermetically sealed type suction reciprocating or discharge cooled rotary compressor or scroll compressor, compressor unit operating on R32. All complete as per drawing and Instructions of the Engineer in-charge/employer ( rates are to be inclusive of copper refrigerant pipe and supply cable with insulation and drain pipe up to 3mtr. Length) Copper only ( <b>Make : Hitachi/Daikin/Carrier/Blue Star/Godrej</b> ). Warrenty : one year from the date of installation alongwith Compressor warrenty 5 years	2	no.		
2	Supply, erection, testing and commissioning of <b>1.5 TR 5 star Inverter Wall Mounted AC</b> units with cordless remote complete with all necessary wiring duly insulated with 9mm thickness Nitrite rubber pipe insulation with (evaporate coil-copper only_ fan and fan motor, machine control panel improved refrigerant joints. Air conditioners shall be fitted with hermetically sealed type suction reciprocating or discharge cooled rotary compressor or scroll compressor, compressor unit operating on R32. All complete as per drawing and Instructions of the Engineer in-charge/employer ( rates are to be inclusive of copper refrigerant pipe and supply cable with insulation and drain pipe up to 3mtr. Length) Copper only ( <b>Make : Hitachi/Daikin/Carrier//Blue Star/Godrej</b> ). Warrenty : one year from the date of installation along with Compressor warranty 5 years	11	no.		
3	S.I.T.C. of L shape / suitable shape M.S. Frame stand for mounting Outdoor Units on wall / On floor with all fixing hardware Within above Cat walk for cassette & split A.c.'s. Complete as required	13	no.		
4	Providing and fixing 5KVA Stabilizer (copper winding) input voltage range of 170-270V and output to be 230V Make : <b>Everest/V-guard/Microtek</b> )	2	no.		
5	Providing and fixing 4KVA Stabilizer (copper winding) input voltage range of 170-270V and output to be 230V Make : <b>Everest/V-guard/Microtek</b> )	11	no.		
	<b>Total</b>				
	<b>GST extra as per applicable</b>				

**Note: Warranty certificates must be submitted along with bills.**

**Stamp and signature of the Firm/Agency/Dealer**