

Sl.No.	Description	UOM	Qty.
Part A:			
1	Supply of inverter type Cassette and Hi-wall mounted split type air conditioner units indoor & outdoor complete with cordless remote control, of required capacity. Only 5 star rating		
a	3.0 TR capacity Cassette type	Set	7
b	2.0 TR capacity HWM type	Set	6
c	1.5 TR capacity HWM type	Set	4
	Sub Total Part A		
Part B:			
1	Installation, testing and commissioning of Cassette and hi wall mounted split type air conditioner units indoor & outdoor complete with in all aspects of required capacity.		
a	3 TR capacity Cassette type	Set	7
b	1.5, 2 TR capacity HWM type	Set	10
2	Supply and erection of suitable size of MS stand for outdoor units	Set	17
3	Supply , installation ,testing and commissioning of Softdrawn copper piping with 9 mm thick Nitrile rubber insulation including all necessary fittings between indoor and out door air cooled condensers of the following sizes		
a	Suction line & liquid line for Cassette units	RM	140
b	Suction line & liquid line for hi-wall mounted units	RM	90
4	Drain line from indoor to outdoor machines as per standards	RM	250
5	Supply, laying, testing and commissioning of flexible cable of suitable size for		
a	Cassette units	RM	140
b	HWM units	RM	90
6	Supply, installation,testing and commissioning of timer for AC units of ATM	Set	1
	Sub Total Part B		
	Grand Total (Part A + Part B)		