

BOQ FOR THE PROPOSED WORKS OF RENOVATION/INTERIOR/FURNISHING OF BRANCH FOR STATE BANK OF INDIA (WITHOUT ATM)					
	BRANCH DETAIL:		KARAH I BRANCH, RBO KHANDWA (M.P.)		
S.N.	Description of Item	Unit	Quantity	Rate	Amount (Rs.)
INTERIOR FURNISHING WORKS					
A	Flooring, False Ceiling and Coves				
1	Gypsum Board False Ceiling	sqM	130.00		
	Providing, and fixing Gypsum Board False Ceiling straight or curve any profile of reputed make which includes G.I. Perimeter Channels of size 0.55mm thick (having One Flange of 20mm and another flange of 30mm & a web of 27mm) along with perimeter of ceiling, screw fixed to brick wall / partition with the help of Nylon sleeves and screws at 610mm centres. Then suspending G.I. intermediate channels of size 45mm (0.9mm thick with two flanges of 15mm each) from the soffit at 900mm centres with ceiling angle of width 25mm X 10mm X 0.55mm thick fixed to soffit with G.I. cleat and steel expansion fasteners. Ceiling section of 0.55mm thick having knurled web of 51.5mm & two flanges of 26mm each with lips of 10.5mm are then fixed to the intermediate channel with the help of connecting clips and in direction perpendicular to the intermediate channel at 457 mm centres.				
2	Mineral Fibre Acoustic Ceiling Tiles :	Sq.M	115.00		
	Providing, making & Fixing at all heights & in spirit level, Acoustical Ceiling System @ Office areas with Armstrong make mineral fibre acoustical suspended ceiling system as per Manufacturer's specification with pin-hole tiles, tegular edge with 24 mm exposed grid. The tiles should have Colour White, in module size of 600mm x 600mm x 15mm. with providing and fixing Hot dipped galvanized Steel suspension system Grid frame with butterfly clips, for laying of Acoustical Ceiling Tiles as per manufacturer's specifications. The grid should be laid on Armstrong/Gyproc stitched True lock 24 TL exposed grid systems with 24 mm wide T-section flanges color white, the tile will be laid on frame work made of Armstrong Prelude 32 with 24 mm wide T - section flanges or of equivalent make, colour white having rotary stitching on all T sections i.e. the Main Runner, 1200 mm & 600 mm Cross Tees with a web height of 32 mm and 27mm ,25 mm respectively. The cost shall include proper installation and provisioning etc. The work is to be completed as per manufacturer's specification. (Make: Armstrong / Diamond / USG Boral)				
3	Same as above but providing, making and fixing Gypsum cove (inside height 150 - 200 mm and border 75 mm) to hide strip/cove light in ceiling or to act as pelmet for roller blinds on windows or for projector screen, etc.	RMt.	118.00		
4	Panelling	Sq.M	58.00		
	Providing and fixing panelling on walls front facia, and, columns at various parts of the premises as required with framework of 50 mm X 25 mm - 18 gauge section anodised Aluminium (as per requirement) frame work @ 16" to 24" c/c for levelling and 10 mm thick commercial ply of approved makes, and/or limited use of 6mm Flexible ply for panelling of circular columns etc. including fixing as per pattern and style as directed, fixed vertically and horizontally 600 mm c/c or less as per site condition finished with 1mm thick decorative laminate of approved made and shade (in one or multi colour) shall be fixed with proper adhesive as directed. Top of the paneling / edges is to be provided lamination or with teak wood decorative beading of 50mm x 20 mm finished with polish/painting as directed.(Make: Archid / Century/ Green Ply)(The test certificate from the manufacture for all the plywood/board/laminate/mica shall be subbmited at the time of dilivry at the site address needs to be included)				
5	Full Height Partly Glazed Partly Wooden Double Skin Plywood Partitions :	Sq.M	18.00		

	BRANCH DETAIL:		KARAH I BRANCH, RBO KHANDWA (M.P.)			
S.N.	Description of Item	Unit	Quantity	Rate	Amount (Rs.)	
INTERIOR FURNISHING WORKS						
	Providing, fabricating, supplying and fixing full height partly glazed and partly wooden double-skin plywood partition up to ceiling/top support, complete in all respects, strictly as per approved drawings, specifications and instructions of the architect/Bank's Engineer. The partition shall comprise the following:					
(a)	Framework: Internal framework made of aluminium box section 50 mm x 50 mmx1.60 mm thick, weighing not less than 0.836 Kg per running meter, fixed both horizontally and vertically at a maximum spacing of 450 mm c/c, securely anchored to floor/slab/seiling using approved fasteners (65-75 mm long) and including all necessary grooves, cut-outs and supports nas per site conditions.					
(b)	Penelling: Double-skin construction on both sides using 9 mm thick ISI-marked commercial plywood (approved makes: Century/Archid/Green ply), treated with anti-termite chemical prior to fixing. Finished with 1.00 mm thick decorative laminate of approved makes, shade and texture on both sides, matching the approved panel layout.					
(c)	Glazing: Providng and fixing 8 mm thick clear float glass at 900-1200 mm above finished floor level, fixed with polished teak wood beading on both sides. Glass shall be etched as per approved design (or film etching rate inclusive). Beading shall be fixed projecting neatly from the partition surface.					
(d)	Top & Side panels: Panel above glazing and side panels made from 9 mm thick commercial plywood, finished with 1.0 mm thick laminate of approved makes and shade.					
(e)	Skirting: Providn and fixing 75-150 mm high skirting made from 9 mm thick commercial plywood, finished with 1.0 mm thick laminate of approved make and shade.					
(f)	Door frame provision: Providng and fixing seasoned teak wood door frame with rebate, finished section size 75 mm x 20 mm, complete as per approved architectural drawings and site requirement.					
(g)	Service provision: Making all necessary provisions for soft boards, white boards, electrical points, switchboards, telephone/data cabling, etc including required support and cut-outs, complete.					
(h)	Finishing: Applying minium two coats of approved matching shade melamine polish to all exposed wooden edges, door openings, cut-out and trims. All wooden members shall be treated with anti-termite/borer-resistant treatment. Workmanship shall be of superior qulity and strictly as per approved details.					
(i)	Rate shall include: Cost of all materials, labour, tool, plants, hardware, fasteners, transportation, hndling, installation at all heights nd locations, lead, lift, wastage, statutory taxes, duties, royalites, and all incidental works required to complete the item in all respects.					
6	Low Height partitions With / Without Glass :	Sq.M	25.00			
	Providing, fabricating, supplying and fixing low-height partly glazed or or non-glazed double-skin plywood partitions, complete in all respects, in accordance with approved drawings, specifications and instructions of the architect/Bank's Engineer.					

	BRANCH DETAIL:		KARAH I BRANCH, RBO KHANDWA (M.P.)		
S.N.	Description of Item	Unit	Quantity	Rate	Amount (Rs.)
INTERIOR FURNISHING WORKS					
	Framework: The partition framework shall be fabricated from aluminium box section of size 50 mm x 50 mm x 1.60 mm thick, having a minimum weight of 0.836 Kg per running metre. The framework shall be fixed both horizontally and vertically at a maximum spacing of 450 mm c/c, or as directed by the Architect/Bank's Engineer. The framework shall be firmly anchored to the floor or slab using approved 65-75 mm long screws/fasteners, ensuring proper alignment, rigidity, and stability. All necessary grooves, cut-outs, and adjustments required to suit site conditions shall be included.				
	The partition shall be double-skin construction, sandwiched on both sides with 8.0 mm thick commercial ply of approved makes. All wooden members shall be treated with anti-termite chemical prior to fixing. Both face of the partition shall be finished with 1.0 mm thick decorative laminate of approved makes, shade, and texture, matching the approved panelling pattern. All exposed border and edges shall be neatly finished with matching laminate or lipping, as specified.				
	Glazing: Where glass is specified, the partition shall be provided with glazed panels as per approved drawings. Glass shall be etched/filmed as per approved design.				
	An additional aluminium section of size 50 mm x 50 mm shall be provided at 700 mm above finished floor level for fixing work tables or other fixtures, wherever required. Additional wooden members shall be provided at door locations or wherever necessary to ensure proper fixing of shutters, hardware, or accessories. The finish surface shall be uniform, true to line, level, and free from defects.				
	Rate shall include: Cost of all materials, labour, tool, plants, hardware, fasteners, transportation, handling, installation at all heights and locations, lead, lift, wastage, statutory taxes, duties, royalties, and all incidental works required to complete the item in all respects.				
7	ACP Panelling in ATM room & exteriors and Shutter boxing with trap door:	Sq.M	30.50		
	Providing and fixing in position Aluminium Composite Panel (ACP) on wall, boxing, shutter panelling with framing of M.S. Tube sections of min. 50 mm x 25 mm and 16 gauge, (OR Aluminium tubular section of same sectional dimensions if required) of good quality, fixed/ fabricated @ 600 mm c/c or less as per site requirement or members recommended by the manufacturer and in accordance with the specifications and recommendations of the manufacturer. The structure shall be fitted in place on walls/ beams/ columns/ ceilings/ MS fabricated structures etc. as instructed using recommended fixing method, with 3M or equivalent adhesive and with mirror screws, joints to be finished with silicon based sealant, ..contd..				
	ACP to be in 600 mm width panels or distributed equally. it shall be of thickness of 3 mm. minimum. Alubond/ Eurobond/ Fujibond/ Alcobond or equivalent ISI brands to be used. Bright silver/ shaden to be as per bank's approval. Additional sections to be provided to fix the indoor AC units. The AC units to be installed near the machine area at the highest position. Shutter Trap door will be of 12 mm MR ply finished with ACP. The cost shall include all scaffoldings, chase making, lifting, cutting, on site adjustments, plaster repairing, etc. complete.				
8	FULL AND LOW HEIGHT STORAGES	Sq.M	19.80		

	BRANCH DETAIL:	KARAH I BRANCH, RBO KHANDWA (M.P.)			
S.N.	Description of Item	Unit	Quantity	Rate	Amount (Rs.)
INTERIOR FURNISHING WORKS					
	Providing, making and placing in position storage cabinets and/or runners from 350 mm to 500 mm depth, height of 750 to 900 and length as per site requirement, and 18 mm commercial plywood construction with 6mm thk. commercial plywood backing complete. It shall have 2 no. of 125 mm deep drawers, equal size (min. 400 mm) wide on upper side and below to drawers, the cupboard unit shall be with openable shutter & adjustable shelf all along the full width of the credenza. All drawers shall be fitted with telescopic channels and locking arrangement and cupboards shall have locking arrangement and all exposed edges of plywood shall be fitted with 1mm thick lamination / PVC beading . shall have polish/painted of matching color.				
	..contd.. middle made of 18 mm commercial plywood with teak wood lipping with melamine polish on exposed edges duly polished. Two equal side hung shutters of 18 mm th commercial plywood with PVC tape of size 2mm on all edges for each compartment. .. contd..				
	.. contd .. No vertical edge of the storage units should be left sharp. The rate to include for necessary hardware fittings (all SS brush finish) like shutters will be on ebco self closing hinges and drawers shall be on ebco plain slides, SS handle to drawers & shutters, one no. of brass magnetic ball catcher for each shutter, one no. 75 mm long SS tower bolt to relevant shutter and one "Godrej" made lock for each compartment & drawers with common key, etc. complete. All the edges of the plywood in contact with floor also to be provided with teak wood lipping of size 20 x 6 mm. Nylon Buffers of suitable size to be provided under the storage units fixed with screws, wherever required.(Measurement area = Length x Height).(Make: Archid / Century / -) (The test certificate from the manufacture for all the plywood/board/laminate/mica shall be subbmited at the time of dilivery at the site address needs to be included)				
9	Side Credenza :	Sq.M	9		
	Providing and fabrication of 2'-6" high and 1'-3" wide side cabinet with cabinet body of 18mm and back 6 mm thick commerical plywood. The drawer shall be made with 12mm & 6mm thick plywood. The door of cabinet to be fixed with EBCO hinges. Drawer shall be mde from 12mm and back shall be made from 6mm ply. All the external exposed surfaces of the cabinet must be covered with 1mm thick laminate of approved brand and shade of Formica or equivalent All the internal / hidden surfaces to be finished with 0.6 mm thick backer lamination. All the edges/ corners of the plywood must be protected with 6 mm thick plain teak wood lipping. Multipurpose lock and handle to be fixed to shutters and. (Measurement area = Length x Height).(Make: Archid / Century / Green ply)				
10	Cabinet with openable shutter around the electric panel	Sq.M	5.04		
	Providing, making and placing in position cabinet with openable shutter around the electric panel. Cabinet and shutter made of 18mm thk commercial plywood. All visible surfaces shall be laminated with 1 mm thick Laminate on external surfaces of approved made and shades and the internal surfaces finsiehed with 8 mm thick bison panel cement-bounded prticle board, including providing teakwood lipping of size 20 x 6 mm on edges. Horizontal slots (approx. 10 mm wide) to be cut in the shutter at top & bottom for ventilation. Rate to include for necessary hardware fixture like providing with 3 nos. of 75mm long SS hinges for each shutter, two nos of 75 mm tower bolt (one top and bottom), SS handles to shutters, magnetic catchers for each shutter and multipurpose Godrej or ebco lock. (Measurement area = Measurement to be taken for the front surface area of the cabinet).				
11	TABLES AND COUNTERS				

	BRANCH DETAIL:		KARAH I BRANCH, RBO KHANDWA (M.P.)			
S.N.	Description of Item	Unit	Quantity	Rate	Amount (Rs.)	
INTERIOR FURNISHING WORKS						
	(a) Providing and fixing at site Officer's table made of 18 mm th. commercial ply with 1mm thick laminate of desired shade, design and gloss on outer visible surfaces; single color on horizontal surface & two color on vertical surfaces. . The front of the table top shall be projected and curved as per drawing. Provision for 3" dia. Round/3" square stainless steel of grade 304 cable manager for computer / electrical cables at appropriate place, will be made in the top surface of the table. Esteem Biege wood lipping will be provided on all the edges of the table, including bottom touching the floor and the drawers.					
	The counter shall have a wooden keyboard rest of size 600mm x 270mm made with 19mm ply fixed with sliding telescopic channels of ebco/godrej/hettich make. The work shall also include provision of foot rest made with wooden member of section 3" x 5" along the leg space.					
	(b) There shall be provision of one storage cabinet 1'3" wide. The frame shall be made with 19mm thick commercial board. The cabinet shall have one lockable drawer running on side mounting drawer slides (channels) of EBCO make & one cupboard with shutter beneath the drawer, made of 19mm thick commercial ply with 1mm thick laminate of desired shade, design and gloss on front face, handle / knob and magnetic catcher shall be provided on one side of the table as per layout. The sides of the drawer shall be made of 12mm thick plywood, bottom of 6mm thick plywood & front of 19mm thick block board.					
	All other surfaces i.e. inside / legsapce of table, inside of drawer / cupboard shall be provided with 0.8mm thick laminate of desired shade/design and gloss, and wood lipping / beading shall be PU polished with matching pigment/deco painted in desired colour. The table shall have a CPU ledge made of 19mm thick block board on one side, complete as per drawing.					
(a)	B.M.'s Table : 1.80m x 0.90 m x 0.75 m ht.	Nos	1.00			
(b)	Officer Tables : 1.50 m x 0.75 m x 0.75 m ht.	Nos	5.00			
(c)	ASSISTANTS, CLERICAL/OTHER Staff (Associated Business/SBI Life Counters) Tables: 1.20 x 0.60x0.75 m ht	Nos	1.00			
12	Single Window Operator Counters :	RMt.	7.50			
	(a) Providing and fixing at site SWO counters as per the new design and drawings. SWO counters to be made of 18 mm thick commercial ply with 1mm thick laminate of desired shade, design and gloss on outer visible surfaces; single color on horizontal surface & two colors on vertical surfaces. The counter shall have a curved front made with flexible 19 mm thick ply and provision of kobe lighting as per the drawings. Provision for 3" dia. Round /3" square stainless steel of grade 304 cable manager for computer / electrical cables at appropriate place, will be made in the top surface of the counter. Teak wood lipping will be provided on all the remaining edges of the counter, including bottom touching the floor and the drawers.The counter shall have wooden keyboard rest of size 600mmx 270mm fixed on sliding telescopic channels of ebco/hettich/godrej. The work shall also include provision of foot rest made with wooden member of section 3" x 5" along the leg space.					

	BRANCH DETAIL:	KARAH I BRANCH, RBO KHANDWA (M.P.)			
S.N.	Description of Item	Unit	Quantity	Rate	Amount (Rs.)
INTERIOR FURNISHING WORKS					
	(b) The counters shall have three self lockable drawers running on side mounting drawer slides (channels) of EBCO/godrej/Hettich make, made of 19mm thick commercial ply with 1mm thick laminate of desired shade, design and gloss on front face & 3 nos. self locking drawer locks be provided on one side of the counter as per layout. The sides of the drawers shall be made of 12mm thick plywood, bottom of 6mm thick plywood & front of 19 mm thick block board. All other surfaces i.e. inside / legsapce of table, inside of drawer/Cupboard shall be provided with 0.8mm thick laminate of desired shade, design and gloss, and wood lipping / beading shall be PU polished with matching pigment/deco painted in desired colour. The drawers shall have partitions for keeping currency notes as per drawing, complete in all respects including the required stainless steel hardware like handles, hinges etc.The counter shall have a CPU ledge made of 19mm thick commercial block board on one side, complete as per drawing.				
13	Grahak Mitra Counters :	Nos	1.00		
	Providing & placing Grahak Mitra approx size 1.65mx0.8-0.9mx0.9-0.75m excluding runner in 18mm commericla ply with C.P.U. space, single drawer and cabinet below as per design and drawing. The Design shall carry arch shape and matching elements which shall be made using 3 nos 6mm thick flexible ply of approved brand, bonded together with synthetic adhesives like fevicol etc. using ply formwork, jigs and fixtures (cost included in the quote). The table edges shall be double thick and all visible surfaces including table tops facia of drawers and outside of shutters etc. shall be finished with 1 mm thick SF/Textured Laminate (up to Rs.650/- per sq.mt.) as directed, the bottom and inside of table shall be finished with 1mm thick laminate of approved make, colour and design and all hidden areas like inside of drawers, cabinets, finished with economical laminate. Cost shall include providing and fixing Computer keyboard trays (Powdercoated MS) EBCO make or equivalent as per approval with keyboard and sliding mouse tray attachment in colour as per approval under worktops as and where instructed. The cost shall be complete with lippings, mouldings, telescopic drawer channels, accessories, hinges etc as per specifications.				
14	Wall Mounted Writing desk :	Nos	1.00		
	Providing & placing Wall Mounted Writing desk in 18mm ply construction as per design and drawing. The table top shall be in 12 mm thick glass.The table edges shall be double thick and all visible surfaces shall be finished with 1 mm thick SF/Textured Laminate (up to Rs.650/- per sq.mt.) as directed, of approved make, colour and design as directed.				
15	CORIAN	sqM	0.00		
	Providing and fixing solid, non-porous, homogenous surfacing of 12 MM Thick Dupont Corian or equivalent upon approval on curved or plain Ply framework/ structures/Bench/ table tops/ modesty panels etc. in required design/ pattern/ shape/ size etc. and including provision for backlighting to be fitted as per the instructions of the architect and manufacturer's specifications and by trained personnel so as to achieve buffed, smooth, seamless, joint-free surface upto the architect's satisfaction.				
16	12 MM TOUGHENED GLASS	sqM	4.50		

	BRANCH DETAIL:	KARAH I BRANCH, RBO KHANDWA (M.P.)			
S.N.	Description of Item	Unit	Quantity	Rate	Amount (Rs.)
INTERIOR FURNISHING WORKS					
	Providing and fixing 12 mm thk TOUGHENED fixed glass for glazing at entrances etc. and half height partitions of Single Window Counters (of approximate size 1450mm x 400mm - 100mm cut and edge polished in curvilinear/tapered shape) fitted with suitable SS Patch Fittings of reputed makes and size as demarcated and adjoining the doors etc and/or as required. The glazing shall be of 12 mm thk. clear float glass, cut to size/shape etc. as directed, edge polished and TOUGHENED, fixed as per SS Fitting manufacturer's recommendations and specifications, fixed to walls, granite pattas, furnitures, adjoining doors or wooden frames/ partitions, panellings etc. as required, The fittings shall be in approved finish. Rates shall take into consideration all aspects like edge polishing, hole making, toughening, supply of S S Patches, transportation, handling, lifting etc. complete upto installation.				
17	12 MM FIXED GLASS	sqM	6.75		
	Providing and fixing 12 mm thk fixed glass for glazing/ Partition / Glass on Transaction side of Single Window Operator Counters of size as demarcated and adjoining the partitions/doors etc and/or as required made out of 12 mm thk. clear float glass, edge polished fixed in grooves, ply framework with wooden lippings and/or wooden top and bottom rails adjoining doors or wooden frames/ partitions with wooden ribs etc. and/or jointed to other glasses with UV setting glass adhesive as required. Cost shall include provision of Lamination of glass with etching film of sticker type as per the architects designs where required.				
18	8 MM FIXED GLASS	sqM	7.50		
	Providing and fixing 8 mm thick clear float glass of reputed brands like Modi, Saint Gobain or equivalent upon approval on Table Tops and glazings, glass shutters in displays, glazed doors, etc. except in the double skin partitions as instructed of size as instructed, made out of edge polished glass fixed from top and bottom in ply partitions or all four sides inside partitions or shutters with tw beadings of design as per approval as instructed on the top and bottom partitions not including cost of beadings/ PU polish of beadings/ d-buttons etc.				
19	12MM TOUGHENED GLASS DOOR	Sq.M	6.60		
	Providing and fixing 12mm thk Toughened Glass Doors of any size at Entrances/ Conference room/ Cabins etc. single or a set of two where required , and of size as demarcated, swing type door openable both sides made out of 12 mm thk. clear toughened float glass, edge polished fixed in SS patch fittings of Dorma or equivalent patch fittings as per the manufacturers recommended process and methods, of approved finish and as per the placement in drawings and specifications fixed on Everite/ozone/ Hardwyn/ Dorma or equivalent floor springs and provision of approved locking system, one set of 25mm dia S. S. brush finish pull handles as per approval complete Including providing "PUSH" * "PULL" sticker lables of approved design & make. Each door shutter shall be treated individually with complete set of accessories to be provided on each door, measurement shall be done of the opening in Sq.M.				
20	FIRE RATED DOOR	Sq.M	1.90		
	Supply, installation, testing, and commissioning of a BIS-certified fire-rated steel doorset of approx. 0.9mx2.1m size or as per site for the Electrical and UPS Room, conforming to IS 3614:2021 (fire doors and doorsets specification) and fire resistance tested as per IS 3614-2:1992 for a minimum 120 minutes (FD120). Door leaf shall be galvanized steel, minimum 1.2 mm, with a proprietary fire-resistant core; pressed steel frame minimum 1.6 mm; factory-finished powder coating ≥60 microns. Provide fire-rated stainless-steel hinges, mortise lockset with lever handle, heavy-duty hydraulic door closer (self-closing), intumescent fire and smoke seals on all edges, drop-down seal/threshold, and optional vision panel using fire-rated glass per IS 16933. Installation with mechanical anchors; perimeter gaps backfilled with fire-resistant sealant; tolerances per manufacturer. Submit NABL-accredited test reports, compliance certificates, product data sheets, and a 5-year warranty; installation by manufacturer-authorized personnel with final functional checks. Makes: Godrej, Shakti Met-door, Ozone, Jindal				
21	DOOR CLOSER	Nos	2.00		

	BRANCH DETAIL:	KARAH I BRANCH, RBO KHANDWA (M.P.)			
S.N.	Description of Item	Unit	Quantity	Rate	Amount (Rs.)
INTERIOR FURNISHING WORKS					
	Providing and fixing Door closers on doors of make Everite/Ozone/ Hardwyn/ Dorma or equivalent upon approval including all packing, levelling, etc. as required and upto the architects satisfaction.				
22	WICKET GATE	Sq.M.	2.16		
	Wicket Gate :-Wicket gate made up of 30 mm.thick flush door ISI marked finished & laminated on both faces with 1.0mm. thick laminate of approved colour. the door shall have heavy duty SS hinges, SS handles, door stopper etc. The cost shall include, material, SS hinges, door stopper, labor etc. complete. And all the edges shall be finished with teak wood lipping and 1mm Laminate after necessary surface preparation complete in all respects as per design ,as specified in tender document.& to the entire satisfaction of the Architect.				
23	NIGHT LATCH LOCK	Nos	1.00		
	Providing and fixing additional Night Latch type Lock (without handle) on doors of make Godrej/Ozone/Europa or approved equivalent make and design. The latch shall have minimum 3 keys and shall have automatic locking, openable from inside with knob/sliding bolt and with keys from outside. The rate shall be inclusive of all required carpentry works, all required guideplates, hardware, hole cutting etc. complete.				
24	DUAL TONE TEXTURE PAINT	SqM	16.50		
	Providing & finishing walls with dual tone decorative texture/duotone paint effects of Asian/ Nerolac or equivalent make as per approval complete having minimum one colour or two colours laid as per the manufacturer's/ applicator's recommendations using appropriate tools/rollers/base paints etc. as required to achieve evenly spread, evenly shaded texture/paint effect to the satisfaction of the Bank Engineer/ Architect. The rate shall include cost of fixing of 4mm thick MDF of reputed brands if required, preparation of surface, all required tools/ scaffoldings/etc. complete and shall include recommended layers of waterproof and/or protective coating of treated / textured/ painted surface complete as directed.				
25	PUTTY	sqM	120.00		
	Providing and applying PUTTY ON FRESH WORK OR OLD WORK ON WALLS/CEILINGS/CEMENT BOARD PARTITIONS ETC. (minimum 2 coats cement based and 1 coat acrylic putty) The scope shall be including surface preparation, cleaning, scrubbing, levelling using suitable grinding stones so as to achieve smooth sand surface without undulations, application of primer, application of minimum 2 coats of cement based putty and one coat acrylic based putty after thorough smoothening, application of required coats of primer so as to achieve a smooth, levelled and error/crack free surface for painting.				
26	PREMIUM EMULSION PAINT	sqM	120.00		
	Providing and applying Premium Emulsion Paint on walls, ceiling, partitions etc. (Old or Fresh Putty Finish Work) including surface preparation, cleaning, scraping & scrubbing the flaky portions of old paint and roughening of paint layers in good conditions. The scope shall include putty touchup at all required areas, application of primer etc. as per good practices and finishing with upto two or more coats of ICI Dulux washable emulsion paint or equivalent - roller finish (matt) to all indicated wall surfaces. The paint shall be applied after thorough cleaning of the existing painted/fresh work surfaces so as to achieve a dirt-free, grease-free, plain surface free of residual paints before painting with the emulsion. The paint shall be applied as per the manufacturer's recommendations, evenly to produce uniform well finished surface, scope shall be including thorough final cleaning of the premises to the Bank Engineer's / Architect's satisfaction and complete at all level.				
27	SYNTHETIC ENAMEL PAINT	sqM	35.00		

	BRANCH DETAIL:		KARAH I BRANCH, RBO KHANDWA (M.P.)		
S.N.	<u>Description of Item</u>	<u>Unit</u>	<u>Quantity</u>	<u>Rate</u>	<u>Amount (Rs.)</u>
INTERIOR FURNISHING WORKS					
	Providing and applying two or more coats of synthetic enamel paint of make Asian, or equivalent of approved shade and finish on all surfaces except on inner sides of drawers, storage etc. or in items including the cost of painting synthetic enamel in their rates) complete including putty, scaffolding etc. as per the manufacturer's recommendations and to the satisfaction of the Bank Engineer's/ Architect's satisfaction				
28	Economical Water Based Emulsion Paint	sqM	180.00		
28	Providing and applying Economical Water Based Emulsion Paint (with single coat putty) on all ceilings and demarcated walls etc. of record rooms, store rooms, stationery rooms, locker rooms etc. and finishing two or more coats of ICI Dulux emulsion paint or equivalent - roller finish (matt) to all surfaces. The paint shall be applied after thorough cleaning so as to achieve a dirt-free, grease-free, plain surface free of residual paints as per manufacturer's specifications, application of primer, one coat of putty and application of primer coat after proper levelling of putty and finally to be applied with paint. The paint shall be applied evenly to produce uniform even surface cost including final cleaning of the premises to the Bank Engineer's / Architect's satisfaction and complete at all level.				
28	MISCELLANEOUS ITEMS				
a	Providing & installing Zebra Blinds of Trac / Mac/ Vista or equivalent, 36" to 54" size of medium range fabric (synthetic material), of approved shade and colour, pull cords shall be 1.7mm dia. Braided nylon with a core of rayon threads. The blinds shall be operate able in any direction with a flight upto 180 degrees and can slide to one side for opening purposes. All metal parts shall be corrosion resistant and rotating parts shall be self lubricating. The fixing of the top rail shall be with special GI brackets at approx 1meter c/c. complete as directed by the Bank	sqM	10.58		
b	Providing and fixing whiteboard as per approval on partitions/walls/ other substrates in various areas of the office including training room, cabins etc. complete including all ribs, adhesives etc as required	sqM	2.07		
c	Providing and fixing Pin-up boards of 12mm thk. pin board covered with plain matty/cotton fabric as per approval, the fabric stuck with rubber based adhesive to the board as instructed. Cost shall include all tw lippings, base preparation required and joints on fabric shall not be approved.	sqM	6.20		
	Total of INTERIOR FURNISHING WORKS			Rs	
In Words Rs.					