

STATE BANK OF INDIA						
BOQ :INTERIOR & FURNITURE WORKS PBB GUWAHATI BRANCH						
BRANCH NAME : PBB BRANCH AT G.S. ROAD, GUWAHATI						
CARPET AREA : 3369 SQ FT						
	NOTES	ALL LAMINATES TO BE AS PER BANK'S NEW UNIFORM LAYOUT POLICY.				
i	The rate shall be inclusive of frame work above false ceiling level. Measurement should be taken up to false ceiling level and visible portion only.					
vi	All furnitures, Workstations, storages shall be finished with 1.0mm thk Laminate/ 4.0mm thk veneer on all external surfaces and all inner serurfaces shall be finished with 0.70/0.80 mm thk laminate of balancing shade, irrespective of being mentioned or not in the detailed item description of works					
SL	DESCRIPTION	UNIT	QNTY	RATE	AMOUNT	
A.	CARPENTRY WORKS					
1	SINGLE WINDOW COUNTERS (SWO)TABLE WITH SIDE CADENZA AS PER THE DRAWING - Supply and installing new SWO Counters of overall size 1680 mm X 1830 mm X 750 mm alongwith side credenza of size 1200mm x 450 mm x 750 mm , made of 18/19MM thick Commercial grade plywood and drawers/cup boards with 18/19MM(6mm for Back only) Commercial grade plywood as per the drawing and direction of Engineer in Charge. It shall consisit of a pedestal comprising of 3 drawers unit placed on the right side of the user in either fixed type or on castors. The counter shall consisit of a keyboard tray 250 mm wide, CPU stand, foot rest as per the design and direction by bank. All the horizontal surfaces shall be provided with 1.0mm thk Laminate, Frosty White fully polished and front edge bended as per design for provision of LED Light and vertical surfaces to be finished with 1.0mm thk glossy laminate in Aqua Blue shade fixed with necessary adhesive over Plywood in Front Facia and sides (Customer Side and inside) and in all shutters of of side storage and Pedestal . All the Thickness shall be finished with1.0mm thk LAMinate of approved shade and make.The side storage/Cadenza shall have doors sliding on rollers as per disign with proper locking system. The key board drawer shall be provided with telescopic rail of "Earl Behari/Fly rail" make . All internal surfaces shall be finished with 0.80mm thk laminate of milky white shade instead of paint . The drawers /cup boards shall be fitted with best quality knob/handle and self locking arrangements of M/s Godrej or equivalent make. The rate to include all necessary charges of hardware materials, labour, taxes, transportation and contractor's overhead etc. Refer Detail Drawing of Single Window for reference. Rates Shall be inclusive of all locks , handles, magnets, Tower bolts etc and other hardware items as may be required and as asked by the architect/ engineer incharge. All laminates to be as per Banks New Uniform Layout Policy	NOS	3			
2	Providing & fixing 12mm thk Float Glass in front of Single Window Counters with cutout for transcastion and also a 75mm dia opening for voice all with polished edges and fixed with necessary S.S Brush finish brackets support on wooden partition as directed. Rate shalll includes fixing of frosted film with Bank's logo as per design & directed.	SQM	3			
3	Providing & Fixing 12 mm thick float glass of size 320mm (width) x 1100mm (height) & tapering towards bottom as per the design and shape as shown in Bank's new uniform colour, layout & elevation policy, fixed with silicon and T.W beading support on wooden partition as directed, on either sides of SWO as per design. Rate shall includes etching of glass as directed by bank. All edges of glass shall be duly bevelled & polished as directed complete. Make: Saintgobin/ Modiguard or equivalent.	SQM	2			
4	Supply and installing of Chief Manager's Table of overall size- 2400 mm x 900 mm x 750 mm including side credenza of size 1200mm x 450mm x 750 mm, made up of 19mm thick plywood all around, finshed with 1.0mm thick laminate of colour, shade & brand as approved. It shall consisit of a pedestal comprising of 3 drawers unit placed on the right side of the user in either fixed type or on castors. The counter shall consisit of a keyboard tray 250 mm wide, CPU stand, foot rest as per the design and direction by bank. The Side credenza unit shall be made with 18/19mm thk commercial grade plywood and finished with 1.0mm thk laminate on all external surfaces . It should have openable/sliding shutter cupboard and intermediate horizontal shelves made in 12 mm thick plywood. All Inner Surfaces should be finished with 0.60/0.80 mm thk laminate of balancing shade. . The works to include all hardwares such as: castors, brass hinges, ball catchers, fully extendable drawer slides, auto locks, handles etc. of Godrej or approved brand. Locks to be of single control type. Design and detail of the table shall be as per direction of EIC. The Table & Cadenza top should be provided with 8mm thick glass with polished edges duly finished with necessary cut-out to accommodate wires, edges to be m/c polished, with ms powder coated wire manager complete. All laminates to be as per Banks New Uniform Layout Policy. Ply/plywood Make: CenturyPly/ Greenply/ Archid Ply or equivalent Laminate Make: Greenlam/ Centurylam/Archidlam or equivalent	Each	1			

5	Supply and installing of Asst. General Manager's Table of overall size- 2430 mm x 1050 mm x 750 mm including side credenza of size 1350mm x 450mm x 750 mm, made up of 19mm thick plywood all around, finished with 1.0mm thk Laminate of approved shade and make as per the Bank's ambience manual. It shall consist of a pedestal comprising of 3 drawers unit placed on the right side of the user in either fixed type or on castors. The counter shall consist of a keyboard tray 250 mm wide, CPU stand, foot rest as per the design and direction by bank. The Side credenza unit shall be made with 18/19mm thk commercial grade plywood and finished with 1.0mm thk laminate of approved shade and make on all external surfaces. It should have openable/sliding shutter cupboard and intermediate horizontal shelves made in 12 mm thick plywood. All inner surfaces shall be finished with 0.80mm thk laminate of milky white shade instead of paint. The works to include all hardwares such as: castors, brass hinges, ball catchers, fully extendable drawer slides, auto locks, handles etc. of Godrej or approved brand. Locks to be of single control type. Design and detail of the table shall be as per direction of EIC. The Table & Cadenza top should be provided with 8mm thick glass with polished edges duly finished with necessary cut-out to accommodate wires, edges to be m/c polished, with ms powder coated wire manager complete as per Bank's new uniform colour, layout & elevation policy. Ply/plywood Make: CenturyPly/ Greenply/ Archid Ply or equivalent Laminate Make: Greenlam/ Centurylam/Archidlam or equivalent	Each	1		
6	Supplying and erecting Tables for Grahak Mitra and cross selling staff table of Overall size - 1500 mm X 600 mm x 750 mm. It shall consist of 18/19 mm thk.Commercial grade plywood top as per design (double edge on the front and back with) supported on18/19 mm thk.Commercial grade plywood verticals. Suitable (as per Architects design) . A 18/19 mm thk.Commercial grade plywood apron shall be provided as per Architects design with necessary pattern. The Table top and side should be finished with with 1.0mm thk laminate of approved shade and make as per approved design.The Front Modesty Panel of the Table (Customer Side) shall be finished with with 1.0mm thk laminate of approved shade and make as per approved design. Each top should be provided with a 3" dia PVC wire manager of approved quality near the CPU / Monitor , 1 no Metal Keyboard Tray of Best quality, 1 no Metal CPU Trolley at position as shown in drawing. It shall consist of a pedestal comprising of 3 drawers unit placed on the right side of the user in either fixed type or on castors. as per design with central locking system. The exposed surfaces and sides of the pedestal shall be finished with 1.0mm thk laminate of approved shade as per design.All internal surfaces shall be finished with 0.70/0.80 mm thk laminate of balancing shade as approved by the architect/ EIC/ Branch. All locks and other hardware fittings to be used shall be strickly of Godrej or equivalent .Rates Shall be inclusive of all locks , handles, magnets, bolts etc and other hardware items as may be required and as asked by the architect/ engineer incharge. All laminates to be as per Banks New Uniform Layout Policy. Ply/plywood Make: CenturyPly/ Greenply/ Archid Ply or equivalent Laminate Make: Greenlam/ Centurylam/Archidlam or equivalent	Each	0		
7	Providing and laying <u>Officer's Workstations</u> of over all size 1675mm x 750 mm x 750 mm along with side cadenza of size 1050mm x 450mm x 750mm as mentioned in the detailed drawing. It shall consist of 18/19 mm thk.Commercial grade plywood top as per design (double edge on the front and back with) supported on18/19 mm thk.Commercial grade plywood verticals. Suitable (as per Architects design) . A 18/19 mm thk.Commercial grade plywood apron shall be provided as per Architects design with necessary pattern. The Table top and side storage alongwith all other exposed surfaces should be finished with 1.0mm thk laminate of approved shade and make as per approved design and a groove shall be maintained and provided at the joints between two colour shade. Each top should be provided with 3" dia PVC wire manager of approved quality near the CPU / Monitor , 1 no Metal Keyboard Tray of Best quality, 1 no Metal CPU Trolley at position as shown in drawing and a foot rest. It shall consist of a pedestal comprising of 3 drawers unit placed on the right side of the user in either fixed type or on castors. as per design with central locking system. The side Storage shall have openable shutter on hinges with necessary locking arrangements. All exposed surfaces of the pedestal & storage, including the shutters shall be finished with 1.0mm thk laminate of approved shade and make as per approved design over plywood .All internal surfaces shall be finished with 0.70/0.80 mm thk laminate of balancing shade as approved by the architect/ EIC/ Branch. All locks and other hardware fitting shall be strictly Godrej or equivalent only and appropriate deduction/ penalisation as deemed fit by the enginger-in-charge/ architect shall be made if the same make for locks and all hardware fittings are not used by the contractor. All laminates to be as per Banks New Uniform Layout Policy.	Each	8		
8	LINEAR WORK STATION/ RUNNING COUNTER 2'-0" WIDE WITH PEDESTAL -Providing and laying in position linear Workstation counter with pedestal ,key board tray , Wire manager, CPU Trolley & Foot Rest at every 4'-6" length for 2'-0" over all size of top . It shall consist of 18/19mm thk. Comm. Ply top as per design (double edge on the front and back with 38mm thk half round moulding on the edges) supported on 18/19 mm thk. Comm. Ply verticals at every 4'-0" length. Suitable (as per Architects design) wooden moulding with mellamine shall be provided to the edge of the top. The top of the counter and all other external surfaces to be finished in 1.0 mm. thk. Laminate of approved shade & make. The Running Counter should also be provided with- 1no. readymade Computer key board tray of Ebco/ Hettich make on telescopicchannel , 1no. pedestal(Modular Type) of size 392mm(L)x 450mm(D) x 680mm(H), movable type on castors . The pedestal/ drawer unit shall consist of two numbers of drawers and one filing box mounted on ebco/ haffle/ hettick make metal telescopic channel on either sides. It shall be provided with central lock mechanism with keys and handles of ebco/ haffle/ hettich make in the front to faciliate opening and closing of drawers .Drawers shall be made of 18/19mm ply finished with laminate outside & wood lipping, mounted on drawer slides. Rates should include all hardware like castors, brass hinges, ballcatches, fully extendable drawer slides, locks, handles etc., of approved make. All exposed edges to have wooden lipping stained to match the desk and melamine finished.All external surfaces should be finished with 1.0mm thk laminate and all inner surfaces should be finished with 0.70/0.80 mm thk laminate of approved shade and make in approved pattern. All laminates to be as per Banks New Uniform Layout Policy	RM	2.2		
9	SECURITY GUARD & SUB STAFF TABLE- 4'-0" X 2'-0" - Providing and laying a Plain Table for Security Gurd with a Pencil Drawers for over all size of top as mentioned above. It shall consist of 3/4" thk. Comm. Ply top as per design (double edge on the front and back with 1 1/2" thk half round moulding on the edges) supported on ¾" thk. Comm. Ply verticals at every 3' length. Suitable (as per Architects design) wooden moulding with mellamine shall be provided to the edge of the top. The top of the counter should be finished with 1.0mm Laminate and all other external surfaces to be finished in 1.0 mm. Thk. Laminate (suede finish)of approved make. All laminates to be as per Banks New Uniform Layout Policy	NOS	1		
10	DINING TABLE OF SIZE-8'-0" X 3'-6" - Providing and making a table of over all size of top as mentioned above. It shall consist of two nos BWP ply 18/19mm and 6/8mm thk sandwiched as per design as Table Top and finished with 1.0mm thk laminate of approved shade . All the edges shall be finished with leaping patty of matching shade .It shall be supported on 18/19mm thk comercial ply base as per the design as in the detailed drawing (as approved by the architect), finished with 1.0 mm thk laminate of approved shade.	NOS	0		
11	PARTITIONS WORKS				

	Note :- The rate shall be include of frame work above false ceiling level. Measurement should be taken up to false ceiling level and visible portion only. All laminates to be as per Banks New Uniform Layout Policy				
a	FULL HT SOLID PARTITION - Providing and fixing in position full height solid partition 75 mm thk. as indicated in the drawing excluding the door. The partition framing shall consists of Heavy Duty Aluminium Box Sections of size 50mm x 50mm x 2mm thk of approved make conforming to IS: 733 and IS : 18/1985, fixed with rawl plugs and screws or with fixing clips with vertical & horizontal members at not more than 600 mm center to center all complete including necessary additional supports for fixing of patch fittings of door, bracing, runner etc. so that lateral movement is arrested as per instructions of EIC / Architect. The first horizontal member shall be fixed at ground level and thereafter at every 600mm. Framework shall be fixed with 8/9 mm thk plywood of approved make of required width and size on one side or on both side as mentioned below and as per drawing including cost of making openings for switches, AC facias etc. The rate includes cost of polishing, adhesives like fevicol,silicon, nails, screws and labour charges etc. all as per instructions of EIC / Architect.. The 8/9 mm thk Plywood fixed Partition shall then be finished with necessary finishing materials like laminate/paint/ veneer/wall paper/ a.c board etc as mentioned below of approved shade and make. Rate shall be inclusive of provision of pencil groove as directed by the Architect. Height of the partitions upto soffit of false ceiling / laminate finish top shall be considered for payment. Alternate, corner vertical members of the partition shall be fixed with necessary brackets /supports at RCC levels. The item does not include the doors. The framework above the false ceiling shall not be considered for payment.s. The partition should be finished with 1.0mm thk Laminate/ 4.0mm thk Veneer finished in melamine polish. The shade of laminate / veneer and polishing finish to be got approved from the Architect.				
i	WITH BOTH SIDE LAMINATE	SQM	26		
b	SEMI HT. SEMI GLAZED PARTITION IN WITH BOTH SIDE LAMINATE (INCLUDING PARTITIONS FOR SWO) - Specification same as 4 above but of low ht as per the drawing. A 70mm x 15mm steam beach moulding with champhered edge is to be provided on all external edges & finished in mellamine as per details. Providing and Fixing inserted Soft board / White boards / itched Glass maintaining the vertical surface lines and no extra measurements would be taken for the soft boards / white boards / Glass.	SQ M	34		
c	FULL HT. FULLY GLAZED PARTITION - WITH TOUGHENED GLASS - Providing and fixing of Fixed Glass partition with 12 mm thick toughened glass using PT Standard fittings like PT90/ PT92 of DORMA make at the top and grouting at the bottom with U - Shaped Aluminium rails and EPDM gaskets including cutting, making holes in glass and fixing the fittings in floors, false ceiling etc. and making the same good with necessary screw, sealent wherever required. The top PT standard fittings to be fitted to the Wooden section fixed above the Gypsum board in the level of GI channels of False ceiling.	SQM	14		
12	PANELLING WORKS - Providing and fixing panelling on walls/ columns with or without framing as per the directions of the architect. Framing if required and provided, shall consists of aluminium sections 50mm x 40mm(wall thickness 2mm) @ 2'-0" c/c both ways horizontally and vertically on the wall. The framing would be covered with 1/4" thk plywood finished in approved shade of laminate / veneer/ lecuquered glass/ Louvers/ Wall Paper/ Mirror Metalic laminate etc. . Wooden moulding, lipping etc as directed by the architect shall be provided wherever required.				
a	PANELLING ON WALLS WITH LAMINATE	SQM	110		
b	PANELLING WITH 8mm thk LACQUERED GLASS	SQM	6		
c	PANELLING WITH WPC LOUVERS	SQM	10		
13	DOORS				
a	ENTRANCE DOORS - IN TOUGHENED GLASS - Providing and fixing 12 mm thick Fully Glazed doors made of toughened glass fixed on patch fittings of approved make and as per design and details given by the architect/designer or as directed by engineer in charge. Cost is inclusive of approved locking arrangement, handles , accessories, floor spring as per door weight (entry door to office)				
i	BANKING HALL - FULLY GLAZED (12 MM THK GLASS)	SQ M	5.5		
b	SOLID DOORS- IN LAMINATE FINISH (with hardware fittings MAKE EVERITE / GOLDEN /HARDWIN /EVEREST) (WITH OR WITH OUT VISION PANEL AS PER DIRECTION OF BANK / ARCHITECT - Providing and fixing solid doors of sizes as shown in the drawing. The door shutter shall of 35 mm thick flush shutter of approved make and finished with 1.0mm thk laminate of approved shade and make on both sides. A door frame of 3.5" x 2" steam beach section shall be provided finished in 1.0mm thk laminate of approved shade and make. Rate shall include Dead lock (Godrej Make), floor springs / door closure (as the case may be), door stopper, a pair of handles 18/19" SS Brushed finished, 5" hinges 4 Nos., buffers, tower bolts, etc with necessary hardware items and with or with out door frames as mentioned above				
i	2-6"/3'-0" x 7'-0" - IN LAMINATE FINISH - (WITH OR WITHOUT WOODEN FRAME)				
	With Door Closure	NOS	2		
14	SIDE / CORNER TABLES - Providing and making corner / side tables of above mentioned size as per drwng. Table top shall consist of 18/19 mm. Thk.float glass with champhered edge(bevelled edge) fitted to the frames with necessary arrangement. The base shall be made up of Steam beach wood frame as directed by the Bank / Architect. It should be with 4 Nos of 35mmx35mm for vertical members tied to each other with horizontal members of 20mm x 35mm frames at bottom and All wooden frames to be finished with melamine.				
a	CORNER TABLES(1'-6" x 1'-6" x 1'-6"HT.)				
	FINISHED WITH 1.0mm thk LAMINATE OF APPROVED SHADE AND MAKE IN APPROVED PATTERN	NOS	0		
b	CENTER TABLES (1'-6" X 2'-6" X 1'-6"HT)				
	FINISHED WITH 1.0mm thk LAMINATE OF APPROVED SHADE AND MAKE IN APPROVED PATTERN	NOS	2		
15	PIN-UP BOARDS / NOTICE BOARDS (4' X 3') - Providing and fixing pinup boards. It consist 18/19mm thick soft boards of good density to be mounted over 18/19mm thickCommercial grade plywood. The soft board will be covered with a plain fabric (appox Rs.250 /Rmts. of approved colour) from front and edges. Suitable steam beach moulding 25mm x 25mm size to be fixed on all four sides and will be finished in melamine polish. Note : Only soft bords provided on other than the partitions will be measured and soft board made in the partitions will be the part of the partition measurement (rate) and not consider separately.	SQM	6		
15	FULL HT / MEDIUM HT / LOW HT / OVER HEAD STORAGEES.				

a	LOW HT RUNNING STORAGE(450mmDX750 HT) (BACK CADENZA) - Providing and laying low ht Storage unit of sizes as mentioned above. They shall consist of 18" thk Commercial grade plywood for top, base and sides and base 9mm thk Commercial grade plywood, 18/19MM thk Commercial grade plywood shutter with self closing hinges of haffle make(full ovel open) & PVC lipping matching with the approved shade of laminate/ veneer/ on all the edges. All external surfaces shall be finished with 1.0mm thk laminate/ 4mm thk veneer of approved shade and make as per approved design.Divisions of the shutter shall be make equally according to the length of the storage. A 3/4" thk BWR Grade fixed ply wood shelf on battens shall be provided @16" intervals from the base. Suitable wooden moulding (as per Architects design) with mellamine polish shall be provided to the edges of the storage top. All internal surfaces shall be finished with 0.70/0.80 mm thk laminate of balancing shade as approved by the architect/ EIC/ Branch.Rates shall be inclusive of all necessary approved fittings like hinges(Godrej or equivalent make), locks, 3" long brushed finish handle, tower bolts and any other misc hardware items of approved make				
i	FINISHED WITH LAMINATE	SQM	15		
b	FULL HT. STORAGE - Providing and fixing storage units of full height as per drwng. They shall consist of 18/19MM thk.MR Grade plywood top, sides,back, bottom, shelves and shutters. The bottom of the storages shall be at 3" from FFL. The top of storages shall touch the false ceiling level or 7'-0" ht. The shutter with box type higes of approved make & steam beach lipping finished with melamine with approved laminate on all the shutter edges. Division of the shutters shall be made equally according to the length of the storages (as approved by Bank/ architect). All the external surfaces shall be finished with 1.0mm thk. Venerred Laminate of approved make. 18/19MM thk. MR Grade plywood shelves removable type supported on side steam beach wood battens on both sides at 16" interval (approximately / divided equally) shall be provided. All inner surfaces shall be finished with laminate including the shutters. Rate shall be inclusive of all necessary approved fittings like hinges, locks, 150mm long SS brushed finish handles,tower bolts, locks and any necessary hardware items. The top ply edge should be fitted with 19mm x 7mm size steam beach moulding finished with melamine.	SQM	15		
c	OVER HEAD STORAGE - WALL - HUNG (2'6" High X 1'3" Deep) : P/ F Wall Hung Storage made out of 19 mm thk MR Ply, 33 cm deep, 6mm thk MR Grade Ply for the back, openable shutters in 18 mm thk MR Grade Ply, with hinges as recommended, 18 mm thk removable shelf with 0.8 mm white laminate finish on both sides, edges shall be provided with 2 mm thk PVC strips on all sides. All hinges, tower bolts, S.S Brush finish handles, ball-catches shall be of brass heavy duty, approved make Locks etc. complete as per design/ instructions. All exposed surfaces whether inner side or outside must be 1mm laminated with approved laminate shade. (Exposed surfaces should not be painted)	SQM	3		
17	FALSE CEILING AND P.O.P. WORK				
a	FALSE CEILING - GYP BOARD FINISHED WITH POP - Providing and fixing ½" thk. Gypsum India board false ceiling at levels as shown in the drg. From FFL. Rate shall be inclusive of all Gypsum India components contained G.I. perimeter channels of size 0.55 thick having one flange of 20mm and another flange of 30mm and a web of 27mm alongwith perimeter of ceiling, screw fixed to brickwall/partition with the help of nylon sleeves and screws, at 610mm centres. The suspending G.I.intermediate channels of size 45mm, 0.9mm thick with two flanges of 15mm each from the soffit at 18/1920mm centres with ceiling angle of width 25mm x 10mm x 0.55 thick fixed to soffit with G.I. cleat and steel expansion fastners at every 610mm c/c. Ceiling sections of 0.55mm thickness having knurled web of 51.5mm and two flanges of 26mm each with lips of 10.5mm are then fixed to intermediate channel with the help of connecting clip and in direction perpendicular to the intermediate channel at 457mm centres. 18/19.5mm tapered edge Gypboard is then screw fixed to ceiling section with 25mm drywall screws driver or drilling machine with suitable attachment. The boards are to be jointed and finished so as to have a flush look which includes filling and finishing the tapered and square edge of the boards with jointing compound & joint paper tape. Rate shall be inclusive of Cut outs for A/c machiness, spot lights, light fixtures, A/C. Grills, fire and security systems cut outs, All Sections should adhere to the manufacturers guidelines. Vertical sides visible will be measured..Rates Shall also be inclusive of vertical drop in ceiling upto 18/19" and no extra measurement for the drop upto 18/19" will be entertained.The rate shall be also inclusive of scrapping, levelling & preparing the surface of the ceiling. Primer coat + 3 coats (minimum) of approved make , quality & finish shall be provided.	SQM	190		
b	MODULAR FALSE CEILING - SILHOUETTE SERIES - Providing and fixing approved Armstrong mineral ceiling Tiles Edge : - Microlook. GRIDS :- Silhouette 5mm.Black/White reveal grids system as per the manufacturers' specification of Mineral Fiber ceiling including suspension system fittings & frame work as per manufacture's specifications. Exposed grid system with 15mm wide T-section flanges, white colour 15mm gird to comprise main runners spaced at1200mm centre to centre securely fixed to structural soffit by approved hangers at 1200mm maximum centre to centre and not more than 150mm from spliced joints. The last hanger at the end of each main hanger should not be greater than 600mm from adjacent wall. Flush fitting 1200mm long cross tees to be interlocked between main runnders at 600mm centre to from 1200x600mm modules. Cut cross tees longer than 600mm require independent support. 600x600mm modules to be formed by fitting 600mm long flush fitting cross tees centrally between the 1200mm cross tees. Perimeter trim to be armstrong trulok wall angle or channel secured to walls at 450mm maximum centres. The rate shall include cutting of the tiles for light fixtures/A.C. diffusers etc. and providing necessary and additional frame work for fixing the same. Wherever channels are cut in this process, additional support shall be made for proper stability. Both butterfly clip hangers and binding wire supports will also be provided for additional support. These fittings will be anchored to the ceiling with anchor fasteners only for more better support etc complete as per the directions of SBIL project incharge. <i>If Silhoutte Series Ceiling is not provided then deduction @ 60% of quoted rate shall be applicalble while setteling the Final bill fo the contractor</i>	SQM	152		
c	WPC BAFFLE CEILING of VOX/ PARE/ LEEBEN Make - Providing and fixing panelling on ceiling with wood finished PVC /WPC Baffle including preperation of base by suspenting with 12/19 mm thk plywood with necessary supports & framings from the slab in plumb line so as to fix the baffle. The size of each section in baffle should be 15mm x 50mm and having a gaping of 25-38 mm in between. Rate sahl be inclusive of all framing, sections, screws etc all complete as required to fix the PVC panel to the desired wall surface. Note if Gypsum is used as Backing Material instead of Plywood of 12/19mm thk then no Payment for Gypsum shall be paid seperately	SQM	15		
18	PLASTIC EMULSION ON GYPSUM CEILING - Providing & applying plastic emulsion paint on walls, columns & ceilings. The rate shall include scrapping, levelling & preparing the surface. Primer coat + (minimum) 3 coats to get evenly spread quality finish (roller finish) of approved make , quality & finish shall be provided.	SQM	200		

19	LUSTRE PAINT ON WALLS - Providing & applying Luster Paint on walls, columns & ceilings. The rate shall include scrapping, levelling & preparing the surface. Primer coat + (minimum) 3 coats to get evenly spread quality finish (roller finish) of approved make, quality & shade shall be provided.	SQM	180		
20	ENAMEL PAINT IN EXISTING ROLLING SHUTTER, WINDOW GRILLS & OTHER M.S WORKS - Providing & applying 1 st quality oil paint of approved make, quality & shade. The rate shall include scrapping, levelling & preparing the surface with primer quote.	SQM	50		
21	DISTEMPER PAINTS FOR WALLS (TOILETS, STORE, UPS etc.) - Providing and applying Distemper paint on walls , columns & ceilings. The rates shall include scrapping, levelling & preparing the surface. Primer coat +(MINIMUM) 3 coats to get evenly spread quality finish(roller Finish) of approved make, quality and finish shall be provided.Note- Rates shall also include - filling up the cracks in the wall & ceilings, making good surface .	SQM	300		
22	TEXTURED PAINT - Providing & applying a coat of textured finish on walls and columns. The rate shall include scrapping, levelling & preparing the surface. Primer coat + (minimum) 3 coats of approved make, quality & shade shall be provided.	SQM	12		
23	MISCELLANEOUS ITEMS				
a	ROLLER BLINDS - Providing and fixing of Vista or Equivalent Roller Blinds having openness factor 3%, Weighted composition 75% PVC,25% Polyester with fabric thickness 0.6 to 0.7mm, 250cm of maximum width at 470 gsm(+ or - 5%) fabric weight conforming to the Fire resistance NFPA 701,BS 5867 part - 2 type A, with required colour fastness to light grade of 6 & UV Blockage up to 97% and Hardware consist of Control unit, Idler, Head rail, Roller tube, Bottom rail, Operating chain and Fixing brackets & clamps complete as per the hardware specifications as described below .The cost inclusive of supply,transport and fixing of Roller Blinds all complete making good to window /opening as per the directions of Engineer-In- Charge.	SQM	14		
b	WALL PAPER - Providing and fixing in position Wallpaper fixed with approved make of adhesive of approved Make and Design as Specified by the Architect	SQM	13		
c	SHUTTERS BELOW GRANITE COUNTERS IN KITCHEN - Providing and fixing 19mm thk. BWR ply shutters with ply frame, skirting gap as shown in the drg. shall be maintained. Division of shutters shall be made equally according to the length of the counter. Shutters shall be hinged to the framework and finished with 1.0mm thk. Laminate (suede finish) of approved shade from outside, applied with approved oil paint from the inside and edges of shutters with steam beach lipping. Rate shall be inclusive of all necessary approved fittings like hinges, ball catch, handle, and any necessary hardware items.	SQM	7		
d	STAINLESS STEEL TOILET SIGNAGES FOR WALLS/ PARTITION/ DOORS - Supplying & fixing in position as directed by the architect, toilet Signages made of thickness 0.5mm and size 150mm x 100mm, made from high quality stainless steel, UV resistant and made for high quality vinyls with hater proof and heat resistance. It shall be fixed with double sided adhesive tape	NOS.	3		
e	ARTIFICIAL WALL HANGING CREEPERS - Supplying and Fixing washable Sphinx Artificial Leaves Garlands/Creepers For Decoration, Made up of polyester fabric, commonly used for decoration of reception area and walls.	RM	44		
f	10MM GLASS SHELVES- 250-300MM WIDE - Providing and fixing 10mm thk Clear Glass Shelves, 250-300MM WIDE in mirror polished edges as per design. The Glass selves should be fixed with the help of Stainless Steel F Type Glass Shelf Bracket Square 12 Inches, with screws to walls / partitions/ panneling, at an interval of 24-30" as per design and as directed by the achitect	RM	6		
g	SYNTHETIC ARTIFICIAL GRASS FOR VERTICAL WALL - Providing and laying Synthetic grass for vertical wall/ landscaped garden with leaves having Gauge3/16"; Dtex 44000D(PP Curly Yarn);Coating: Double PP+SBR Latex; Colour: Green	SQM	12		
j	WRITING LEDGE IN LAMINATE FINISH - P/F Writing Desk/ ledge of total length as per drawing and 1'-0" in width X 3'-6" ht. in 25 mm thk. Exterior Grade MDF Board of approved make for Ledge top and Vertical side supports .The side& Top should be finished with 1.0MM THK LAMINATE of approved shade and make in desired pattern as directed by the architect/ EIC. NOTE :(Please check the Ledge Length sizes per layout to fit the site condition).	Nos	2		
k	Customised Stainless Steel Bank's Logo with Back Lit - Supplying , fabricating and installation of Customised Stainless Steel (S.S.) back-lit Bank's Logo, for both indoor and outdoor branding, featuring 3D letters that create a halo-illumination effect. It shall be made with High-grade 304 or 316 Stainless Steel (brushed, mirror, or golden finish) 3D letter fabrication with laser-cut for precision all alongwith LED modules, having a total thickness of 2 inches (50mm) to allow for internal LED placement. It shall be fitted with following- i) Waterproof LED modules (warm white) for uniform backlighting, ii)3mm thick diffuser acrylic mounted at the back to disperse light evenly, iii)12V DC power transformer (suitable for 100-240V AC input).It shall be installed using stainless steel studs to stand off from the wall, allowing the backlight to wash over the mounting surface, with all concealed wiring and pocket behind to hide the adapter and the socket, etc.				
I	OVERALL SIZE 900-1000 MM DIA	NOS	0		
i	OVERALL SIZE 600-750MM DIA	NOS	2		
ii	OVERALL SIZE 600-750MM DIA	NOS	1		
l	NOTICE BOARD - Providing and fixing notice board size as required/ directed (matching with the panel of the cabin) with openable shutter on the front. Made out of 19mm thick Steam beech veneered plywood frame and outer frame in 2 1/2" x 1 1/2" Steam beech wood section , concealed hinges , locking arrangement , and glass of (5.5mm thick) with rear panel of SITATEX board , covered with fabric of approved shade. (Basic rate Rs.100/-per mtr , 48" width), fixed to back ply 6mm thick . All complete including melamine polish in stain of required shade. All complete as per approval of the Architect / employer	SQM	5		

m	SUGGESTION BOX (450 x 600 x 200) : Providing and fixing suggestion box made out of 19mm BWP ply and finished with 1mm laminate and enamel painted on the inside. A 300 mm long slit is to be made in the front for letters, etc. The work should be completed in all respects.	Nos	1		
n	CHEQUE DROP BOX - P/F one cheque drop box made out of 12 mm thick BWP duly laminated with all hardware fitting and fixtures. Size 400 x 300 x 100 mm	Nos	1		
o	DRY PLANTER BOX WITH POT & PLANTS - Providing and fixing dry Planters Boxes of avg. size 350mm x 350mm x 300- 450mm(H); The Planter Box shall be made out of 2 nos 18 mm thk. sandwitched plywood - sides finished in both inner and outer surfaces with 1.0mm thk laminate of approved shade and all exposed side edges of Ply/ board shall be covered with teak wood beading finished with matching Deco paint to give it similar finish. Rates shall be inclusive of 12-14" dia PVC Flower pot with artificial/ natural plants as per architect's choice.	NOS	10		
p	LAMINATED COLLAGE PRINTING - Supplying fixing and placing in position PVC Vinyl poster of approved design and pattern. The Vinyls poster should be sandwitched between 2 nos 4/5 mm thk clear acrylic sheet (one in front and the other in the back) . The poster should be fixed on the wall/ partition with 8-10 Nos S.S Studs as per design and as directed by the architect.	SQM	6.2		
q	SHUTTERS WITH FRAME FOR ELECTRICAL PANELS - Providing and fixing 18mm thk. Com ply shutters with same ply frame. Division of shutters shall be made equally according to the length. Shutters shall be hinged to the framework and finished with 1.0mm thk. Laminate of approved colour and shade on outer side and inside finished with 2 coats of enamel paint of app colour and shade. Rate shall be inclusive of all necessary approved fittings like hinges, ball catch, 150 mm long SS Brush Finish handle, tower bolts, locks, Aluminium powder coated air vent grills and necessary hardware fittings complete, etc.,	SQM	1.8		
r	COLOURED VINYL/FROSTED FILM OVER GLASS/ WALLS/ PILLARS/ PARTITIONS - Supplying and Fixing coloured flex/ Wall paper/ Film of approved shade, pattern and design as approved by the architect on finished walls/ partitions/ceilings/pannelling, as directed by the architect with approved make of adhesive.	SQM	12		
s	PANTRY LEDGE IN LAMINATE FINISH - Erecting & fixing wall hanged/ supported 15'-18" wide Pantry Ledge made with 19mm thk Plywood and finished with 6mm thk Corian and bended on all edges, in approved shade and make in desired pattern as directed by the architect/ EIC. The ledge to be fixed with the wall and supported with M.S angle support for the whole length	RM	5		
t	MIRRORS IN TOILETS - Providing and fixing 12mm thk. clear mirror (First Quality) with bevelled edges on all sides on 12mm thk. Marine ply backing, fixed with 38-50mm dia S.S spacer bars and S.S Studs, to wall as per design and as directed by the architect/ EIC. Necessary Support with S.S studs shall be provided on either sides for every length of 900mm. The rate shall be inclusive all necessary fixtures & fittings.	SQM	5		
u	DRESSING MIRROR FOR LOCKER ROOM -Providing and fixing dressing table made out of mirror of size 1' 6" x 3' 0" using 12mm thk. Comm. Ply with 6mm thk. clear Mirror fixed on the wall & tray of size 1'6"x1'6" with one drawer for cosmetics. (Measurement is measured only for mirror)	SQM	2		
v	ROLLING SHUTTER BOXING - Providing and Fixing Shutter Boxing with 19mm thk Marine Ply and Finished with wooden textured Aluminium Composite Panel. The boxing of shutter should be made openable type for periodic maintainance. <u>Note the mode of measurement would be the multiplication of the length and the height of the boxing.</u>	SQM	6		
A	TOTAL OF CARPENTRY WORKS OF PBB BRANCH ON GROUND FLOOR				