

Subject	Proposed Interiors for State Bank of India, Regional Business Office - IV, at Fourth Floor, Sheranwala Gate, The Mall, Patiala, Distt. Patiala. (Pb).				
	BOQ				
S.No	ITEM	QTY	UNIT	RATE	AMOUNT
	INTERIORS / FURNISHING				
	Note - The work / Items includes all kind of leads / lift, shuttering & scaffolding for all heights & floors. No extra Payment shall be made for the same.				
1	Officer's & Staff Tables Table made of 19 mm thk. Commercial ply with Table Top, front and side visible vertical surfaces to be finished with 1.0 mm thk. laminate of approved colour & shade, with 40 mm X 12 mm thick teak wood all around, as per drawing. The front of the table top shall be projected as per drawing. Provision for 3" dia. round / 3" square cable manager for computer / electrical cables at appropriate place will be made in the top surface of the table. The wood lipping will be provided on all the edges of the table, including bottom touching the floor and the drawers. The table shall have a key board tray of size 600 X 270 fixed on channels finished with laminate, as per manufacturers instructions / specifications.				
	A full depth CPU shelf 15" wide shall be provided at left hand side of counter underneath the working top, at 4" above the floor level and 3" away (horizontally), from vertical end which will be made of 19 mm thick commercial ply & (includes required flexible ply of required specifications) finished with 1.0 mm thk. laminate and 3/4" x 1/4" teakwood lipping on all visible sides. One drawer with lock and one cupboard with shutter made of 19 mm commercial ply with 1.0 mm laminate on front side of cupboard shutter with shutter having good quality locks, magnetic catcher, hinges, handle / knob etc. is to be provided. The shutters shall be provided beneath the drawers with each counter on its right / left hand side. The sides of the drawer shall be made of 12 mm thick plywood / 19 mm ply, bottom of 6 mm thick plywood & front of 19 mm thick ply. A full length foot rest made of hard wood 3" x 2" section shall be provided at 4" above floor level. Non-Visible / inside surfaces i.e. inside / leg-space of table, inside of drawer / cupboard shall be finished liner of 0.7 to 0.8 mm thk. off white / white colour and teak wood edges / lipping / beading shall be spirit (natural) polish. Make - Saint Gobain / TATA / Asahi Makes - Telescopic Channel - Ebco / Haffele / Godrej / Ozone / Door set / Herison), Locks - Godrej / Hettich / Dorma / Ozone / herison / doorset / plaza, Plywood Make: ISI marked BMR-IS 303.				
a	RM - Size 8'0" X 3'6" X 2'6"	1.00	Nos.		
b	C.M. - Size 6'0" X 3'0" X 2'6"	5.00	Nos.		
c	M.T. / O.T. / S.T. - Size 5'0" X 2'6" X 2'6"	34.00	Nos.		
d	OT - made to shaped - Size 5'0" X 5'0" X 2'6"	2.00	Nos.		
e	Reception table - two lvls. - Size 5'0" X 5'0" X 2'6" & 3'6"	1.00	Nos.		
f	Meeting Table - Size 12'0" X 4'0" X 2'6"	1.00	Nos.		

Subject	Proposed Interiors for State Bank of India, Regional Business Office - IV, at Fourth Floor, Sheranwala Gate, The Mall, Patiala, Distt. Patiala. (Pb).				
	BOQ				
S.No	ITEM	QTY	UNIT	RATE	AMOUNT
2	Console - Solid teak wood - 3'6" X1'6" X 2'6" - made to shaped. Providing and supplying a Teak Wooden Console for reception area with an overall size of 3'6" X1'6" X 2'6" - made to shaped. Tho frame of the console is crafted from solid teak wood, which is expertly polished in Melamine for an elegant and durable finish. The table features an 35 mm clear glass top, adding a touch of sophistication to the design. At the bottom of the console, base / vertical members is provided, which is constructed using 50 mm x 50 mm crafted top of bottom. The leak wood is also polished in melamine, allowing you to choose the desired shade to match your interior decor. This Wooden console combines the natural beauty of teak wood with the practicality of a Teak Wooden top and curve edges.	1.00	Nos.		
3	8.0 MM thk glass on top of officers tables. All the edges of the glass shall be grinded polished including Hole for cable manager. Make - Saint Gobain / TATA / Asahi	655.00	Sft.		
4	Side Credenza with three Drawers Providing & fixing Side credenza (15" to 18" deep) made of 19 mm thick commercial ply and 6 mm thick plywood on back side & finished with 1.0 mm thk. laminate of approved colour on top horizontal surface & vertical visible side only, with teak wood lipping on all edges including bottom touching floor. The credenza will have three lockable drawers, horizontally running on side mounting drawer slides /channels. The remaining part of the credenza will have cupboard with shutters and one shelf. The shutters with handle / knob and magnetic catcher shall be provided beneath the drawers all Non-Visible / inside surfaces i.e. inside of drawer / cupboard shelf etc. shall be finished liner / laminate of 0.7 to 0.8 mm thk. off white / white colour and teak wood edges / lipping / beading shall be Spirit polished with matching pigment. Makes - Telescopic Channel - Ebco / Haffele / Godrej / Ozone / Door set / Herison), Locks - Godrej / Hettich / Dorma / Ozone / herison / doorset / plaza, Plywood Make: ISI marked BMR-IS 303.				
a	Officer's & Staff side credenza as per Drawing & specification mention in item above. Size - 3'-6" / 4'-0" X 1'-6" / 1'-3" X 2'-6" (W X D X H)	360.00	Sft		

Subject	Proposed Interiors for State Bank of India, Regional Business Office - IV, at Fourth Floor, Sheranwala Gate, The Mall, Patiala, Distt. Patiala. (Pb).				
	BOQ				
S.No	ITEM	QTY	UNIT	RATE	AMOUNT
5	Back credenza / Storage Providing & fixing back credenza 18" deep (top surface 18" to 24" as per site) & 3'0" HT. made of 19 mm thick commercial ply and 6.0 mm thick plywood on back side & finished with 1.0 mm thk. laminate of approved colour on top horizontal surface & vertical visible side only, with teak wood lipping on all edges including bottom touching floor. The back credenza will have cupboard with shutters and one shelf. The shutters with handle and magnetic catcher shall be provided beneath the drawers and Non-Visible / inside surfaces i.e. inside of cupboard & shelves shall be finished liner of 0.7 to 0.8 mm thk. off white / white colour and teak wood edges / lipping / beading shall be Spirit polished with matching pigment. Makes - Telescopic Channel - Ebco / Haffele / Godrej / Ozone / Door set / Herison), Locks - Godrej / Hettich / Dorma / Ozone / herison / doorset / plaza, Plywood Make: ISI marked BMR-IS 303.	1250.00	Sft.		
6	False Ceiling - (Mineral Fibre- Armstrong Dune supreme.) Providing and fixing false ceiling at all heights, made of 600 mm X 600 mm X 16 mm, RH 99 mineral fibre ceiling tiles of type – Fine Fissured micro lock with silhouetted grid (black reveal), Tegular edge, laid on manufacturer exposed grid systems. The frame work comprises of main rubber spaced at 1200 mm c/c, securely fixed to the structural soffit by approved hangers of spacing not more than 1200 mm c/c. Hangers (required G.I. wire of 4 mm dia.) to be fixed by approved rawl plugs, level adjusters & screws etc. The last hanger at end of each main runner should not be more than 450 mm from the adjacent wall.	3100.00	Sft		
	Flush fitting 1200 mm long Cross T's (with double stitching) to be interlocked between main runners at 600 mm c/c to form 1200 mm X 600 mm modules. Cut cross T's longer than 600 mm to be supported independ-ently. 600 mm X 600 mm modules to be formed by fitting 600 mm long flush fitting cross T's centrally between the 1200 mm Cross T's. The rates shall be inclusive of making opening with frame, removal of existing false ceiling & disposal to dumping site etc. for electrical / air conditioner & finishing of ceiling in all respect, the work includes provision of trap door if required. Make - Armstrong / Unidus / Diamond.				
7	False Ceiling With Steps. & Cove - Gypsum Board Providing and fixing suspended false ceiling (as per specification of manufacture) including steps as per design with 12.5 mm tapered edge Gyp-board / 12 mm thick Elephant Gypsum Board to the grid comprising of cold rolled galvanized metal section to the required line and level. The grid consists of a perimeter channel (MF6a of dimensions 20 mm X 27 mm X 37 mm X 3.5 M) fixed round the perimeter to receive and of the ceiling section (MF5) and the outer edges to gyp-board. The intermediate channel (MF7 of dimensions 15 mm X 45 mm X 0.9 mm X 3.6 M) at 1200 mm c/c in the one direction and the ceiling section (MF5 of dimensions 80 mm X 26 mm X 0.5 mm X 3.6 M) at 450 mm c/c in the other direction are connected by a connecting clip (MF9).	5100.00	Sft.		

Subject	Proposed Interiors for State Bank of India, Regional Business Office - IV, at Fourth Floor, Sheranwala Gate, The Mall, Patiala, Distt. Patiala. (Pb).				
	BOQ				
S.No	ITEM	QTY	UNIT	RATE	AMOUNT
	The grid is suspended with an adjustable strap hanger (MF8) of dimensions 25 mm X 0.5 mm at 1200 mm c/c on both ways from the structural soffit using a soffit cleat and expandable bolts / fasteners Nut and bolts are used to connect strap hangers to soffit cleats and for joining ends of channel sections together. The gypsum board layers are screwed to the M/F ceiling sections with gyp-board drywall screws. Jointing and screw spotting are then carried out as per manufacturer's standard recommendations. Perimeter Channels (MF7) to be used around the cut outs for light fittings. A/C ducting etc. The work should be complete as per instructions of Architect or Engineer in charge. The rates should be inclusive of two or more coats of plastic emulsion over a coat of primer to give an even shade & removal of existing false ceiling & disposal to dumping site.				
	The rate should be inclusive of making opening with frame etc. for electrical / air conditioner, A.C. grills & trap door etc. if required & finishing of ceiling in all respect. Steps / Vertical bands / cove shall be measured in square feet. Payments shall be made only for exposed surfaces & actual measurement at site. The work includes cost and conveyance of materials and labour charges including. All operational charges, tools, lifts and all heights etc. Make - Gyproc / Saint Gobain / India Gypsum & USG Boral.				
8	Extra for cove over gypsum board false ceiling. Providing and fixing cove in suspended false ceiling as instructed including all required sections / parameters & labour as per mentioned above. Measurement shall be made from bottom external band only.	680.00	Rft.		
9	Full Height Partitions with etching on glasses. - Solid / partially glazed/ flush door with frame in partitions. Providing and fixing partition made of 50 mm X 25 mm X 16 Gauge aluminium extruded sections @ 16" c/c vertically & horizontally. The aluminium extruded sections frame shall be fixed rigidly at floor level as well as ceiling with rawl plugs / steel lugs. The frame work to be clad with 8.0 mm thick commercial ply & required flexible ply for the curve and finished with 1.0 mm thk. of approved laminate as per pattern on both sides upto 3'0" height and above 7'0" height and 5.00 mm thick glass with etching as per design fixed with teak wood moldings above 3'0" height and upto 7'0" height. The skirting shall be finished with 1.0 mm thk brushed steel finish laminate. Work also includes providing and fixing of door with frame as per drawing and specifications & making of stencils / ferma for the curves. All teak veneer / ply / wood to be treated with wood preservatives of approved ISI quality.	1250.00	Sft.		
	All wood shall be finished with high gloss spirit polished of approved shade. The rate shall also include for providing grooves in Laminate / veneer. All job to be done to Architect's satisfaction / as per bank direction. Measurements to be taken upto false ceiling level & Payments shall be made only for exposed surfaces & actual measurement at site, no payment shall be made above false ceiling. Plywood Make: ISI marked BMR-IS 303.				

Subject	Proposed Interiors for State Bank of India, Regional Business Office - IV, at Fourth Floor, Sheranwala Gate, The Mall, Patiala, Distt. Patiala. (Pb).				
	BOQ				
S.No	ITEM	QTY	UNIT	RATE	AMOUNT
10	Low Height Partition with etching on glasses (Height + 4'-0" / 5'0") Providing and fixing Low Height Partition made of 50 mm X 25 mm X 16 Gauge aluminium extruded sections @ 16" c/c vertically & horizontally. The aluminium extruded sections frame shall be fixed rigidly at floor level with rawl plugs / steel lugs / screw. The frame work to be clad with 8.0 mm thick commercial ply and finished with 1.0 mm thk. approved laminate as per pattern on both side's upto 4'0" height. The skirting shall be finished with 1.0 mm thk brushed steel finish laminate. All teak veneer / ply / wood to be treated with wood preservatives of approved ISI quality. All teak veneer / ply / wood shall be finished with high gloss spirit polished of approved shade. The work includes the cost of D - brackets for fixing the required glass within the partitions.	1500.00	Sft.		
11	Paneling to Wall & to Ceiling Providing and fixing paneling over the existing wall made out of framework of 50 mm X 25 mm - 18 gauge section un anodised Aluminium (as per requirement) frame work @ 16" to 24" c/c vertically & horizontally & Frame work for bands - 3" / 6" / 9" / 12" & 15" as required paid in sq. feet. The frame work to be clad with 8.0 mm thick commercial ply and following finishings as per drawing and instructions. All exposed surfaces to be clad with teakwood moulding of size 35 mm X 8.0 mm made to shape. The work should be complete in all respects including provisions of grooves duly designed & finished. All wood to be treated with wood preservatives of approved ISI quality. All exposed teak wood shall be spirit polished with matching pigment. The rate shall include for providing grooves in laminate & wood. Payments shall be made only for exposed surfaces & actual measurement at site, no payment shall be made for paneling behind furniture such as tables, Credenza , storage etc.				
i.	Panelling finished with 1.0 mm thk. Approved shade & colour laminate.	2000.00	Sft.		

Subject	Proposed Interiors for State Bank of India, Regional Business Office - IV, at Fourth Floor, Sheranwala Gate, The Mall, Patiala, Distt. Patiala. (Pb).				
	BOQ				
S.No	ITEM	QTY	UNIT	RATE	AMOUNT
ii	Panelling with veneer / pine wood to wall & Ceiling (including suspensions) Providing & fixing 4 MM thk. Veneer / pine wood ledge (pine wood ledge - size 60 mm to 150 mm wide & 2500 mm length) of approved shade & colour made to design & desired grooves / patterns with fram work as mentioned above including required wooden framework made of hard wood, soft wood, commercial board & ply of required size & thickness finished with 4 mm thk venner over 8.0 mm thk commercial ply & The Veneer needs to be prepared sanded and malamine polish. The wotk includes all kind of coves & provisions of LED lights. The rate should be inclusive of making Coves for provision of LED / lighting / opening with frame etc. for electrical / air conditioner, A.C. grills & trap door etc. venner / pine wood ledge & Cove (s) / Steps / Vertical bands / shall be measured in square feet. Payments shell be made only for exposed surfaces & actual measurement at site. The work includes cost and conveyance of materials and labour charges including. All operational charges,tools, lifts and all heights etc. Basic rate of Veneer Rs. 120 /sft.	1150.00	Sft.		
iii	Extra for providing veneer with polish in ceiling - Providing and fixing 4mm thk. Veneer in ceiling over 8mm thk. commercial ply screwed to GI ceiling sections / aluminium (as per requirement) frame work work as item number above (8 / 11).The work includes providing grooves as per pattern, spirit polished of approved shade on the veneer surface. Payment shall be made for the visble finished area. The work should be complete as per instructions of Architect or Engineer in charge.	850.00	Sft.		
iv	Charcoal fluted / Lovers Paneling to Wall & to Ceiling. Providing and fixing paneling over the existing wall made out of framework of 50 mm X 25 mm - 18 gauge section un annodised Aluminium (as per requirement) frame work @ 16" to 24" c/c vertically & horizontally & Frame work for bands - 3" / 6" / 9" /12" & 15" as required paid in sq. feet. The frame work to be clad with 8.0 mm thick commercial ply and finishiged with Charcoal fluted / Lovers Panells as per instructions. All exposed surfaces to be clad with teakwood moulding of size 35 mm X 8.0 mm made to shape. The work should be complete in all respects including provisions of grooves duly designed & finished. All wood to be treated with wood preservatives of approved ISI quality. All exposed teak wood shall be spirit polished with matching pigment. The rate shall include for providing groves in laminate & wood. Payments shell be made only for exposed surfaces & actual measurement at site, no payment shell be made for paneling behind furniture such as tables, Credenza , storage etc.	250.00	Sft.		

Subject	Proposed Interiors for State Bank of India, Regional Business Office - IV, at Fourth Floor, Sheranwala Gate, The Mall, Patiala, Distt. Patiala. (Pb).				
	BOQ				
S.No	ITEM	QTY	UNIT	RATE	AMOUNT
12	Flush door with teak wood frame / chockhet to Opening : Providing and fixing Flush door, the work to include providing and fixing of partly glazed wooden door shutters using 35mm readymade ISI flush door shutter with 1.0mm thick laminate of desired shade / textures / gloss as per drawing with Hard wood frame of 100mm x 65mm. The door shall have 6.0 mm thick teak wood lipping all around the edges. he door shall have vision panels with 5.0 mm thick clear float glass with etching fixed with double 14 mm x 25 mm thick teak wood moulding as per design. The exposed surface of wood shall be Sprit polished (natural) / desired shade. The door shall be complete in all respect with hardware handles, door stoppers, 8" tower bolts - 2 Nos, hinges etc all in brass.	260.00	Sft.		
13	Toughened Glass 12.0 mm thk. with etching including all / as per given below	650.00	Sft.		
i.	12 MM thk. toughend glass for Banking / SWO Counters with Etching. - front & Sides. Providing and fixing 12 mm thick, clear plain toughend glass of fixed in vertical position at counter level & to side partitions as per drawing, the counter top glass fixed on both sides to toughned glass partitions & side partitions fixed to wooden partition with superior quality stainless steel L - shaped clamps / glass holders 2 no. on both sides. A 6" dia. semi circular hole at the bottom for transaction shall be provided. All the edges of the glass shall be grinded polished and left free. Make - Saint Gobain / TATA / Asahi.				
ii	Main Entrance Door for B.O, E - corner & BM - Toughened Glass 12.0 mm thk. with etching Providing & fixing frameless fully glazed 12.0 mm thk. toughend float glass single leaf glazed Toughned door of size approximately, 1800 to 700 mm X 2400 / 2100 mm all sides (as per drg. / instructions) edge grainded, polished to be fixed on patch fittings, the door to be to be fitted horizontally / vertically as per instructions. The cost including cutting, making holes, cutouts in glass of required shape and size to accomodate fitting etc. the rate shall be include nessessery etching film / logo all inclusive, complete.				
iii	Fixed Glass / Glazing / Partition - Toughened Glass 12.0 mm thk. with etching. Providing & fixing frameless fully glazed 12.0 mm thk. toughend float glass of size - as per site all sides edge grainded, polished to be fixed with necessary patch fittings (godrej / dorma) the glazing to be to be fitted horizontally / vertically as per instructions. The cost including cutting, making holes, cutouts in glass of required shap and size to accomodate fittings and fixing the fixtures, screws, sealant wherever required and SS cover over patch fittings, etc. the rate shall be include nessessery etching film / logo all inclusive, complete.				
iv	The modesty guard to officials Tables shall be finished with 12.0 mm thk. toughed glass in 3" / 4" wide S.S. Spacer.				

Subject	Proposed Interiors for State Bank of India, Regional Business Office - IV, at Fourth Floor, Sheranwala Gate, The Mall, Patiala, Distt. Patiala. (Pb).				
	BOQ				
S.No	ITEM	QTY	UNIT	RATE	AMOUNT
14	Providing & Fixing of (Make : DORMA) Automatic Door Operator for 12mm Plain toughened glass opening (all sizes as per site) single / both side sliding shutters.	1.00	Nos.		
	Supply & Installation of Fully Automatic Sliding door operator (Dorma ES 200 Easy), compliant with future European standards and produced according to the guidelines for power-operated windows, doors and gates BGR 232, the UVV and the VDE regulations. TÜV design tested, tested according to the low voltage guidelines, production according to ISO 9001:2000 certification. Fulfils the DIN V18650 (prEN 12650).				
	Automatic Sliding Door Operator should have mounting backplate for easy installation and a flexible track profile for improved noise & vibration dampening and easy maintenance. Microprocessor-controlled control unit. Self-learning, with adjustable parameters for opening and closing speed, hold-open time and opening and closing force. Class of protection IP 20.				
	DORMA ES200 EASY 4150mm Operators are of very sturdy design with Self balancing Panel suspension system and with Anti-Jump fitting with clear passage width of 2000 mm SD (Two shutters of equal width) and clear height of 2400 mm .Door Panel weight max 2x100 kg. With the following accessories				
	Function programs: Program Modes: - Off, Automatic, Permanent open, Exit only, Partial open. Adjustable Hold Open Time: Hold Open is easily adjustable at module as per client's requirement, Hold Open Time: 0.5 – 30 Sec. Adjustable Parameters Via parameter display and selection key at electronic module. Adjustable Opening Speed: 10 -50 Cm/S, Adjustable Closing Speed: 10 – 40 Cm/S, Auto Error Display, with Error Code Display for error correction. Read-out error store with error codes Emergency off – Connection for Emergency Off Button, On activation Operator will Open Fully and Stop all functions, enabling passenger to pass through in case of Panic.				
	Safety devices:Inbuilt Obstruction detection feature with automatic reversing cycle on obstruction, dynamic and static force limitation, emergency control unit (emergency stop), Safety PhotoCells: 1/ 2 Pair of PhotoCells are provided for safety of passenger standing in line of motion of Moving Panel and for through-passage monitoring Connection: 230 V, 50/60 Hz, UPS Supply. Activators: Radar system 02 Nos, with 24 GHz, Mandatory as Int'Nat Standards, Light barriers, comprising receiver and transmitter -01 Pair				
	Locking: Electro-mechanical locking, Bistable. UPS of 750 VA shall be provided by others, which will give power backup of 20 min. only & if the duration of power cut to the operator is more than 30 min., then separate arrangement for the same as Automatic Operator require un-interpreted stabilized power supply.				

Subject	Proposed Interiors for State Bank of India, Regional Business Office - IV, at Fourth Floor, Sheranwala Gate, The Mall, Patiala, Distt. Patiala. (Pb).				
	BOQ				
S.No	ITEM	QTY	UNIT	RATE	AMOUNT
	Wall / partition Connecting Profile base rail with fixing holes incl. clamping parts with screws and gasket for 12mm glass with cover profile on both sides.				
15	Hardware & Accessories for fixing Toughened Glass doors etc. Providing and fixing the fittings in floors, soffits, jambs including necessary fixtures, screws, sealant wherever required and SS cover over patch fittings to accomodate toughened glass of above items - Hardware - Top pivot, Top patch fitting(s), Bottom patch fitting(s), Corner / Central lock(s) with strike plate, Floor spring, 1'-6" S S door handle (both sides) in door - pair, etc. all complete. Make - Godrej / Ozone / doorset / Dorma.	7.00	Job		
16	Hardware & Accessories for fixing Toughened Glass / glazing etc. Superior quality stainless steel, S.S. Spacer / S.S. glass holders of required size & L - shaped lamps with cover / cap 2 no. on both sides to holding the front glass partition to S.W.Counter & fixed glazing including required glass holes to fix the clamps complete. - ISI marked.	200.00	Nos.		
17	Wall Connecting Profile In Floor / Bottom Providing and fixing wall connecting profile in floor to hold 12mm thk. Toughened glass including gas skid, Rubber & hardware as per manufacturar's specifications to complete the job Material & labour etc. make: Godrej / Ozone / Hyper / Dorset / Hettich / Dorma// Intek Hardwares / Imperia Innovations / Dhariwal Industries / D. I. Interio / Ares Interior & Safety Solutions Inc.	36.00	Rft.		
18	Door Closer - Providing and fixing silver colour (or matching with colour scheme / as per site) hydraulic door closer to Doors complete in all respects. Make - Godrej / Ozone / Hyper / Dorset / Hettich / Dorma .	16.00	Nos.		
19	Mortice Lock -Providing and fixing silver colour (or matching with colour scheme as per site) to Doors complete in all respects. Make - Godrej / ozone / herison / doorset / plaza / Hettich / Dorma.	7.00	Nos.		
20	Painting Work – Texture Paint with white shade over coating Providing and applying special / texture paint with Asian royal matalic finish of approved shade / white & make as per manufacturers specification and architects instructions. payment shall be made only exposed surface of texture paint. No measurement shall be made for texture paint behind paneling, furniture such as tables, Credenza, storage etc. Make - Asian / Spectrum	1500.00	Sft.		
21	Door to UPS / Network rack room including instalation - Size as per existing opening at site - Fire rated steel door including frame - 2 (Two) Hrs Metal test certificate will be provided issued from GQMC.	21.00	Sft.		

Subject	Proposed Interiors for State Bank of India, Regional Business Office - IV, at Fourth Floor, Sheranwala Gate, The Mall, Patiala, Distt. Patiala. (Pb).				
	BOQ				
S.No	ITEM	QTY	UNIT	RATE	AMOUNT
a)	Frame - Providing and fixing fire resistant door frame of section 100 x 50 mm having built in rebate out made up of 1.2 mm GPSP Sheet duly powder coated / 16 SWG G.I. sheet (zinc coating not less than 120 gm / sqm) duly filled with vermiculite based concrete mix, suitable for mounting 120 minutes fire rated door shutters. The frame is fitted with intumescent fire seal strip of size 10 x 4 mm (minimum) around the frame and fixing with dash fastener of approved size and make, including apply a coat of approved brand fire resistant primer etc. complete as per direction of Engineer – in charge (including Dash fastners).				

Subject	Proposed Interiors for State Bank of India, Regional Business Office - IV, at Fourth Floor, Sheranwala Gate, The Mall, Patiala, Distt. Patiala. (Pb).				
	BOQ				
S.No	ITEM	QTY	UNIT	RATE	AMOUNT
b)	Shutter - Providing and fixing Metal Door Shutter 46 mm thk.made up of 0.8mm thick GPSP Sheet. Glazed fire resistant door shutters of 120 minutes fire rating conforming to IS : 3614 (Part – II), tested and certified as per laboratory approved by Engineer – in – charge, with suitable mounting on door frame, the entire shutter filled insulation material / Honeycomb craft paper of 160gsm (zinc coating not less than 120 gm/m2) and fixing with necessary stainless steel ball bearing hinges of approved make,provision of Fire Rated Wired Glass size of glass 300 X 200 including applying a coat of approved fire resistant primer etc. all complete as per direction of Engineer – in charge (paneling to be paid for separately).				
c	Hardware for fixing - Fire rated steel door including frame Providing and fixing following hardware for fixing fire rated steel door including frame, complete. Hinges 4X3X3 (Min. 3Nos), Pull Handle 19 X 250mm - Pair, Dead Lock, Fire Rated Wired Glass size - 300 X 200, Fastners Hilti 10 X 92mm - (Min - 10Nos.).				
22	Electrical panel Niche / covering for branch with lining of Bison board. Providing and fixing electrical niche upto 18" to 24" deep as per drawing / instructions with outer frame made of 19 mm thick commercial ply with 1.0 mm thick laminate on all outer visible surfaces as per pattern / design / Battens for ventilation. The inner surfaces shall be finished with Bison board, on the inner face of the panel box. Work also includes providing and fixing of doors as per drawing and specifications. All wood to be treated with wood preservatives of approved ISI quality. All exposed teak wood shall be spirit polished with matching pigment. The rate shall also include for providing groves in laminate & wood, hardware like hinges, handles, chitkney & locks etc. The work should be done to the entire satisfaction of the Architect / Engineer. For measurements front shall be measured.	65.00	Sft.		
23	Planter Housing Providing and supplying planter housing of overall size (3'0"L X 1'6"W X 1'6"H) / (3'0"L / 1'6"L X 1'6"W X 3'0"H) as per drawing & design - made to shaped with outer frame made of 19 mm thick commercial block board with 1.0 mm laminate on all outer visible surfaces. The inner surfaces of planter housing / box shall be lined / claded with 1.0 mm laminate or with aluminium sheet . All the exposed edges of board shall be provided with teak wood lipping of 12 mm thick and teak wood edges / lipping / beading shall be spirit polished natural / as per instructions with matching pigment to the satisfaction of the Architect / Engineer.	10.00	Nos.		
	Total (A)				
	GST extra as per applicable				