

| Subject     | <b>Proposed Interiors / renovation work of State Bank of India, Branch Office – Surajpur at Amravati Enclave, Panchkula, (Hry.). Br. Code – 01579.</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |            |             |             |               |
|-------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------|-------------|-------------|---------------|
|             | <b>BOQ</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |            |             |             |               |
| <b>S.No</b> | <b>ITEM</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        | <b>QTY</b> | <b>UNIT</b> | <b>RATE</b> | <b>AMOUNT</b> |
|             | <b>Interiors / Furnishing &amp; Associated civil work</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |            |             |             |               |
| 1           | <b>Single Level SWO Counters</b><br>Providing and fixing at site SWO counters each upto 5'0" long, 2'6" high and 3'0" wide, as per design and drawing. SWO counters to be made of 19 mm thick commercial ply with 1.0 mm thick laminate on outer visible surfaces (single color on horizontal surface & two colors on vertical surfaces), with 40 mm X 12 mm thick teak wood beading required all around, as per drawing. Provision for 3" dia. round / 3" square cable manager for computer / electrical cables at appropriate place will be made in the top surface of the counter. The top with Curvilinear profile shall be made out of 19mm thk. commercil ply and finished with 6mm thk. flexi ply as base for acrylic sheet as per design with provision for LED Light in bottom. Teak wood lipping will be provided on all the remaining edges of the counter, including bottom touching the floor and the drawers. The counter shall have a keyboard tray of size 600 X 270 finished with laminate on top side with back support, fixed on channels, as per manufacturer's instructions / specifications. | 15.00      | Rft.        |             |               |
|             | Three drawers with autolock running on both sides mounting Telescopic (channels), made of 19 mm thick commercial ply with 1.0 mm thick laminate on front face and drawer locks to be provided on one side of the counter as per layout. The sides of the drawers shall be made of 12 mm thick plywood, bottom of 6 mm thick plywood & front of 19 mm thick commercial ply. Non-Visible / inside surfaces i.e. inside / leg-space of table, inside of drawer / cupboard shall be finished with liner / laminate of 0.7 to 0.8 mm thk. off white / white colour and all exposed Teak wood edges / teak wood lipping beading shall be spirit (natural) polish as required. The drawers shall have partitions for keeping currency notes & the counter should also includes foot rest, Space for CPU as per drawing, complete in all respects. Makes - Telescopic Channel - Ebco / Haffele / Godrej / Ozone / Door set / Herrison), Locks - Godrej / Hettich / Dorma / Ozone / herrison / doorset / plaza, Plywood Make: ISI marked BMR-IS 303.                                                                        |            |             |             |               |
| 2           | Providing & fixing 12 mm thk. Solid Surfaces (Acrylic Sheet) on counter top & required vertical position made to shaped for Single window Counter at transaction level as per design and approved colour (White).<br>Make: LG / Samsung / Gravia / Granimum.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       | 95.00      | Sft.        |             |               |

| Subject | Proposed Interiors / renovation work of State Bank of India, Branch Office – Surajpur at Amravati Enclave, Panchkula, (Hry.). Br. Code – 01579.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |       |      |      |        |
|---------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|------|------|--------|
|         | BOQ                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |       |      |      |        |
| S.No    | ITEM                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        | QTY   | UNIT | RATE | AMOUNT |
| 3       | <b>Officer's &amp; Staff Tables</b><br>Table made of 19 mm thk. Commercial ply with Table Top, front and side visible vertical surfaces to be finished with 1.0 mm thk. laminate of approved colour & shade, with 40 mm X 12 mm thick teak wood all around, as per drawing. The front of the table top shall be projected as per drawing. Provision for 3" dia. round / 3" square cable manager for computer / electrical cables at appropriate place will be made in the top surface of the table. The wood lipping will be provided on all the edges of the table, including bottom touching the floor and the drawers. The table shall have a key board tray of size 600 X 270 fixed on channels finished with laminate, as per manufacturers instructions / specifications.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |       |      |      |        |
|         | A full depth CPU shelf 15" wide shall be provided at left hand side of counter underneath the working top, at 4" above the floor level and 3" away (horizontally), from vertical end which will be made of 19 mm thick commercial ply finished with 1.0 mm thk. laminate and ¾" x ¼" teakwood lipping on all visible sides. One drawer with lock and one cupboard with shutter made of 19 mm commercial ply with 1.0 mm laminate on front side of cupboard shutter with shutter having good quality locks, magnetic catcher, hinges, handle / knob etc. is to be provided. The shutters shall be provided beneath the drawers with each counter on its right / left hand side. The sides of the drawer shall be made of 12 mm thick plywood / 19 mm ply, bottom of 6 mm thick plywood & front of 19 mm thick ply. A full length foot rest made of hard wood 3" x 2" section shall be provided at 4" above floor level. Non-Visible / inside surfaces i.e. inside / leg-space of table, inside of drawer / cupboard shall be finished liner of 0.7 to 0.8 mm thk. off white / white colour and teak wood edges / lipping / beading shall be spirit (natural) polish. Make - Saint Gobain / TATA / Asahi<br>Makes - Telescopic Channel - Ebco / Haffele / Godrej / Ozone / Door set / Herison), Locks - Godrej / Hettich / Dorma / Ozone / herison / doorset / plaza,<br>Plywood Make: ISI marked BMR-IS 303. |       |      |      |        |
| a       | C.M. / B.M. - Size 6'0" X 3'0" X 2'6"                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       | 1.00  | Nos. |      |        |
| b       | O.T. / S.T. - Size - 5'0" / 4'9" X 2'6" X 2'6"                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              | 2.00  | Nos. |      |        |
| 4       | <b>8.0 MM thk glass on top of officers tables.</b> All the edges of the glass shall be grinded polished including Hole for cable manager. Make - Saint Gobain / TATA / Asahi                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                | 43.00 | Sft. |      |        |

| Subject     | <b>Proposed Interiors / renovation work of State Bank of India, Branch Office – Surajpur at Amravati Enclave, Panchkula, (Hry.). Br. Code – 01579.</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |            |             |             |               |
|-------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------|-------------|-------------|---------------|
|             | <b>BOQ</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |            |             |             |               |
| <b>S.No</b> | <b>ITEM</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       | <b>QTY</b> | <b>UNIT</b> | <b>RATE</b> | <b>AMOUNT</b> |
| 5           | <b>Side Credenza</b><br>Providing & fixing Side credenza ( 15" to 18" deep ) made of 19 mm thick commercial ply and 6 mm thick plywood on back side & finished with 1.0 mm thk. laminate of approved colour on top horizontal surface & vertical visible side only, with teak wood lipping on all edges including bottom touching floor. The credenza will have three lockable drawers, horizontally running on side mounting drawer slides /channels. The remaining part of the credenza will have cupboard with shutters and one shelf. The shutters with handle / knob and magnetic catcher shall be provided beneath the drawers all Non-Visible / inside surfaces i.e. inside of drawer / cupboard shelf etc. shall be finished liner / laminate of 0.7 to 0.8 mm thk. off white / white colour and teak wood edges / lipping / beading shall be Spirit polished with matching pigment.<br>Makes - Telescopic Channel - Ebco / Haffele / Godrej / Ozone / Door set / Herison), Locks - Godrej / Hettich / Dorma / Ozone / herison / doorset / plaza,<br>Plywood Make: ISI marked BMR-IS 303. |            |             |             |               |
| a           | Officer's & Staff side credenza as per Drawing & specification mention in item above. Size - 3'-6"/ 4'-0" X 1'-6"/1'-3" X 2'-6" (W X D X H)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       | 30.00      | Sft         |             |               |
| 6           | <b>Back credenza / Storage</b><br>Providing & fixing back credenza 18" deep (top surface 18" to 24" as per site) & 3'0" HT. made of 19 mm thick commercial ply and 6.0 mm thick plywood on back side & finished with 1.0 mm thk. laminate of approved colour on top horizontal surface & vertical visible side only, with teak wood lipping on all edges including bottom touching floor. The back credenza will have cupboard with shutters and one shelf. The shutters with handle and magnetic catcher shall be provided beneath the drawers and Non-Visible / inside surfaces i.e. inside of cupboard & shelves shall be finished liner of 0.7 to 0.8 mm thk. off white / white colour and teak wood edges / lipping / beading shall be Spirit polished with matching pigment.<br>Makes - Telescopic Channel - Ebco / Haffele / Godrej / Ozone / Door set / Herison), Locks - Godrej / Hettich / Dorma / Ozone / herison / doorset / plaza,<br>Plywood Make: ISI marked BMR-IS 303.                                                                                                           | 150.00     | Sft.        |             |               |
| 7           | <b>False Ceiling - (Mineral Fibre- Fine Fissured /Armstrong Dune supreme.)</b><br>Providing and fixing false ceiling at all heights, made of 600 mm X 600 mm X 16 mm, RH 99 mineral fibre ceiling tiles of type – Fine Fissured / Dune supreme micro lock with silhouetted grid (black reveal), Tegular edge, laid on manufacturer exposed grid systems. The frame work comprises of main rubber spaced at 1200 mm c/c, securely fixed to the structural soffit by approved hangers of spacing not more than 1200 mm c/c. Hangers (required G.I. wire of 4 mm dia.) to be fixed by approved rawl plugs, level adjusters & screws etc. The last hanger at end of each main runner should not be more than 450 mm from the adjacent wall.                                                                                                                                                                                                                                                                                                                                                           | 620.00     | Sft         |             |               |

| Subject     | <b>Proposed Interiors / renovation work of State Bank of India, Branch Office – Surajpur at Amravati Enclave, Panchkula, (Hry.). Br. Code – 01579.</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |            |             |             |               |
|-------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------|-------------|-------------|---------------|
|             | <b>BOQ</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |            |             |             |               |
| <b>S.No</b> | <b>ITEM</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   | <b>QTY</b> | <b>UNIT</b> | <b>RATE</b> | <b>AMOUNT</b> |
|             | Flush fitting 1200 mm long Cross T's (with double stitching) to be interlocked between main runners at 600 mm c/c to form 1200 mm X 600 mm modules. Cut cross T's longer than 600 mm to be supported independ-ently. 600 mm X 600 mm modules to be formed by fitting 600 mm long flush fitting cross T's centrally between the 1200 mm Cross T's. The rates shall be inclusive of making opening with frame, removal of existing false ceiling & disposal to dumping site etc. for electrical / air conditioner & finishing of ceiling in all respect, the work includes provision of trap door if required.<br>Make - Armstrong / Unidus / Diamond.                                                                                                                                                                                                                                          |            |             |             |               |
| 8           | <b>False Ceiling With Steps. &amp; Cove - Gypsum Board</b><br>Providing and fixing suspended false ceiling (as per specification of manufacture) including steps as per design with 12.5 mm tapered edge Gyp-board / 12 mm thick Elephant Gypsum Board to the grid comprising of cold rolled galvanized metal section to the required line and level. The grid consists of a perimeter channel (MF6a of dimensions 20 mm X 27 mm X 37 mm X 3.5 M) fixed round the perimeter to receive and of the ceiling section (MF5) and the outer edges to gyp-board. The intermediate channel (MF7 of dimensions 15 mm X 45 mm X 0.9 mm X 3.6 M) at 1200 mm c/c in the one direction and the ceiling section (MF5 of dimensions 80 mm X 26 mm X 0.5 mm X 3.6 M) at 450 mm c/c in the other direction are connected by a connecting clip (MF9).                                                           | 1200.00    | Sft.        |             |               |
|             | The grid is suspended with an adjustable strap hanger (MF8) of dimensions 25 mm X 0.5 mm at 1200 mm c/c on both ways from the structural soffit using a soffit cleat and expandable bolts / fasteners Nut and bolts are used to connect strap hangers to soffit cleats and for joining ends of channel sections together. The gypsum board layers are screwed to the M/F ceiling sections with gyp-board drywall screws. Jointing and screw spotting are then carried out as per manufacturer's standard recommendations. Perimeter Channels (MF7) to be used around the cut outs for light fittings. A/C ducting etc. The work should be complete as per instructions of Architect or Engineer in charge. The rates should be inclusive of two or more coats of plastic emulsion over a coat of primer to give an even shade & removal of existing false ceiling & disposal to dumping site. |            |             |             |               |
|             | The rate should be inclusive of making opening with frame etc. for electrical / air conditioner, A.C. grills & trap door etc. if required & finishing of ceiling in all respect. Steps / Vertical bands / cove shall be measured in square feet. Payments shall be made only for exposed surfaces & actual measurement at site. The work includes cost and conveyance of materials and labour charges including. All operational charges, tools, lifts and all heights etc. Make - Gyproc / Saint Gobain / India Gypsum & USG Boral.                                                                                                                                                                                                                                                                                                                                                          |            |             |             |               |
| 9           | <b>Extra for cove over gypsum board false ceiling.</b><br>Providing and fixing cove in suspended false ceiling as instructed including all required sections / parameters & labour as per mentioned above. Measurement shall be made from bottom external band only.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          | 240.00     | Rft.        |             |               |

| Subject     | <b>Proposed Interiors / renovation work of State Bank of India, Branch Office – Surajpur at Amravati Enclave, Panchkula, (Hry.). Br. Code – 01579.</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |            |             |             |               |
|-------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------|-------------|-------------|---------------|
|             | <b>BOQ</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |            |             |             |               |
| <b>S.No</b> | <b>ITEM</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    | <b>QTY</b> | <b>UNIT</b> | <b>RATE</b> | <b>AMOUNT</b> |
| 10          | <b>Full Height Partitions with etching on glasses. - Solid / partialy glazed/ flush door with frame.</b><br>Providing and fixing partition made of 50 mm X 25 mm X 16 Gauge aluminium extruded sections @ 16" c/c vertically & horizontally. The aluminium extruded sections frame shall be fixed rigidly at floor level as well as ceiling with rawl plugs / steel lugs. The frame work to be clad with 8.0 mm thick commercial ply and finished with 1.0 mm thk. of approved laminate as per pattern on both sides upto 3'0" height and above 7'0" height and 5.00 mm thick glass with etching as per design fixed with teak wood moldings above 3'0" height and upto 7'0" height. The skirting shall be finished with 1.0 mm thk brusshed steel finsih lamiantte. Work also includes providing and fixing of door with frame as per drawing and specifications. All teak veneer / ply / wood to be treated with wood preservatives of approved ISI quality. | 800.00     | Sft.        |             |               |
|             | All wood shall be finished with high gloss spirit polished of approved shade. The rate shall also include for providing groves in Laminate / veneer. All job to be done to Architect's satisfaction / as per bank direction. Measurements to be taken upto false ceiling level & Payments shall be made only for exposed surfaces & actual measurement at site, no payment shall be made above false ceiling.<br>Plywood Make: ISI marked BMR-IS 303.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |            |             |             |               |
| 11          | <b>Low Height Partition with etching on glasses (Height + 4'-0" / 5'0")</b><br>Providing and fixing Low Height Partition made of 50 mm X 25 mm X 16 Gauge aluminium extruded sections @ 16" c/c vertically & horizontally. The aluminium extruded sections frame shall be fixed rigidly at floor level with rawl plugs / steel lugs / screw. The frame work to be clad with 8.0 mm thick commercial ply and finished with 1.0 mm thk. approved laminate as per pattern on both side's upto 4'0" height. The skirting shall be finished with 1.0 mm thk brusshed steel finsih lamiantte. All teak veneer / ply / wood to be treated with wood preservatives of approved ISI quality. All teak veneer / ply / wood shall be finished with high gloss spirit polished of approved shade. The work includes the cost of D - brackets for fixing the required glass within the partitions.                                                                          | 100.00     | Sft.        |             |               |

| Subject     | <b>Proposed Interiors / renovation work of State Bank of India, Branch Office – Surajpur at Amravati Enclave, Panchkula, (Hry.). Br. Code – 01579.</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |            |             |             |               |
|-------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------|-------------|-------------|---------------|
|             | <b>BOQ</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |            |             |             |               |
| <b>S.No</b> | <b>ITEM</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                | <b>QTY</b> | <b>UNIT</b> | <b>RATE</b> | <b>AMOUNT</b> |
| 12          | <b>Paneling to Wall &amp; to Ceiling</b><br>Providing and fixing paneling over the existing wall made out of framework of 50 mm X 25 mm - 18 gauge section unannodised Aluminium ( as per requirement ) frame work @ 16" to 24" c/c vertically & horizontally & Frame work for bands - 3" / 6" / 9" / 12" & 15" as required paid in sq. feet. The frame work to be clad with 8.0 mm thick commercial ply and following finishings as per drawing and instructions. All exposed surfaces to be clad with teakwood moulding of size 35 mm X 8.0 mm made to shape. The work should be complete in all respects including provisions of grooves duly designed & finished. All wood to be treated with wood preservatives of approved ISI quality. All exposed teak wood shall be spirit polished with matching pigment. The rate shall include for providing grooves in laminate & wood. Payments shall be made only for exposed surfaces & actual measurement at site, no payment shall be made for paneling behind furniture such as tables, Credenza , storage etc.                                                                         |            |             |             |               |
| i.          | Panelling finished with 1.0 mm thk. Approved shade & colour laminate.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      | 600.00     | Sft.        |             |               |
| ii          | Panelling with veneer / pine wood to wall & ceiling<br>Providing & fixing 4 MM thk. Veneer / pine wood ledge (pine wood ledge - size 60 mm to 150 mm wide & 2500 mm length) of approved shade & colour made to design & desired grooves / patterns with frame work as mentioned above including required wooden framework made of hard wood, soft wood, commercial board & ply of required size & thickness finished with 4 mm thk veneer over 8.0 mm thk commercial ply & The Veneer needs to be prepared sanded and malamine polish. The work includes all kind of coves & provisions of LED lights. The rate should be inclusive of making Coves for provision of LED / lighting / opening with frame etc. for electrical / air conditioner, A.C. grills & trap door etc. veneer / pine wood ledge & Cove (s) / Steps / Vertical bands / shall be measured in square feet. Payments shall be made only for exposed surfaces & actual measurement at site. The work includes cost and conveyance of materials and labour charges including. All operational charges, tools, lifts and all heights etc. Basic rate of Veneer Rs. 80 /sft. | 300.00     | Sft.        |             |               |
| iii         | <b>Extra for providing veneer with polish in ceiling -</b><br>Providing and fixing 4mm thk. Veneer in ceiling over 8mm thk. commercial ply screwed to GI ceiling sections / aluminium ( as per requirement) frame work work as item number above ( 8 / 11). The work includes providing grooves as per pattern, spirit polished of approved shade on the veneer surface. Payment shall be made for the visible finished area. The work should be complete as per instructions of Architect or Engineer in charge.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          | 150.00     | Sft.        |             |               |

| Subject     | <b>Proposed Interiors / renovation work of State Bank of India, Branch Office – Surajpur at Amravati Enclave, Panchkula, (Hry.). Br. Code – 01579.</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |            |             |             |               |
|-------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------|-------------|-------------|---------------|
|             | <b>BOQ</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |            |             |             |               |
| <b>S.No</b> | <b>ITEM</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 | <b>QTY</b> | <b>UNIT</b> | <b>RATE</b> | <b>AMOUNT</b> |
| 13          | <b>Flush door with teak wood frame / chockhet to Opening :</b><br>Providing and fixing Flush door, the work to include providing and fixing of partly glazed wooden door shutters using 35mm readymade ISI flush door shutter with 1.0mm thick laminate of desired shade / textures / gloss as per drawing with Hard wood frame of 100mm x 50mm. The door shall have 6.0 mm thick teak wood lipping all around the edges. he door shall have vision panels with 5.0 mm thick clear float glass with etching fixed with double 14 mm x 25 mm thick teak wood moulding as per design. The exposed surface of wood shall be Sprit polished (natural) / desired shade. The door shall be complete in all respect with hardware handles, godrej 6-lever lock / night latch lock, door stoppers, 8" tower bolts - 2 Nos, hinges etc all in brass. | 35.00      | Sft.        |             |               |
| 14          | <b>Writing desk / Customer Voucher Stand / Forms Stand including Pass Book, Cheque Drop &amp; Suggestion Box</b><br>Providing and fixing forms stand of size 4'-0" X 1'-6" X 3'-9" with 3 nos. storage units of forms with 12 mm glass top fixed with 3" SS spacer. Space for housing vouchers of size 1'6" W, 1'-0" D & 9" H is also provided on the top and on side (L-shaped, wall hung) including provision of Pass Book, Cheque Drop & Suggestion Box as per drawings made of 19 mm thick commercial ply with 1.0 mm thick laminate to be fixed and ¾" x ¼" teak wood lipping on two visible sides on it. All exposed Teak wood edges / teak wood lipping / beading shall be spirit polished with matching pigment. etc. & to be fixed on the wall cost of spacers ect all inclusive complete.<br>Plywood Make: ISI marked BMR-IS 303. | 1.00       | Nos.        |             |               |
| 15          | <b>Toughened Glass 12.0 mm thk. with etching including all / as per given below</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         | 350.00     | Sft.        |             |               |
| i.          | 12 MM thk. toughend glass for Banking / SWO Counters with Etching. - front & Sides.<br>Providing and fixing 12 mm thick, clear plain toughend glass of fixed in vertical position at counter level & to side partitions as per drawing, the counter top glass fixed on both sides to toughned glass partitions & side partitions fixed to wooden partition with superior quality stainless steel L - shaped clamps / glass holders 2 no. on both sides. A 6" dia. semi circular hole at the bottom for transaction shall be provided. All the edges of the glass shall be grinded polished and left free. Make - Saint Gobain / TATA / Asahi.                                                                                                                                                                                               |            |             |             |               |
| ii          | Main Entrance Door for B.O, E - corner & BM - Toughened Glass 12.0 mm thk. with etching<br>Providing & fixing frameless fully glazed 12.0 mm thk. toughend float glass single leaf glazed Toughned door of size approximately, 1800 to 700 mm X 2400 / 2100 mm all sides (as per drg. / instructions) edge grainded, polished to be fixed on patch fittings, the door to be to be fitted horizontally / vertically as per instructions. The cost including cutting, making holes, cutouts in glass of required shape and size to accomodate fitting etc. the rate shall be include nessessery etching film / logo all inclusive, complete.                                                                                                                                                                                                  |            |             |             |               |

| Subject     | <b>Proposed Interiors / renovation work of State Bank of India, Branch Office – Surajpur at Amravati Enclave, Panchkula, (Hry.). Br. Code – 01579.</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |            |             |             |               |
|-------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------|-------------|-------------|---------------|
|             | <b>BOQ</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |            |             |             |               |
| <b>S.No</b> | <b>ITEM</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   | <b>QTY</b> | <b>UNIT</b> | <b>RATE</b> | <b>AMOUNT</b> |
| iii         | Fixed Glass / Glazing / Partition - Toughened Glass 12.0 mm thk. with etching.<br>Providing & fixing frameless fully glazed 12.0 mm thk. toughend float glass of size - as per site all sides edge grained, polished to be fixed with necessary patch fittings (godrej / dorma) the glazing to be to be fitted horizontally / vertically as per instructions. The cost including cutting, making holes, cutouts in glass of required shap and size to accomodate fittings and fixing the fixtures, screws, sealant wherever required and SS cover over patch fittings, etc. the rate shall be include nessessery etching film / logo all inclusive, complete. |            |             |             |               |
| iv          | The modesty guard to officials Tables shall be finished with 12.0 mm thk. toughed glass in 3" / 4" wide S.S. Spacer.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |            |             |             |               |
| 16          | <b>Hardware &amp; Accessories for fixing Toughened Glass doors etc.</b><br>Providing and fixing the fittings in floors, soffits, jambs including necessary fixtures, screws, sealant wherever required and SS cover over patch fittings to accomodate toughened glass of above items - Hardware - Top pivot, Top patch fitting(s), Bottom patch fitting(s), Corner / Central lock(s) with strike plate, Floor spring, 1'-6" S S door handle (both sides) in door - pair, etc. all complete. Make - Godrej / Ozone / doorset / Dorma.                                                                                                                          | 4.00       | Job         |             |               |
| 17          | <b>Hardware &amp; Accessories for fixing Toughened Glass / glazing etc.</b><br>Superior quality stainless steel, S.S. Spacer / S.S. glass holders of required size & L - shaped lamps with cover / cap 2 no. on both sides to holding the front glass partition to S.W.Counter & fixed glazing including required glass holes to fix the clamps complete. - ISI marked.                                                                                                                                                                                                                                                                                       | 40.00      | Nos.        |             |               |
| 18          | <b>Wall Connecting Profile In Floor / Bottom</b><br>Providing and fixing wall connecting profile in floor to hold 12mm thk. Toughened glass including gas skid, Rubber & hardware as per manufacturar's specifications to complete the job Material & labour etc. make: Godrej / Ozone / Hyper / Dorset / Hettich / Dorma// Intek Hardwares / Imperia Innovations / Dhariwal Industries / D. I. Interio / Ares Interior & Safety Solutions Inc.                                                                                                                                                                                                               | 30.00      | Rft.        |             |               |
| 19          | <b>Door Closer</b> - Providing and fixing silver colour (or matching with colour scheme / as per site) hydraulic door closer to Doors complete in all respects. Make - Godrej / Ozone / Hyper / Dorset / Hettich / Dorma .                                                                                                                                                                                                                                                                                                                                                                                                                                    | 7.00       | Nos.        |             |               |
| 20          | <b>Mortice Lock</b> -Providing and fixing silver colour (or matching with colour scheme as per site) to Doors complete in all respects. Make - Godrej / ozone / herison / doorset / plaza / Hettich / Dorma.                                                                                                                                                                                                                                                                                                                                                                                                                                                  | 4.00       | Nos.        |             |               |
| 21          | <b>Night latch</b> in cash cabin door - Providing and fixing night latch lock Godrej make in aluminium / wooden doors, complete in all respects.<br>Make - Godrej                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             | 1.00       | Nos.        |             |               |

| Subject     | <b>Proposed Interiors / renovation work of State Bank of India, Branch Office – Surajpur at Amravati Enclave, Panchkula, (Hry.). Br. Code – 01579.</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |            |             |             |               |
|-------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------|-------------|-------------|---------------|
|             | <b>BOQ</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |            |             |             |               |
| <b>S.No</b> | <b>ITEM</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | <b>QTY</b> | <b>UNIT</b> | <b>RATE</b> | <b>AMOUNT</b> |
| 22          | <b>Painting Work – Texture Paint with white shade over coating</b><br>Providing and applying special / texture paint with Asian royal matalic finish of approved shade / white & make as per manufacturers specification and architects instructions. payment shall be made only exposed surface of texture paint. No measurement shall be made for texture paint behind paneling, furniture such as tables, Credenza, storage etc. Make - Terraco / Spectrum                                                                                                                                                                                                                                                                                                                | 150.00     | Sft.        |             |               |
| 23          | <b>Door to UPS / Network rack room including instalation - Size as per existing opening at site -</b><br>Fire rated steel door including frame - 2 (Two) Hrs Metal test certificate will be provided issued from GQMC.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       | 21.00      | Sft.        |             |               |
| a)          | Frame - Providing and fixing fire resistant door frame of section 100 x 50 mm having built in rebate out made up of 1.2 mm GPSP Sheet duly powder coated / 16 SWG G.I. sheet (zinc coating not less than 120 gm / sqm ) duly filled with vermiculite based concrete mix, suitable for mounting 120 minutes fire rated door shutters. The frame is fitted with intumuscent fire seal strip of size 10 x 4 mm (minimum) alround the frame and fixing with dash fastener of approved size and make, including apply a coat of approved brand fire resistant primer etc. complete as per direction of Engineer – in charge (including Dash fastners).                                                                                                                            |            |             |             |               |
| b)          | Shutter - Providing and fixing Metal Door Shutter 46 mm thk.made up of 0.8mm thick GPSP Sheet. Glazed fire resistant door shutters of 120 minutes fire rating conforming to IS : 3614 (Part – II), tested and certified as per laboratory approved by Engineer – in – charge, with suitable mounting on door frame, the entire shutter filled insulation material / Honeycomb craft paper of 160gsm (zinc coating not less than 120 gm/m2) and fixing with necessary stainless steel ball bearing hinges of approved make,provision of Fire Rated Wired Glass size of glass 300 X 200 including applying a coat of approved fire resistant primer etc. all complete as per direction of Engineer – in charge (paneling to be paid for separately).                           |            |             |             |               |
| c           | Hardware for fixing - Fire rated steel door including frame<br>Providing and fixing following hardware for fixing fire rated steel door including frame, complete.<br>Hinges 4X3X3 ( Min. 3Nos), Pull Handle 19 X 250mm - Pair, Dead Lock, Fire Rated Wired Glass size - 300 X 200, Fastners Hilti 10 X 92mm - (Min - 10Nos.).                                                                                                                                                                                                                                                                                                                                                                                                                                               |            |             |             |               |
| 24          | <b>Panelling With ACPWith Aluminium Frames)</b><br>Supplying & fixing 3.0 mm thick Aluminum component sheet of approved make and shade including making of ground of (1"X2") aluminum hollow section as per design, with 6mm-19mm wide vertical or horizontal groove finished with Dow Cowing sealant (789) as per Architect's drawings & instructions aluminum componenet sheet should be of virgin grade and having aluminum profile thickness of 0.5 mm on both sides of core. The rate is inclusive of all fixtures and fittings (with sealent) for proper finish. The works includes front face shutter boxing complete. the rate includes all required shuttering, scaffolding, labour, material, complete. Make - Aluco bond / ALU Décor / Alstrong / Alstone / Alex. | 450.00     | Sft.        |             |               |

| Subject     | <b>Proposed Interiors / renovation work of State Bank of India, Branch Office – Surajpur at Amravati Enclave, Panchkula, (Hry.). Br. Code – 01579.</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |            |             |             |               |
|-------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------|-------------|-------------|---------------|
|             | <b>BOQ</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |            |             |             |               |
| <b>S.No</b> | <b>ITEM</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   | <b>QTY</b> | <b>UNIT</b> | <b>RATE</b> | <b>AMOUNT</b> |
| 25          | <b>Electrical panel Niche / covering for branch with lining of Bison board.</b><br>Providing and fixing electrical niche upto 18" to 24" deep as per drawing / instructions with outer frame made of 19 mm thick commercial ply with 1.0 mm thick laminate on all outer visible surfaces as per pattern / design / Battens for ventilation. The inner surfaces shall be finished with Bison board, on the inner face of the panel box. Work also includes providing and fixing of doors as per drawing and specifications. All wood to be treated with wood preservatives of approved ISI quality. All exposed teak wood shall be spirit polished with matching pigment. The rate shall also include for providing grooves in laminate & wood, hardware like hinges, handles, chitkney & locks etc. The work should be done to the entire satisfaction of the Architect / Engineer. For measurements front shall be measured. | 72.00      | Sft.        |             |               |
| 26          | <b>Repairing of existing wooden- Panelled / flush doors</b><br>Providing and fixing 4.0 mm thk. commercial ply finished with 1.0 mm thk. approved colour laminate to existing solid shutters etc fixed with teak wood moldings as per drawing and specifications. All wood to be treated with wood preservatives of approved ISI quality. All exposed teak wood shall be spirit polished with matching pigment. The rate shall include all hardware required dismantling / removing & refixing with required Hardware etc. to complete the job.                                                                                                                                                                                                                                                                                                                                                                               | 20.00      | Sft.        |             |               |
| 27          | <b>Dismantling of existing all required old material -</b><br>Dismantling of existing all required old material loose & fixed furniture, all kind of partitions, gypsum double skin partition, false ceiling, panelling, AC ductable Units, AC duct required cutting & closed the void / vent of duct matching with existing material, hahging tight the remaining & Repairing.etc. includes disposal of malba from site to unobjectionable place & out side of municipal Limits. The loose furniture shall be arranged at new position as per banks instructions. All old material excluding malba is the property of bank branch hand over to the bank authorities. During the period of of renovation all arrangments shall be made to functional the branch. The work includes partition of system room & UPS including doors & existing doors shall hand over to the Bank.                                               | 1.00       | Job         |             |               |
| 28          | <b>Dismantling</b><br>Dismantling of brick work, R.C.C. work, concrete work, removing of windows & doors for filling of bricks as required size / all kind of openings of any size & disposal of malba from site to unobjectionable place & out side of municipal Limits. No, wood work / furnishing work includes in this item & not to be paid. The precautions have been made while dismantling, so that the flooring shall not be damaged & damaged flooring matched to existing shall be provided on the contractors cost. the work includes to hold tightly all conduites / cables / wires to the roof with required G.I wires / patties.<br>Note - The work includes removing of all the Rolling shutters from the all windows, glazing & grills / All old material excluding malba is the property of bank branch hand over to the bank authorities.                                                                  | 200.00     | Cft.        |             |               |

| Subject     | <b>Proposed Interiors / renovation work of State Bank of India, Branch Office – Surajpur at Amravati Enclave, Panchkula, (Hry.). Br. Code – 01579.</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |            |             |             |               |
|-------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------|-------------|-------------|---------------|
|             | <b>BOQ</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |            |             |             |               |
| <b>S.No</b> | <b>ITEM</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            | <b>QTY</b> | <b>UNIT</b> | <b>RATE</b> | <b>AMOUNT</b> |
| 29          | <b>Brick work</b><br>Brick work with F.P.S. bricks of first class designation 75 in plinth & superstructure for all level in all shapes and sizes in Cement mortar 1:4 ( 1cement : 4 coarse sand) including all type of lead / lift, scaffolding, curing complete in all respects. The brick work shall be execute / erected from the proper base - beam / slab, not to be erected on the finished floor – tiles / stone / granite. The works includes cutting of finished floor – tiles / stone / granite from required cutter.                                                                                                                                                                                                                                                                                                                                                                                                                                       |            |             |             |               |
| a           | 9" thk. Brick Work                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | 150.00     | Cft.        |             |               |
| b.          | 4 ½" thk. Brick Work                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   | 60.00      | Sft.        |             |               |
| 30          | <b>Reinforced cement concrete Work</b><br>Reinforced cement concrete 1: 1 ½: 3 for slab, Beam, Lintel, shelves, mechanically / manually mixed and vibrated including steel reinforcement as per design up to 110 kg per cum including bending, binding & placing in position, Scaffolding, centering and shuttering laid in position complete in all respects.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         | 10.00      | Cft.        |             |               |
| 31          | <b>Cement Plaster including required Kuccha &amp; dismantalling</b><br>of existing plaster. - Interior, exterior, top & internal of parapet walls.<br>15 mm thk. cement plaster with water proofing compound 1: 4 (1 cement : 4 fine sand & water proofing compound) on roof top - brick walls new / old, Facia with groves maching with existing butch / tile / all kind of stones work like dholpur etc., Projection balcony, chajja vertical, Horizontal etc. including required Kaccha with required concrete & shuttring and all type of lead / lift, shuttering & scaffolding for all heights, curing complete in all respects after removal / dismantalling of existing plaster/ all kind of grangular finish - Dana- chapai / tile work / cladding, & disposal of malba to an unobjectionable place upto all lead. The work includes removing of holdings / sinage - as per bank's instractions. Make - (Cement - ACC, Ambuja, Ultratech, JK Cement & Bangur). | 500.00     | Sft.        |             |               |
| 32          | <b>Flooring – Vitrified Tiles</b><br>Providing and laying approved vitrified tiles with out groove (Johanson - white shade ( Albano White, Albeto, Alaska Snow, Snow allour first quality, double charge / premium quality range Homogeneous size - 800 mm X 800 mm in floor and skirting laid on 20 mm. thick base of adhesive of 1st quality like Pidilite including - Dismantling of existing all kind of flooring / tiles / stone etc., filling depressions in floor level, preparing of surface & disposal of required malba from site to an unobjectionable place & out side of municipal Limits, including Pointing the joints with epoxy grout as directed etc. as per design pattern. The work shall be completed in all respects to the entire satisfaction of the Engineer / Architect. (skirting shall be paid in sq.feet).                                                                                                                                | 1400.00    | Sft.        |             |               |

| Subject     | <b>Proposed Interiors / renovation work of State Bank of India, Branch Office – Surajpur at Amravati Enclave, Panchkula, (Hry.). Br. Code – 01579.</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |            |             |             |               |
|-------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------|-------------|-------------|---------------|
|             | <b>BOQ</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |            |             |             |               |
| <b>S.No</b> | <b>ITEM</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             | <b>QTY</b> | <b>UNIT</b> | <b>RATE</b> | <b>AMOUNT</b> |
| 33          | <b>Flooring – Endura - sandex salt &amp; pepper seres</b><br>Providing and laying approved Endura Sandex salt & pepper tiles first quality / premium range, Homogeneous 600 mm X 1200 mm x 10 mm thk. or as per manufacturer specifications in floor and skirting laid on 20 mm. thick base of adhesive of 1st quality like Pidilite including pointing the joints with white cement and matching pigments etc, as per design pattern including dismantling of existing all kind of flooring / tiles / stone etc., filling depressions in floor level, preparing of surface & disposal of required malba from site to an unobjectionable place & out side of municipal Limits. The work shall be completed in all respects to the entire satisfaction of the Engineer / Architect. (skirting shall be paid in sq.feet).                                                                 | 300.00     | Sft.        |             |               |
| 34          | <b>Flooring – Ceramic Tiles</b><br>Providing and laying Ceramic first quality anti skid floor tiles - Gr-V, Size - 600 mm X 600 mm or approved size, colour & shade in floor and skirting of Kajaria /Johnson / RAK as directed by Bank's Engineer / Architect laid on 20 mm. thick base of adhesive of 1st quality like Pidilite including pointing the joints with white cement and matching pigments etc., The work / rate shall be inclusive of skirting and required filling depressions in floor level, preparing of surface, dismantling of existing tiles, old flooring of terrazzo / conglomerate etc. if required including removal of malba to an unobjectionable place & out side of municipal Limits. The work shall be completed in all respects to the entire satisfaction of the Engineer / Architect. (skirting shall be paid in sq.feet).                             | 90.00      | Sft.        |             |               |
| 35          | <b>Wall Tiles - Ceramic glazed Tiles</b><br>Ceramic first quality glazed tiles 300 mm X 450 mm / 300 mm X 600 mm of of Kajaria / Johnson make of approved colour, shade, size, pattern and thickness in dado on 12 mm. thick cement plaster 1: 3 in base and jointed with white cement slurry in joints including beveled corners. The work / rate shall be inclusive dismantling of the old terrazzo, plaster, any stone slab & wall tile work etc. in dado or skirting and removing the old dismantled material to an unobjectionable place & out side of municipal Limits.. The work shall be completed in all respects to the entire satisfaction of the Engineer / Architect.                                                                                                                                                                                                      | 370.00     | Sft.        |             |               |
| 36          | <b>Water Closet - European type - One Piece Closet</b><br>Providing and fixing white vitreous china pedestal type water closet European type one piece of Hind ware make with seat, jet spray including connecting pipe and matching polypropylene seat cover, vitreous china 10.0 / 12.5 litre low level flushing cistern & 2 Nos. of angular stop cock of Jaquar (for jet & for cistern) with fittings & C.I. / M.S. brackets, 40 mm flush bend, highly flexible Semi rigid PVC connections, over flow arrangement with specials of standard make and mosquito proof coupling of approved municipal design complete including painting of fittings and brackets connecting with existing CI pipe with CI / PVC pipes, removing existing fixtures, cutting and making good the walls and floors wherever required & as per directions. The work includes following as per given below. | 2.00       | Each        |             |               |

| Subject     | <b>Proposed Interiors / renovation work of State Bank of India, Branch Office – Surajpur at Amravati Enclave, Panchkula, (Hry.). Br. Code – 01579.</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |            |             |             |               |
|-------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------|-------------|-------------|---------------|
|             | <b>BOQ</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |            |             |             |               |
| <b>S.No</b> | <b>ITEM</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | <b>QTY</b> | <b>UNIT</b> | <b>RATE</b> | <b>AMOUNT</b> |
| i           | Vitreous china pedestal type European water closet in one piece - Size : 69 x 36 x 74 cm, ELEMENT ITALIAN COLLECTION Cat. No.: 92085 (S-10), Cat. No.: 92091 (P-18) Starwhite. Cat. No.: 92082(S-30), Cat. No.: 92084 (S-22) Star rated.                                                                                                                                                                                                                                                                                                                                                                                                                                                     |            |             |             |               |
| ii          | Jet spray including connecting pipe                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |            |             |             |               |
| iii         | Matching colour polypropylene seat cover                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |            |             |             |               |
| iv          | 10.0 / 12.5 litre low level flushing cistern                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |            |             |             |               |
| v           | Angular stop cock (Cat. No. -053) of Jaquar - 2Nos. (for jet & for cistern)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |            |             |             |               |
| vi          | Long / short Body Bib Cock - Bib Cock extra heavy body of Jaquar with adjustable wall flange size 15 mm. (Cat. No. - 107).                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |            |             |             |               |
| ix          | Floor Trap with c.p. Grating of required size & nos.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |            |             |             |               |
| 37          | <b>Wash Basin - Flat back</b><br>Providing and fixing wash basin with pedestal of Hind ware with C.I. brackets, 15 mm C.P. brass FLR-5005NB Single Lever Tall Boy with 150mm Extension Body Fixed Spout without Popup Waste System with 600mm Long Braided Hoses for Wash Basin & angular stop cock of Jaquar, 32 mm C.P. brass waste of standard pattern, highly flexible Semi rigid PVC connections & P.V.C. waste pipe, including removing existing fixtures, painting of fittings and brackets, cutting and making good the walls wherever required, etc. White Vitreous China Flat back wash basin & sample to be got approved from Architect.the works includes following.             | 2.00       | Each        |             |               |
| i           | Wash basin MINI NEO, (Cat. No. -10099) with pedestal (Cat. No. -11032) of Hind ware, Size : 50 x 40 x 80 cm, Starwhite.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |            |             |             |               |
| ii          | Pedestal of wash basin with C.I. brackets pedestal (Cat. No. - 11032) of Hind ware                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |            |             |             |               |
| iii         | Single Lever Tall Boy with Extension Body Fixed Spout with Braided Hoses - Pillar cock - 1Nos.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |            |             |             |               |
| iv          | Angular stop cock (Cat. No. -053) of Jaquar.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |            |             |             |               |
| v           | Highly flexible Semi rigid PVC connections & P.V.C. waste pipe                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |            |             |             |               |
| vi          | Floor Trap with c.p. Grating of required size & nos.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |            |             |             |               |
| 38          | <b>Flat Back Half Stall Urinal – Single (Starwhite)</b><br>Providing and fixing white vitreous china flat back urinal & automatic flushing cistern (Cat. No – 5101) of Cera or equivalent in Hindware make with fittings, & angular stop cock (Cat. No.- 053) of Jaquar, standard flush pipe and C.P. brass spreaders with brass unions and G.I. clamps complete, highly flexible Semi rigid PVC connections & P.V.C. waste pipe including painting of fittings and brackets, cutting and making good the walls and floors wherever required and removing existing fixtures etc. One urinal basin of size 580 X 380 X 350 mm & white vitreous china automatic flushing cistern (7.5 liters). | 1.00       | Each        |             |               |
| i           | Urinal & automatic flushing cistern.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |            |             |             |               |
| ii          | Angular stop cock (Cat. No. -053) of Jaquar.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |            |             |             |               |
| iii         | Highly flexible Semi rigid PVC connections & P.V.C. waste pipe.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |            |             |             |               |
| vi          | Required Urinal Partitions.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |            |             |             |               |

| Subject | Proposed Interiors / renovation work of State Bank of India, Branch Office – Surajpur at Amravati Enclave, Panchkula, (Hry.). Br. Code – 01579.                                                                                                                                                                                                                                                                                                                                                                      |       |      |      |        |
|---------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|------|------|--------|
|         | BOQ                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |       |      |      |        |
| S.No    | ITEM                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 | QTY   | UNIT | RATE | AMOUNT |
| 39      | <b>Highly Rigid PVC - SWR pipes</b><br>Providing and fixing soil, waste and vent pipes with Joints (wars her & solution) & PVC - Heavy duty (6.0 Kgf) fittings like bends, sockets, Tee & required traps - 'P' / 'S' etc. laid on concrete bed & imbedded in P.C.C (1: 4: 8 ) cost includes to connect the existing sewer line, gully trap & existing Inspection Chamber.                                                                                                                                            |       |      |      |        |
| a       | 50 mm. dia.: Rigid PVC pipes                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         | 5.00  | Rft  |      |        |
| b       | 80mm. dia.: Rigid PVC pipes                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          | 10.00 | Rft  |      |        |
| c       | 110 mm. dia.: Rigid PVC pipes                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        | 10.00 | Rft  |      |        |
| 40      | <b>UPVC Plumbing pipes</b><br>Providing and fixing UPVC Plumbing pipes (external) complete with fittings and clamps, concealed including cutting chases and making good the wall. (Make - Astral / Jindal / Ashirwad / Green fit). UPVC Plumbing pipes - 15 mm. / 20 mm.                                                                                                                                                                                                                                             | 30.00 | Rft  |      |        |
| 41      | <b>Mirror</b><br>Providing and fixing 600 X 750 mm beveled, grinded & polished edge mirror 5.0 mm thk. of superior glass (Atul / Saint Gobbin) complete with C.P. holders fixed in wall with C.P. brass screws, washers, clips, Studes, spacers etc. & sample to be got approved from Architect.                                                                                                                                                                                                                     | 2.00  | Each |      |        |
| 42      | <b>Soap Dish</b><br>Providing and fixing in position C.P. soap dish holder fixed into wall with C.P. brass screws and complete in all respects including cutting and making good the walls etc. - Jaquar / Excel / Ess Ess.                                                                                                                                                                                                                                                                                          | 2.00  | Each |      |        |
| 43      | <b>Towel Rail</b><br>Providing and fixing in position towel rail (Cat. No. -1111N) of Jaquar fixed with rawl plugs embedded In walls with C.P. brass screws, complete in all respects including cutting and making good the walls etc. single towel rail 600 mm. long.                                                                                                                                                                                                                                               | 2.00  | Each |      |        |
| 44      | <b>Pantry counter ( Size - L -6'0" X 2'-0")</b><br>Providing and fixing S.S. sink with jet black granite counter with chamfered corners if required as per drg. on 2 ½" thk. RCC slab embedded in wall including necessary reinforcement steel in shape of tor steel with 32 mm C.P. brass waste of standard pattern & P.V.C. waste pipe, including removing existing required fixtures cutting and making good the walls wherever required, etc.<br>S.S. sink of size 18" X 18" X 9" & the work inlludes following. | 1.00  | Each |      |        |
| i       | Highly flexible Semi rigid PVC connections & P.V.C. waste pipe.                                                                                                                                                                                                                                                                                                                                                                                                                                                      |       |      |      |        |
| ii      | Floor Trap with c.p. Grating of required size & nos.                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |       |      |      |        |
| 45      | <b>Floor Traps</b><br>Providing and fixing highly rigid PVC floor traps conforming to I.S.I. specifications of reputed firm of the self cleaning design with C.P. brass hinged grating with frame with or without vent arm and including cement concrete 1: 2: 4 under and around the floor trap where required upto floor level complete in all respects including cutting and making good the walls and floors, etc. minimum depth of water should be 150 mm. with a minimum seal 50 mm with 75 mm. I / d outlet.  | 5.00  | Each |      |        |

|             |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |            |             |             |               |
|-------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------|-------------|-------------|---------------|
| Subject     | <b>Proposed Interiors / renovation work of State Bank of India, Branch Office – Surajpur at Amravati Enclave, Panchkula, (Hry.). Br. Code – 01579.</b>                                                                                                                                                                                                                                                                                                                                                                                  |            |             |             |               |
|             | <b>BOQ</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |            |             |             |               |
| <b>S.No</b> | <b>ITEM</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             | <b>QTY</b> | <b>UNIT</b> | <b>RATE</b> | <b>AMOUNT</b> |
| 46          | <b>Long / short Body Bib Cock.</b><br>Providing and fixing Long Body Bib Cock extra heavy body, with adjustable wall flange size 15 mm. (Cat. No. - 107) for pantry.                                                                                                                                                                                                                                                                                                                                                                    | 1.00       | Each        |             |               |
| 47          | <b>Stop / Angular Cock.</b><br>Providing and fixing Stop / angular Cock extra heavy body, with adjustable wall flange size 15 mm. (Cat. No. - 093 / 097 ) for Aquagard / filter.                                                                                                                                                                                                                                                                                                                                                        | 1.00       | Each        |             |               |
| 48          | <b>M.S. Grill</b><br>Providing / Fixing & Suppling M.S. Grill made out of Square bar 12.0 mm X 12.0 mm @ 125 mm C/C both side fixed on 40.0 mm X 5.0 mm Flat all round including welding & fixing / emended in position with hold fast in 3" X 3" concrete block (1: 2: 4 & two coats of primer and two coats of synthetic enamel paint off white or required shade. (Weight of every 6.0 mtr. length bar is 6.0 kg). Make - ISI.                                                                                                       | 10.00      | Sft.        |             |               |
| 49          | <b>Painting Work – Plastic Emulsion</b><br>Applying three or more coats of plastic emulsion (Asian / Nerolac) including making of surfaces with oil based putty and rubbing, etc. in case where the surface has been white / colour washed, the old white / colour wash shall be entirely removed and surface broomed / scrapped down before the new paint is applied. Rates include cleaning splashes from glass panes, floor, furniture etc. The work shall be completed in all respects to the entire satisfaction of the Architect. | 1500.00    | Sft.        |             |               |
| 50          | <b>Painting Work – Enamel Paint</b><br>Applying two or more coats of enamel paint (Asian / Nerolac) on wooden / steel surfaces including filling and making of surfaces smooth with oil based putty required to give even and smooth surface. Rates include cleaning splashes from glass panes, floor, furniture etc.                                                                                                                                                                                                                   | 300.00     | Sft.        |             |               |

| Subject     | <b>Proposed Interiors / renovation work of State Bank of India, Branch Office – Surajpur at Amravati Enclave, Panchkula, (Hry.). Br. Code – 01579.</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |            |             |             |               |
|-------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------|-------------|-------------|---------------|
|             | <b>BOQ</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |            |             |             |               |
| <b>S.No</b> | <b>ITEM</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      | <b>QTY</b> | <b>UNIT</b> | <b>RATE</b> | <b>AMOUNT</b> |
| 51          | <p><b>Granite - Lappato, on floor / floor bands of all widths - including inlay in ramp, Steps, vertical, horizontal &amp; Skirting.</b></p> <p>Providing &amp; laying 19.0 mm thk. albeta / gang saw cut mirror polished premoulded and prepolished machine cut Lappato Granite granite / approved shade, colour and texture shade laid over 20mm thick base cement mortar 1:3 (1 cement : 3 coarse sand) with joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing to edges to give high gloss finish etc. complete at all levels, Margin for making sharp edge moulding at edges - half round / chamfered required rubbing / grinding &amp; polishing including dismantling of existing all kind of flooring / tiles &amp; disposal of malba from site to an unobjectionable place &amp; out side of municipal Limits. The works includes cutting of existing flooring from the required cutter for the granite bands of all sizes / widths in state &amp; sharp edges. Preparation of rough work / kaccha / surface treatment to make unique dimensions with cement mortars (1:2:3) including filling depressions in floor level, preparing o surface &amp; including all scaffoldings &amp; shuttering complete in all respect. The work shall be completed in all respects to the entire satisfaction of the Engineer / Architect. Band / Skirting of all widths shall be paid in sq.feet . (Basic Rate @ 120.00 per sft.). The work including removing &amp; reinstalling / refixing of existing railing to ramp &amp; stairs including required repair.</p> | 30.00      | Sft.        |             |               |
| 52          | <p><b>M.S. steel door to Safe room &amp; lockers room</b></p> <p>Providing and fixing M.S. steel door made up of 12 MM dia M.S. bars @ 3" c/c welded with angle frame braced with 25mm x 40mm flats and 16 guage m.s.sheet on one side and locking arrangements (two aldrops and one gordwan lock) as per drawings including provision of angle chowket 40 x 40 x 6mm with holdfasts duly embedded in M 20 concrete duly primer and painted complete in all respect .</p> <p>Providing and fixing M.S. steel ventilator made up of 3 MM M.S. plate on all five sides duly welded to form a box and a grill of 12mm m/s. bar @ 3" c/c bothways welded as per drawings including provision of slotted wire mesh sutter with holdfasts duly embedded in M 20 concrete finished with 2 coats of ready-mixed red led non-setting primer of approved quality &amp; 2 coats of enenal paint off white or approved colour complete in all respect .</p>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | 25.00      | Sft.        |             |               |

|             |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |            |             |             |               |
|-------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------|-------------|-------------|---------------|
| Subject     | <b>Proposed Interiors / renovation work of State Bank of India, Branch Office – Surajpur at Amravati Enclave, Panchkula, (Hry.). Br. Code – 01579.</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |            |             |             |               |
|             | <b>BOQ</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |            |             |             |               |
| <b>S.No</b> | <b>ITEM</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        | <b>QTY</b> | <b>UNIT</b> | <b>RATE</b> | <b>AMOUNT</b> |
| 53          | <b>Collapsible Door / Shutter</b><br>Providing and fixing in position collapsible steel shutter, with vertical channels 20 mm x 10 mm x 2 mm and braced with flat iron diagonals 20 mm x 5 mm size, with top and bottom rails (Emended in the floor) of T-Iron 40 mm x 40 mm x 5 mm with 38 mm dia. steel pulleys, complete with bolts, nuts, locking arrangements, stoppers, handles, etc. the entire arrangement fixed / welded in a frame of Square pipe 50 mm x 50 mm x 14 gauge, the vertical members of frame fixed in position in floor & embedded in cement concrete block of mix 1:2:4 of size, 300mm x 300 mm x 400 mm deep & entire steel work finished with 2 coats of ready-mixed red led non-setting primer of approved quality & 2 coats of enamel paint off white or approved colour , The payment is to be made for exact size of clear opening where collapsible shutter to be fixed. The works includes cutting of existing flooring from the required cutter for the bottom mamber / rails to emended in the floor & complete / finish upto the satisfaction of architect / engineer incharge. | 35.00      | Sft.        |             |               |
|             | <b>Total</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |            |             |             |               |
|             | GST extra as per applicable                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |            |             |             |               |