

**BOQ for Strengthening and repairing of boundary wall at SBI Staff Quarter,
Michael Faraday Road, Durgapur**

Sl. No.	Item Description	Unit	Quantity	Rate (Rs./Unit)	Amount (Rs.)
1	Supplying, fitting galvanised 3 ply 12 gauge / 6 lines of barbed wire in fencing (holes already made in the body of the post) or fixed by staples tightening and fixing the wires in taut condition with straining bolts including the cost of cutting and of lapping joints in the wire as necessary but excluding the cost of galvanised staples, straining bolt and binding wire where necessary. Total length=432m	RM	432.00		
2	Cutting and trimming of big sized trees near the boundary wall so as to facilitate fixing of roofing sheets along the boundary wall	Nos	8.00		
3	Providing and erecting Brickwork with good quality 1st class brick upto a height of 1.5m from the base level (10 inch thick brick-wall) :klin burnt clay brick/fly ash brick in superstructure at any	cum	20.86		
4	Plastering (avg. 15 mm thick) with cement : medium sand mortar = 1 : 4 to walls, ceiling, columns, beams, etc., at any floor level	sqm	569.00		
5	External paint on boundary wall surface : Acrylic exterior grade Weather-coat Anti-fungal Emulsion Paint (two coats) to external walls, ceiling, columns, beams, etc., over two coats of Acrylic Primer. Note: The rates are inclusive of priming coat, labour and scaffolding charges	sqm	569.00		
6	Demolition of damaged RCC posts and tie-beams and erection of new RCC tiebeams and columns : Pouring and placing in position Reinforced Cement Concrete (RCC) in all sorts of structural members at any level as directed with mix proportion of either 1 : 1.5 : 3, or, 1 : 2 : 4, as directed, for nominal mix with a water-cement	cu.m	23.64		
7	Lowering and Re-fixing of Existing Galvalume Sheet. The existing pre-painted Galvalume sheet fixed over the boundary wall was carefully dismantled from its original position without causing any damage to the sheets or supporting members. The sheets were subsequently lowered to the required level and re-fixed in the revised position over the existing M.S. supporting framework using the existing/new self-drilling self-tapping screws with EPDM washers as required. The work included dismantling, handling, shifting, alignment, cutting wherever necessary, and complete re-installation to the satisfaction of the Engineer-in-Charge.	Ls	1.00		
8	Total amount				-
11	After rounding off				

Note: Estimate has been prepared as per Bank's approved rates for similar works

Goods & Services Tax (GST) shall be paid extra as admissible on final bill.

Signature of the Contractor with Official Seal

Bank reserves the right to select any material out of the specified make.