

TENDER OF AIR CONDITIONING (PIPING WORK) WORK AT SBI					
REENGUS BRANCH					
S. No.	Details	Qty.	Unit	Rate	Amt Rs.
1	DRAIN PIPE:-				
(a)	Condensate drain water piping 1" Dia PVC Duly				
	Insulated to nearest drain trap to be laid concealed.				
	Rigid CPVC drain pipe of				
	6 Kg/Sq.cm with 6 mm thk. Nitrile rubber insulation				
	Insulated to nearest drain trap to be laid concealed.	100.00	R mt.		
2	REFRIGERANT PIPE including electrical cable :-				
a)	High wall split A.C.				
	of approved make duly insulated with elastometric				
	nitrile rubber tubular insulation (9mm)				
	between each set of indoor & put				
	door unit for above mentioned units to interconnect				
	indoor unit and outdoor unit.				
	Copper piping as per manufacturer specifications				
	with authorized certificate.				
	It should also be mentioned by vender in tender.				
	P & F electrical Copper (FRLS) wire of				
	3.0 core X 4.0 Sq.mm (Polycab, Finolex, KEI)	100.00	R mt.		
b)	Cassette type A.C. (DAIKIN MAKE)				
	of approved make duly insulated with elastometric				
	nitrile rubber tubular insulation (9mm)				
	between each set of indoor & put				
	door unit for above mentioned units to interconnect				
	indoor unit and outdoor unit.				
	Copper piping as per manufacturer specifications				
	with authorized certificate.				
	It should also be mentioned by vender in tender.				
	P & F electrical Copper (FRLS) wire of				
	4.0 core X 4.0 Sq.mm (Polycab, Finolex, KEI)	120.00	R mt.		
	TOTAL (GST EXTRA)			Rs.	