


**INTERIOR FURNISHING & SPRINKLER WORKS AT VAISHALI PBB BRANCH GROUND FLOOR JAIPUR,
STATE BANK OF INDIA**

S.No		Title	Description	Unit	Quantity	Estimated Rate	Estimated Amount
1	BS R 201 9 10.2 7	Gypsum False Ceiling	A) P&F false ceiling with Gypsum Board 12.5mm thick fixed to a metal frame comprised of ceiling channel of size 80mm X 26mm X 0.5mm @ every 450 cms centres, inter channel 45mm X 15mm X 0.9mm @ every 1220mm centres, peri-meter channel 20mm X 26mm all along the wall, strap hanger suspendeds 25mm X 0 5mm with nuts and bolts 6.4mm x 12.7mm, connecting clip 2.64mm thick, dry walls screw 25mm long , soffit cleat. 27mm X 37mm X 25mm X 1.6mm thick and dash fastener/ rawl plug 12.5mm dia X 35mm long with 6mm dia bolt. The joint of gypsum board to be taped 3 times and sealed with jointed compound with three coat plastic emulsion paint finished. Cut-out are provided to accommodate luminaries, air conditioning grills and fire warning detectors if any. All fitting to be separately hung from the ceiling and should not rest on the false ceiling. Painting Cost is included. Patta Height only 150 mm is part of this item. Makes : Gyproc / USG BORAL / GYPSOMAN	Sqm.	259.00		-
2		Gypsum False Ceiling Patta	A) P&F false ceiling with Gypsum Board 12.5mm thick fixed to a metal frame comprised of ceiling channel of size 80mm X 26mm X 0.5mm @ every 450 cms centres, inter channel 45mm X 15mm X 0.9mm @ every 1220mm centres, peri-meter channel 20mm X 26mm all along the wall, strap hanger suspendeds 25mm X 0 5mm with nuts and bolts 6.4mm x 12.7mm, connecting clip 2.64mm thick, dry walls screw 25mm long , soffit cleat. 27mm X 37mm X 25mm X 1.6mm thick and dash fastener/ rawl plug 12.5mm dia X 35mm long with 6mm dia bolt. The joint of gypsum board to be taped 3 times and sealed with jointed compound with three coat plastic emulsion paint finished. Cut-out are provided to accommodate luminaries, air conditioning grills and fire warning detectors if any. All fitting to be separately hung from the ceiling and should not rest on the false ceiling. Painting Cost is included. Patta more then 150 mm is part of this item.. Makes : Gyproc / USG BORAL / GYPSOMAN	Rm.	34.00		-
3	BS R 201 9 10.2 9	Grid False Ceiling	The grid false ceiling shall be provided in the Banking Hall, Manager's etc. The ceiling height and level shall be determined at the perimeter. The minimum height of the ceiling cavity should be 100mm. All service fittings integrated within the suspended ceiling must be independently supported from the ceiling grid by a structure designed for the purpose. ♦ Ceiling tiles Shall be Armstrong Dune RH99 of 16mm thickness. Suspension system shall be of Armstrong Trulok Silhouette reveal profile grid system with 15mm flanges incorporating 3mm central recess in global white with black reveal. Silhouette main runners and cross tees to have mitred ends and "birdsmouth" notches to provide mitred cruciform junctions. ♦ Installation Main runners will be placed at 1200mm centers securely fixed to the structural soffit by approved hangers at 1200mm maximum centers and not more than 150mm from spliced joints. The last runner at the end of each main runner should not be greater than 600mm from the adjacent wall. 1200mmm long cross tees to be interlock between main runners at 600mm centers to form 1200x600mm modules. Cross tees longer than 600mm require independent support. 600x600mm modules to be formed by fitting 600mm long cross tees centrally between the 1200mm cross tees. The 1200mm cross tees to have central "birdsmouth" notches to facilitate fitting of 600mm cross tees. The perimeter trim to be Armstrong Trulok equal w'all angle of white color secured to walls at 450mm maximum centers. Make Armstrong/Pyrotech/Hunter douglas/Celestials durlum	Sqm.	205.00		-

S.No		Title	Description	Unit	Quantity	Estimated Rate	Estimated Amount
4		WPC Baffle Ceiling	WPC Baffle Ceiling : Providing & fixing wpc baffles of width 50 mm and height 60 mm with 40 mm clear gap between two baffles. The ceiling needs to be supported through a metal support system screwed to true ceiling. Baffles should have WPC core, should have real wooden look as per selection, should be water proof and termite proof. Approved makes: Vigaceil, Uniceil. Quantity measurement will happen only for installed quantity. No wastage will be payable extra. Wastage needs to be incorporated in quoted rate.	Sqm.	30.00		-
5	BS R 10.3 3.2	calcium silicate Tile False Ceiling	Providing & fixing calcium silicate perforated ceiling tiles of size 595 x 595 mm in true horizontal level suspended on inter locking metal grid of hot dipped galvanised steel sections (galvanized @ 170 gsm/sqm.) consisting of main "T" runner with suitably spaced joints to get required length and of size 24x38mm made from 0.30mm thick (minimum) sheet spaced at 1200mm center to center and cross "T" of size 24x25mm made of 0.30mm thick (minimum) sheet, 1200mm long spaced between main "T" at 600mm center to center to form a grid of 1200x600 mm and secondary cross "T" of length 600mm and size 24x25mm made of 0.30 mm thick (minimum) sheet to be interlocked at middle of the 1200x600mm panel to form grids of 600x600mm and wall angle of size 21x21x0.30 mm and laying false ceiling tiles of approved texture in the grid including, wherever, required, cutting/making, opening for services like diffusers, grills, light fittings, fixtures, smoke detectors etc. Main "T" runners to be suspended from ceiling using GI slotted cleats fixed to ceiling with 6 mm dia and 50mm long dash fasteners, 4mm GI adjustable rods with galvanised level clips spaced at 1200mm center to center along main 8 mm thick Makes : HILUX/ RAMCO / AEROLITE	Sqm.	13.00		-
6		Full Height Partition (Wooden with Laminate)	Supply and fixing of partitions upto height as specified having an internal frame work of Aluminium frame work of 2" x 2" 1.2 mm thick sections placed at min 2'x2' horizontally & vertically (as per site requirement) with 12mm water proof MDF Board / 12mm commercial ply and a pattern of laminates, 1.0mm laminate on both sides & 12mm thick toughened glass approved make and shade with columns and bands as per design and a pattern of grooves etc. as per details and specifications. The grains of the laminate should be matched properly. Proper arrangement as per detail shall be made for providing electrical wires and misc. cables at 2'6" ht. and at skirting level. This is highlighted on the finished partition with the help of grooves/ projections as per detail. 1mm grooves to be provided vertically at specified distance. Measurement of height shall be taken from finished floor level up to the true ceiling. The rate to include Provision of extra frame work as necessary for skirting and making cutouts for electrical switch plates, switch boxes, light fittings light etc. making provision for laying conduit; as per drawings & directions of site Eng. / Architect. Laminate as per selection by Architect / SBI. Bank may select shade from Equivalent range as required. Rate includes 12 mm toughened glass and teak wood beading with polish required for holding the glass. Partitions need to be closed above false ceiling also. Makes : Century/ Merino Green/Archid Brand(s) as approved by Architect In Charge.	Sqm.	174.00		-

S.No		Title	Description	Unit	Quantity	Estimated Rate	Estimated Amount
7		column /wall panelling (Laminate)	Providing & fabricating of coloumn / wall panelling made out with Aluminium Framework consisting of 2" x 1" ,1 mm thick placed at min. 2'x2' horizontally & vertically (as per site requirement) with 12 mm water proof MDF Board ? 12 mm thick commercial grade ply. G.I Framework with MDF Board skinning 1mm th. mica of approved shade over the coloumnns / wall & necessary vinyl prints as per approved drawings. The rates are including the design provided in the approved drawing.. Makes : Century/ Merino Green/Archid Brand(s) as approved by Architect In Charge. The rate should include working with flexible ply.	Sqm.	304.00		-
8		SBI LOGO	SBI LOGO with SBI text : SITC Backlite acrylic Logo as per tender drawing.	No.	2.00		-
9	BSR 12.40.1	Plastic Emulsion (for Wall & Roof in Ceiling)	Supply and application of Wall & (Roof in Ceiling as per required) painting with plastic emulsion paint of approved brand and manufacture to give an even shade including all scaffolding : Two or more coats on new work including preparation of base with primer, putty, lippy etc complete in all respect. Makes : Asian paints, Nerolac, Berger, Opus	Sqm.	629.00		-
10	BSR 12.46.1	Enamel Paint	Providing & laying 2 or more coats of Syntheic Enamel paint for exisisting grill & railing as per Bank's instructions. Makes : Asian paints, Nerolac, Berger, Opus	Sqm.	50.00		-
11		3M Frosted Film	Providing & fixing in position 'Garware' make frosted glass film in stardust range fixed to glass as per pattern. Area of application to be measured as maximum length x maximum height of application on that particular piece of glass. Makes : 3M / Garware	Sqm	58.00		-
12		Wooden Door	Providing and fixing flush door with 35mm water proof door with 4mm wood veneer finish including melamine polish (of approved shade) on both sides The item includes 105X75mm Sal wood Grade-1 choukhat or double ply framework as per detail, 7 lever mortise lock, SS handle, stopper hinges, door closer, paint/polish etc complete.Cost to include all edgings and vision panel. choukhat with melamine polish 2 coats clear matte coat. Bank may select shade of veneer from Equivalent range as required. Melamine polish for this item is included in this rate. Hardware : OZONE/DORMA				-
			Door Size - 900mm X 2400mm (four hinges)	Nos.	3.00		-
13		FLUSH DOOR	Providing and fixing flush door with 35mm water proof door with 1mm high glass laminate (of approved shade) on both sides The item includes 105X75mm Sal wood Grade-1 choukhat, 7 lever mortise lock, SS handle, stopper hinges, paint/polish etc complete.Cost to include all edgings and vision panel. choukhat with Oil paint. Item including with door closer. Makes : Greenlam, Century, Merino/Archid & Hardware : OZONE/DORMA	Sqm.	14.00		-
14		Roller Blinds	Providing and fixing Roller blinds of required width & Length quality of approved make fabric made of 100% polyester thickness 0.30mm with Acrylic coating resistance to Cracking & Fraying and treated for dust repellency, UV proof , virtually maintenance free having plastic bottom chain thickness of chain 0.50mm and diameter-3mm, weight per sqm 201g, Degree of opacity 100%, Light frastness 4/6, Plastic with metal bottom weight - 116.20mmX48.30mm and suitable coating on exterior, including all fixtures and fittings complete in all respect as per design/color/shade including requisite installation brackets etc as required for installation at site with anchoring arrangements complete as directed. MAKES : Vista levellor/ MAC	sqm	37.00		-
15		Fire door	Fire door : P&F of two Hour rated Firedoor of size 900x2400mm & 975x2400 with 300x300 vision panel inclusive of firerated lock, door closer & other accessories. Approves makes : Shakti Hormann, Aadhunic, Tata pravesh. All Accessories to be of dorma make.	LS	2.00		-

Axes Architectural Design And Engineering Services Pvt. Ltd.


Director

S.No		Title	Description	Unit	Quantity	Estimated Rate	Estimated Amount
16		Half Brick work	Half Brick work with mechanised autoclaved clay bricks conforming to IS:12894:2002 of class designation 100 in superstructure above plinth level upto floor V level in Cement mortar 1:4 (1 Cement : 4 coarse sand). Item Rate Including scaffolding. USE 1st quality Red clay bricks and Sand	sqm	87.00		-
17		Plaster	12 mm thick Ready mix Plaster : Providing 12mm thick (average thickness) Ready mix plaster in single coat in (finishing the surface even including labour,curing,scaffolding etc.,complete over masonry wall, RCC surface inside the building finishing at all heights). Rate is inclusive of carting away debris. Rate is also inclusive of application of wiremesh for prevention of cracks at joints of RCC columns and masonry. Approved makes Ready mix: Birla Aerocon, Ultratech readiplaster, Ambuja Plazto, Magicrete	sqm	348.00		-
18		Kitchen Counter	P&F Modular Kitchen : Base structure to be made of 18 mm thick prelaminated HDHMR Board of Action Tesa / Green Panel Make base side board to be 8 mm thk. shutters to be made of 18 mm thk. HDHMR with pre laminated boards as well. with aluminium profile handles Hardware to be of Hettich/Hafele/Ebco make. The structure should include shelves and two drawers and two wire baskets. The counter size 1800mm X 600mm X 750mm with over head counter.	L.S.	1.00		-
19		BM Cabin Decorative Wall & DESIGNER Storages	a. FULL Height Cupboard with Laminate Finish: Providing & fixing Storage Cupboard of 750 to 2400 (0 TO 2400) height and 600mm deep. Outer exposed structure with to be made with 19mm BWP ply as per IS 303 and back side using 8mm BWP grade ply. All shutters to be made from 25 mm thk BWP Ply and shelves to be made with 19 mm thk.BWP ply. Designer cabinet details. Size - 1650 x 600 x 2400 (ht) mm including louvers in aluminum for ventilation. Only front elevation will be considered for area calculation.	SQM	5.00		-
20		HALL Storages	a. Low Height Cupboard with Laminate Finish: Providing & fixing Storage Cupboard of 750 to 2400 (0 TO 2400) height and 450mm deep. Outer exposed structure with to be made with 19mm BWP ply as per IS 303 and back side using 8mm BWP grade ply.All shutters to be made from 25 mm thk BWP Ply and shelves to be made with 19 mm thk.BWP ply. Designer cabinet details. Size - As per Drawing including louvers in aluminum for ventilation. Only front elevation will be considered for area calculation.	SQM	16.00		-
21		12 MM TH. FULLY GLAZED DOOR	12 MM TH. FULLY GLAZED DOOR : Providing and fixing position 12 mm fully glazed toughened glass door, single/ double shutter, of approx. size 900/ 1500 x 2100/2400 mm Providing and fixing in position frameless glass door shutter made using 12mm thick toughened glass fixed to the partition (glazed / solid / gypsum partitions) using heavy duty floor spring with pivot of approved make including necessary cutting of floor and making the surface good to its original position including all necessary Patch fittings of approved make and fixtures & hardwares. Approved make: DORMA Top Pivot - PT 24, Top Patch Fittings - PT 20, Bottom Patch fittings - PT 10, Floor Spring - BTS 75 V, Corner lock with strike plate and Handle - TG DIH600 - 600mm (length) or equivalent brand fittings from Hettich / Hafele / as per sample approved by the Bank. Rate should also include providing film as per design/ instructions of Bank. Mode of Measurement: Door opening size shall be measured. Glass- Asaahi/ Tata / Modi guard / Saint gobain	sq m	7.00		-

S.No		Title	Description	Unit	Quantity	Estimated Rate	Estimated Amount
22		BM table	Supply & fixing in position branch head table (size 7' x2'-6") made out of 19 mm thick BWR board with 1mm thick high gloss laminate finish on table top complete. Drawers shall have ball bearing slides & locks etc. complete internal surface shall be finished with 1.00 mm th.laminated with high gloss white laminate. Each table shall have the provision of key board with ball bearing slides Arrangement. 2 mm thk white foam & 10mm thick Toughened glass top shall be provided along with 12mm Toughened glass modesty panel covered with frosted film complete. The provision of side storage (upto3'-0" x30"x1'-6" as per site) is included in the rate . The Design will be as per drawing approved.	No.	1.00		-
23		sales / officer's table with LAMINATE top	Table 5'-0"x 2'-6"x 2'-6" made out of 19 mm MR board with 1 mm thick laminate as approved, with wooden keyboard tray with side laminate & front modesty panel with double box structure & Board Strips, beading as per design. All external sides finished with 1 mm laminate as approved & internal sides with 0.8 mm balancing laminate as approved. Top edge all sides made of 40 mm thickness with BWR. board 19 mm box framing as per design. Edges of design finished with T.W. beading with polish finish. Table drawer unit made out of 19 mm B. W. R. Board with top drawer 6" depth & lower Shutter with approved laminate. Outer side 1 mm thick & balancing laminate 0-8 mm internal sides with approved drawer channels , handles, locks, & all hardware as per design complete. with approved shade laminate with necessary hardware, hinges, locks, magnetic catchers of approved make, complete unit as per design.Skirting4 " high made out of 19 mm MR Board finished with approved shade laminate 1mm thin. The provision of side storage (upto3'-0" x30"x1'-6" as per site) is included in the rate . The Design will be as per drawing approved. as per design as approved by architect /bank incharge Plywood Make: Greenply, Century, Duro, Archid or equivalent approved by the Bank. Table includes provision of 10 mm Toughned glass top with bevelled edges.	No.	6.00		-
24		TABLE	Table 4'-0"x 2'-0"x 2'-6" made out of 19 mm MR board with 1 mm thick laminate as approved, with wooden keyboard tray with side laminate & front modesty panel with double box structure & Board Strips, beading as per design. All external sides finished with 1 mm laminate as approved & internal sides with 0.8 mm balancing laminate as approved. Top edge all sides made of 40 mm thickness with BWR. board 19 mm box framing as per design. Edges of design finished with T.W. beading with polish finish. Table drawer unit made out of 19 mm B. W. R. Board with top drawer 6" depth & lower Shutter with approved laminate. Outer side 1 mm thick & balancing laminate 0-8 mm internal sides with approved drawer channels , handles, locks, & all hardware as per design complete. with approved shade laminate with necessary hardware, hinges, locks, magnetic catchers of approved make, complete unit as per design.Skirting4 " high made out of 19 mm MR Board finished with approved shade laminate 1mm thin as per design as approved by architect /bank incharge Plywood Make: Greenply, Century, Duro, Archid or equivalent approved by the Bank. Table includes provision of 10 mm Toughned glass top with bevelled edges.	Nos	1		-

S.No		Title	Description	Unit	Quantity	Estimated Rate	Estimated Amount
25		Banking Counter (with Laminate Top)	Providing and fixing counter 2'-6" wide comprising of following & complete in all respects. Officer / staff working counter top 2'6" deep finished with 1mm high gloss laminate including customer working top made with 19mm thick BWR board finished with 1mm white high gloss laminate as per approved drawing. Attached moulded in curve shape downwards up to 1'9" form top. Lower portion in front shall be provided with blue laminate 1mm thick on 19mm th. BWR board with LED strip complete with driver will be provided as per drawing. Side table of size 3'(L) x 2'6"(H) x 1'-6"(D) as per drawing to be made in same material. The top & side table will have toughened glass of 10 mm th. with 1" beveling is also included in the item. The exposed edges of the glass shall be finished with necessary grinding & mirror polish. Telescopic CPU stand & key board shall be provided of Ebco make. All remaining exposed surfaces will be finished with Enamel paint complete. Footrest made with T.W member of size 4" x 1 1/2" finished with Laminate complete. The drawer unit to be made of 19 mm bwr board as per drawing and top drawer unit shall be provided with automatic lock by EBCO/hettich. Boxing made with 12mm thick plywood finished with Enamel paint shall be provided below the table top for electrical conduit and at the bottom for the LAN cabling / Telephonic wire conduit. The item to include all necessary hardware & fittings in stainless steel finish to all edges & making provision only for electrical fitting.	RM	10.00		-
26		BACK cabinate (Laminate top)	Providing and fixing wooden storage 450 mm wide as per drawing having sides, partitions shelves and shutter made of 19 mm thick Board finished with 1 mm thick High gloss laminate with all other exposed internal surfaces finished with enamel paint complete with side hinged shutter complete with handles, locks etc. (for the purpose of contractor's payment only front elevation area of a cabinet will be measured.)	Sqm	14.00		-
27		Reception Table	Providing and fixing of table made as per attached tender drawing. The frame work to be made in 12 mm thick ply finished Laminated and corian sheet as per selection. Flexible ply will have to be used wherever required as per drawing. Table 6'-8"x 2'-4"x 2'-10"	Each	1.00		-
28		SBI LIFE & SBI Credit Card Table	Providing and fixing of table made as per attached tender drawing. The frame work to be made in 12 mm thick ply finished 1 mm thick High gloss laminate with all other exposed and internal surfaces. Flexible ply will have to be used wherever required as per drawing. Table size 14'-6"x 3'-0"x 3'-0"	Each	1.00		-
29		Wicket Gate	Wicket gate have to match with the partition / counters. Wicket gate should be made up of 32mm flush door finished with 1mm laminate. The door shall have SS finished door lock, heavy duty SS hinges, SS handles, door stopper etc. as per schedule of interior, furniture & finishes. Refer schedule of interiors, furniture & finishes. Refer dwgs.	sqm	2.00		-
30		Lock	P & F Gate giving access behind the counter shall have autolock, which can not be opened from outside in cash counter and wicket gate.	Nos.	2.00		-

S.No		Title	Description	Unit	Quantity	Estimated Rate	Estimated Amount
31		Cubicle	<p>Toilet Cubicle Work</p> <p>Supply and installation of cubicles of width and depth as per Athena Lite- SS Series Cubicles- Std Sizes (W x D x H):900 mm x 1550 mm x 2105 mm, (Height is including 100 mm gap from bottom, Door Width- 600 mm x 1820 mm specifications/ site drawings). Cubicle height to be 2105 mm. Made from solid grade compact high pressure laminate as per IS:2046 and EN-438 manufactured under high specific pressure > 5 MPa and temperature >120°C, All doors will be of single colour and made of 12 mm thick Merino HPL compact panel. The doors will have chamfered edges. Each door will be supported by 3 stainless steel made hinges affixed to the pilasters. Size of panels to be as per drawing. HARDWARE & ACCESSORIES are H shaped (Top) head frame structure made of extruded Aluminium grade 6063 T5- 50 micron epoxy powder coated for surface protection, Size to be 125x70x5T. Corner joinery section, Size to be 40x16.5x1.8T. UChannel Wall joinery section,Size to be 22x16x1.6T. Door stopper section, Size to be 21x12.5x1.6T. Spring loaded Butt Hinges made from Stainless steel grade 304. Surface finish to be matt type. Covers to be lacor coated.etc complete. as per approved drawing, design and as per the direction of Engineer-in-charge. Makes: Merino/Greenlam/Action TESA</p>	sqm	1.00		-
			AUTOMATIC SPRINKLER SYSTEM				-
							-
			SUPPLY, INSTALLATION, TESTING & COMMISSIONING OF :-				-
32			15 mm dia. Quartzoid bulb type G.M. Sprinkler head suitable to operate at 68°C (UL/FM/LOC listed /approved) Make : HD Fire, New Age, Senju				-
a)			Standard Pendent type in brass	Each	39		-
							-
33			Providing & Fixing of corrugated stainless steel (AISI 304) un braided flexible sprinkler pipe drps of 25 mm dia of follwing length and maximum working pressure of 175 psi with all accessories and clamps as required. The flexible pipe drop shall be UL approved. The Pipe drop shall be of following lengths.				-
a)			1000 mm lengths	Each	10		-
							-
34			Providing and fixing Slim seal Butterfly valves (PN 1.6) complete with matching flanges rubber insertion, nuts, bolts and washer etc. of following sizes. Make : Zol,leader,poline etc				-
a)			80 mm dia nominal bore	Each	1		-
b)			100 mm dia nominal bore	Each	1		-
							-
35			Providing and fixing Ball valve with hard chrome plated ball inside PTFE (Teflon) seat & ring with chrome plated centre handle with female BSP threads complete: in all respects.Make: L&T, Zoloto,Hawa valves,kirloskar etc.				-
a)			25 mm dia nominal bore	Each	1		-
							-
36			Providing and fixing electrically operated flow indicating switch with threaded connection for a minimum flow of 90 lpm for indicating water flow in sprinkler line with necessary junction box installed in accessible place & suitable connection with fire alarm panel. Make : HD Fire,Tyco, system sensor etc.	Each	1		-
							-

S.No		Title	Description	Unit	Quantity	Estimated Rate	Estimated Amount
37.0			Providing and fixing Mild Steel Pipe (IS: 1239 Part-1) heavy class including cutting, welding/serving etc. and providing all fittings viz. Flanges, Bends, Tees, Elbow, Reducers, Clamps, Hangers etc. including cutting holes and chases in brick or RCC walls/slabs and making good the same to the approval of engineer/consultant complete including painting with one coat of primer and two or more coats of enamel paint of approved make and shade including steel work. (Make : Jindal star, tata pipes, APL apollo, surya roshni)				-
a)			100 mm dia	RM	6		-
b)			80 mm dia	RM	6		-
c)			65 mm dia	RM	12		-
d)			50 mm dia	RM	12		-
d)			40 mm dia	RM	18		-
e)			25 mm dia	RM	48		-
							-
38			Providing and fixing 25 mm dia inspecting & testing assembly with gunmetal valve, gunmetal sight glass, bypass valve & connected to drain line.	Each	1		-
							-
39			(Double fire Extingnisher stand) Providing fabricating, supplying installing SS double fire Extingnisher stand Suitable for 2 Extingnisher (2-9 Kg capacity) approx weight of stand (9-11 KG) per stand.made 25mm to 40mm dia pipe, complete with clamps, labour & all accessories.	Each	4		-
			Total Amount				-
							-