

BOQ FOR INTERIOR AND FURNISHING WORKS AT SBI ARTHLA BRANCH (EXISTING PREMISE)					
S.NO.	DESCRIPTION	UNIT	QTY.	RATE	AMOUNT
	FURNISHING WORK				
1.0	FALSE CEILING				
1.1	<p>Providing and fixing suspended false ceiling in Glass Fiber Reinforced Gypsum board. Gypsum board suspended ceiling shall comprise of providing and fixing G.I. perimeter channel (MF-6A) of size 0.50mm thick having one flange of 19.6mm and another flange shall be of size 29.6mm and a web of 26.6mm along with perimeter of ceiling, screw fixed to the beam for the required curvature with nylon sleeves and screws are not exceeding 610mm centers. Then suspending G.I. intermediate channel (MF-7) of size 45mm, 0.9mm thick with two flanges of 15mm each bent to the required curvature by cutting both of its flanges. Suitable bracing to be provided where ever the flanges are cut with 0.9mm G.I. Flat and nuts and bolts at specific positions and thereafter at 1220mm centers with ceiling angle of width 25mm x 10mm x 0.50mm thick fixed to the soffit with G.I. cleats and steel expansion fasteners. Ceiling section (MF-5) of 0.50mm thickness having knurled web of 51.5mm and two flanges of 25.6mm each with lips of 10.5mm bent to the required profile by cutting both its flanges. Suitable bracing to be provided wherever the flanges are cut with 0.50mm flats.</p> <p>Steel screws, are then fixed to the intermediate channel with the help of connecting clip and in direction perpendicular to the intermediate channel at 457mm centres. 12.5mm tapered edge Glass Fiber Reinforced Gypsum board (conforming to IS-2095-1982) is then screw fixed to ceiling section with 25mm drywall screws at 230mm centres.</p> <p>Screw fixing is done mechanically either with screw driver or drilling machine with suitable attachment. The boards are to be jointed and finished which includes filling and finishing the tapered and square edges of the boards with jointing compound and fiber tape suitable for Gypsum board. A layer up to of 3.00mm thickness of Veneer Plaster is applied followed by two coats of topcoat (primer) at the face of board to give smooth seamless finish. 2 or more coats of plastic emulsion paint (roller finish) of approved shade and make shall be applied.</p> <p>The item includes making all necessary cut outs & frame work for electrical fixtures / air conditioning work coves etc. Shall have edge groove details and cove lighting provisions as per drawings.</p> <p>Rectifying all defects and cracks formed during the construction period before handing over the work complete. The rates shall include for necessary supports, scaffolding and labor. All as per drawing, approval and instructions of the architect / employer.</p> <p>Note: - Horizontal surface shall be measured for the purpose of payment.</p>				
	<p>NOTE:-</p> <ul style="list-style-type: none"> • For item no. 1.1 the false ceiling design can be stepped / curved / architectural design etc however only plan / horizontal surface shall be measured for the purpose of payment. 				
		Sq.Mtr.	57.00		0.00

S.NO.	DESCRIPTION	UNIT	QTY.	RATE	AMOUNT
	<ul style="list-style-type: none"> • Ceiling shall be hung from the existing slab through hanger's. Rate quoted in the tender shall be applicable for all floor levels/ all floor height including scaffolding, etc complete. The rate of falseceiling items also includes 6 mm ply backing for supporting light fixtures in the false ceiling. 				
	FALSE CEILING TOTAL	:			0.00
2.0	PARTITIONS & PANELLING WORK				
2.1	Providing and fixing fully glazed partition including door made 12mm thick toughened glass fixed to the floor / wall / false ceiling with patch fittings. Exposed edges of glass shall be machine cut & polished. Door shall have 1" dia. 2'-0" long SS brushed finish handle (Hettich Make 9250424) on both sides including heavy duty double action floor-spring HETTICH Make Cat. No. 9227856 with steel cover plate, all accessories complete including lock etc. Cost includes cutting and making good the floor, walls, ceiling etc. for fixing floor spring and patch fittings. All glass to glass , glass to ceiling , glass to wooden partition & glass to floor joints shall be sealed with transparent silicon. All complete as per approval of the Architect / Engineer-in-Charge.				
a	FIXED PARTITION	Sq.Mtr.	12.00		0.00
b	DOOR	Sq.Mtr.	6.00		0.00
2.2	LOW HEIGHT PARTITION				
	Providing and fixing in position low height partition of 2100mm / 1200 mm high with 12mm thick toughened glass with 3M glass film as per design including 38mm thick Flap door shutter finished with 1.0mm thick laminate on both side with steam beech wood chowkhat of size 76mm x 65mm approx. made out of aluminum hollow section of 50mm x 50mm size 1.50 thick (Section no. 14525) of JINDAL/ INDAL as internal frame structure placed horizontally & vertically at max distance of 600mm approx c /c both ways. Fixing 12mm thick EDHMR ply on both sides finished with High gloss PU paint / 1.0mm thick ultra gloss laminate of Blue & White / approved shade as per architect instructions. 12mm thick toughened glass (blue shade) as per design fixed with teak wood beading of finished size 1½"x 1" all along the edge.	Sq.Mtr.	11.00		0.00
	Item includes teak wood edging of size 3" x 1 ½" at the exposed edges of the partition. All exposed woodwork to be high gloss PU polished. Shutter hung on 3 nos. heavy-duty SS butt ball bearing hinges of size 100 x 5.5mm with screws etc. The item inclusive Night Latch locks of Godrej make (ULTRA C2) with both side key, s tower bolt etc. complete in all respect. All complete as per approval of the Architect / employer.				
2.3	Providing and fixing in position paneling on existing wall including making niches, cove, design as per drawing shall be made out of aluminum hollow section of 50.80mm x 25.40mm size 2.03 thick (Section No. 14003) of JINDAL / INDAL as internal frame structure placed horizontally & vertically in 600mm x 600mm center to center. Frame work clad with 12mm thick EDHMR ply finished with high gloss PU paint / 1.00mm thick edge laminate in approved shade with groove pattern as per architect instructions. The item also includes 32mmx 25mm steam beech wood moulding finished with melamine polish, scaffolding etc. All complete as per approval of architect/ engineer				

S.NO.	DESCRIPTION	UNIT	QTY.	RATE	AMOUNT
a	Finished with 1.0 mm thick laminate premium range (Basic rate Rs. 550/- Sq.m.)	Sq.Mtr.	70.00		0.00
b	Same as item no. 2.3 but panelling to be Finished with 1.25/1.5mm thick laminate premium range (Basic rate Rs. 850/- Sq.m.) instead of 1mm thick laminate.	Sq.Mtr.	8.00		0.00
c	Same as item no. 2.3 but panelling to be Finished with 4mm thick annealed GRIHA rated lacquered glass instead of 1mm thick laminate (of Saint-Gobain make or equivalent) coated with PU lacquer (minimum 60 micron thick or more) of color Vert Onyx and lemon green as per approval of Engineer -in -charge / Architect . Glass fixed with compatible neutral core silicon / lacquered glass compatible double sided tape (SGG PlaniFIX or equivalent) . Silicon / tape should not react with coating on glass & render even color tone when viewd from glass side. Lacquered glass must be made industrially; must be opaque (if viewed against a support wall) must have panel to panel color consistency (measured by Minolta spectrophotometer CM5081 or eq.); highly durable (passes PERSOZ hardness test for min. 220 oscillatios or more); humid resistant (conforms to BS EN 1036 1999 or eq); environmentally friendly (no lead, no arsenic, no copper, no formaldehyde); appropriate recycled content (12% post industrial / 6% post consumer or eq.); compressive strenght (1000 MPa) & tensile strenght (40 MPa),same as float glass. All complete as per approval of Engineer -in -charge /	Sq.Mtr.	2.00		0.00
d)	Same as item no. 2.3 but panelling to be cladded with 12 mm thick flute Panel (Basic rate Rs. 2500/- Sq.m.) instead of 1mm thick laminate.	Sq.Mtr.	7.00		0.00
2.4	Providing and fixing frosted / striped / designer glass film of 3M, Avery Dennison or equivalent (basic rate of film Rs. 600/ Sq.m.) on existing glass as per manufacturer's specification. All as per drawing, approval and instructions of the Architect / Eingneer-in-charge.	Sq.Mtr.	10.00		0.00
2.5	Providing, fabricating & fixing in position Aluminium Composite Panel (ACP) with framing of aluminum hollow section of 53mm x 38.10mm size 1.80 thick (Section no. 14089) of JINDAL / INDAL as internal frame structure placed horizontally & vertically in 600mm x 600mm center to center. Joint free ACP to be in minimum 600mm width panels or distributed equally as per the direction of Bank/Architects and site condition.	Sq.Mtr.	20.00		0.00
	Panels to be fixed to the frame with adhesives as per manufacturer's specification. ACP shall be of minimum 4mm thickness (0.5mm+3mm+0.5mm). Colour of ACP shall be as per bank's preference. Additional Aluminium Sections to be provided to fix the AC units near the machine area at the highest position. All complete as per approval & instructions of the architect/ employer.				
	Note For Item No. 2.1, 2.2,2.3, 2.4, 2.5 : - For the purpose of payment partition shall be measured including the area of door / door frames up to false ceiling height.				
a)	Framework shall be rigidly secured to floor, bottom of slab & existing walls at 600mm c/c with dash fasteners.				
b)	For All Full height partitions (Toughned Glass, Solid, Partly Glazed) framework and ply shall be provided up to the bottom of slab. The item also includes scaffolding for maximum height upto 4000 mm from floor etc complete				

S.NO.	DESCRIPTION	UNIT	QTY.	RATE	AMOUNT
c)	Center to center spacing may vary to make provision for fixing dado rail / to adjust the level of glass or for fixing counter / storage units or otherwise as per site requirement.				
d)	No extra payment shall be made for reduction in framework, opening as indicated in the drawing or as instructed by the Engineer-in-charge. Framework shall be rigidly secured to floor, walls and ceiling by dash fasteners etc. at maximum 600mm c/c.				
e)	For full height solid / partly glazed partitions rate also includes providing and fixing steam beach chowkhat, doors with laminate / veneer as per the specification of the items including handles, locks, door closer, door stopper, Hinges / patch fittings, accessories etc of approved make. Ref. HETTICH Cat. 1) FOR door closer Article no. : 9227817 (2) Handle Article no. 922768 (3) Mortise cylinder lockcase Article no. 9228136 (4) Europrofile Clynder Lock Article No. 9228171 (5) Ball bearing butt hinges 102 x 76 x 3 mm article No.9287297(6) Door stooper: 9228709 (7) Cylindrical door lock 9228335				
f)	For all full height partitions (solid / partly glazed / toughend glass) rate also includes providing and doing infill of 50mm glass wool insulation having density of 24kg/ cu.m. with polybag covering on either sides in partition framework.				
2.0	PARTITION WORK TOTAL	:			0.00
3.0	DOOR'S / WINDOWS				
3.1	FIRE DOORS - Providing and fixing with all frame, panic bar, and accessories as below.				
	Providing and fixing of Hollow metal fire rated doors as per IS 3614. Pressed Galvanized steel with the following specification. Recommended fire door should have been tested earlier of similar design at CBRI for maximum rating of 2hrs. Individual Test certificates should also be provided. Doors should be finished in Thermo setting Powder Coating desired RAL Shades. Approved manufacturer Navair / Shakti Harmann or equivalent subject to architect's approval. And should be ISO Certified company. Door frame shall be double rebate profile of minimum size 153mm x 77mm made out of 1.50mm minimum thick galvanized steel sheet. Frames shall be Butt jointed and field assembled with self bolted. The frames should be finished with Thermo setting Powder Coating in desired Shade. All provision should be mortised, drilled and tapped for receiving appropriate hardware. Frames should be provided with back plate bracket and anchor fasteners for installation on a finished plastered masonry wall opening. Door leaf shall be minimum 46mm thick fully flush single skin door with vision lite. Door leaf shall be manufactured from 1.0mm minimum thick galvanised steel sheet. The internal construction of the door should be rigid reinforcement pads for receiving appropriate hardware. The infill material shall be Rock wool treated with Viper FRS881LH. All doors shall be factory prepped for receiving appropriate hardware and provided with necessary reinforcement for hinges, locks, and door closers. The edges should be inter locked with abending radius of 1.4mm. For pair of doors astragals has to be provided on the meeting stile for both active and inactive leaf.				

S.NO.	DESCRIPTION	UNIT	QTY.	RATE	AMOUNT
	Vision lite wherever applicable should be provided as per manufacturers recommendation with a beeding and screws from inside. However the glass should be contraflam Door Lite 11mm clear 120 min fire rated and partially insulated (EW120), Non Wired Toughened, interlayered glass having a sound reduction and Impact Resistance as per EN12600 standard from Saint Gobain. All doors and frames shall be finished with Powder coating in desired Regular Shades.				
	VISION PANEL				
	Providing & fixing of Contra flam Door Lite 11mm thick, 120 min fire rated (EW120) clear, Non Wired Toughened Inter layer edglass with a light transmission of 86% and a sound reduction and is to be used as vision panel including cost of fire rated ceramic tape and moulding / beading all complete. NOTE : THE MINIMUM SIZE OF VISION PANEL SHOULD BE 220 x 370mm.	Sq.Mtr.	2.00		0.00
3.2	Providing & fixing Solid Flush Door 30 mm thick flush door with teak/Sal wood chowkhat with 10 mm teak wood lipping on all sides finished with 1.0 mm thick laminate of approved shade on door and chowkhat fixed on both sides. The door is to be provided with 12 x 200 mm SS Aldrop, 150 mm SS handles (2 nos), 200 mm long SS tower bolt, Mortised Lock, hydraulic door closer , spring loaded SS Door stopper, heavy-duty SS ball bearing butt hinges 100 x 5.5 mm (4 Nos. per shutter) AND with screws. All wood surfaces to be treated with 2 coats of Fire retardant paint Viper of navair/equivalent and finally finished with malamine polish complete to the satisfaction of Bank's Engineer. TOTAL NUMBER OF DOORS-4	Sq.Mtr.	6.50		0.00
	DOOR / WINDOWS TOTAL	:			0.00
4.0	WORKING COUNTERS / TABLES				
4.1	Providing and fixing 750mm wide staff counter made of 18mm thick EDHMR board . Working top and edges of the worktop shall be finished with 12mm thick Corian curved to shape as per design.				
	Front bracing panel made of 18mm thick EDHMR board finished with 4.0mm thick lacquered Glass (of Saint-Gobain make or equivalent) coated with PU lacquer (minimum 60 micron thick or more) of approved shade. All edges of EDHMR board shall be sealed with teak wood edging of size 1/4"x3/4" finished with high gloss PU Paint. The counter to be provided with platform type of foot rest of size 450mmx 600mm.				
	Drawer unit made out of 18mm thick EDHMR board having 2nos. drawers at top and one no. openable shutter below. Drawers Base, Back & sides @ 12mm thick EDHMR board. Front @ double layer, 12mm thick EDHMR ply . All drawers shall run on hydraulic drawer slides. Top drawer shall have partitions as per banks requirement made of 6mm thick EDHMR ply Shutter shall be provided with hydraulic auto closing hinges (Ref Hettich Artical No. 9281432 & 9281434 - 2 nos. per shutter). All shutters / drawers shall be provided with lock, 150mm long S.S. brush finish handles, All exposed edge finished with the teak wood edging. All surfaces exposed to view shall be finished with 1.0mm thick ultra gloss laminate				

S.NO.	DESCRIPTION	UNIT	QTY.	RATE	AMOUNT
	Each seat shall be provided with keyboard pull out tray of size 480-500 x 240-260mm minimum made of 0.8mm thick CRCA steel duly powder coated, of minimum thickness 45 micron, with metallic roller slides (Telscopic channels Ref Hettich Article No. 9193319) on both sides and shall be fixed to the bottom of worktop surface with the help of screws, readymade metal powder coated CPU trolley, grommet & footrest .Item includes w height partition of 2100mm / 1200 mm high with 12mm thick toughened glass with 3M glass film above working top with patch fittings. All exposed wood shall be high gloss PU polished and non-laminate surface to be enamel painted. All complete as per approval and instructions of the Architect / employer.	R.Mtr.	7.00		0.00
4.2	<p>Providing and placing the tables as per drawing and the following specification</p> <p>Table top made out of 18mm thick EDHMR board (Double Layer 18+18mm)over hard wood frame work. Top including edges finished with 1mm thick laminate of approved make and shade. Item includes 10mm thick clear toughened Glass on the table top with all beveled edges machine cut & polished. Bracing panel, sides made of 18mm thick EDHMR (Double Layer 18+18mm) board finished with 1.0mm thick laminate & flute12mm thick flutes. All exposed edge of board shall be finished with the steam beech wood edging.</p> <p>Top supported on side credenza and drawer unit as per detail drawing. Each table shall be provided with 1 no. grommet, 1 no. CPU Trolley,1 no. footrest, 1 no. prefabricated computer key board tray including drawer slides 12.5" x 22" tray with 14" telescopic slides including L – brackets for securing to the table top.</p>				
	Side credenza finished with 1mm thick laminate top and drawer unit made out of 18mm thick EDHMR board. Drawers Base, Back & sides @ 12mm thick EDHMR ply. Front @ double layer, inside of 12mm thick ply, outside 18mm thick EDHMR board. All external surfaces shall be finished with 1.0mm thick laminate of approved shade and all internal surfaces shall be finished with .8 mm thick laminate. All drawers shall run on drawer slides.				
	All exposed edge finished with the edges steam beech wood edging. All woodwork to be melamine polish and all non laminated surfaces to be finished with two or more coats of spirit polish. All complete including lock, auto- closing hinges, 6" long S.S. handles, studs for adjustable shelving etc.				
a)	T1 1650mm x 800mm x 750mm high with side credenza 1650mm x 450mm x 712mm & drawer unit 450mm x 600mm.	Nos.	1.00		0.00
4.3	Providing and placing writing desk with cheque drop box of size 900mm x 300mm and shape as per drawings and made of 18mm thick EDHMR board finished in 1.0mm thick laminate.Top having 12mm thick clear float glass. Shutter below shall be partly glazed having 6mm thick clear float glass. All exposed edges of EDHMR board sealed with steam beech wood beading of size 6mm x 19mm . All beading and exposed wood shall be melamine polished and non- laminate surface to be finished with two or more coats of spirit polish. All complete as per approval of the Architect / employer.	Each	1.00		0.00

S.NO.	DESCRIPTION	UNIT	QTY.	RATE	AMOUNT
4.4	Providing and fixing in position Grahak Mitra table 1200 X600x1050(h) mm wide (as per design) with 1 mm thick high gloss laminate in approved make comprising of the following complete in all respects (REFER DRAWING):Work top to be made with 19 mm thick HDHMR Board finished with with 1 mm thick gloss laminate in approved make all complete. Inside portion of the HDHMR Board shall be finished with 1 mm thick laminate and edges shall be finished with matching 0.8 mm PVC edge banding all complete as per Architect. Edge of table is made with double board finished with matching 0.8 mm PVC edge banding. Horizontal drop box (apron) & Horizontal fascia to be made with 19 mm thick HDHMR Board finished with 1 mm thick high gloss laminate. all complete on all exposed fascia as per Architect. Vertical supports made with 19 mm thick HDHMR Board finished with 1 mm thick high gloss laminate on exposed fascia as per Architect. CPU stand and keyboard tray shall be provided. The item to include all necessary hardware and fittings in SS finish, Locks in drawer unit, MATCHING PVC Edge banding to all edges, providing SS wire manager etc. Necessary SS D-brackets required for fixing the glass are to be provided. All inside edges are finished with 0.7 mm laminate as/approval. Note:- Contractor to use masking tapes etc. to prevent any polishing from affecting the laminate. Aluminium PROFILE HANDLES (as/approval) of make Inox/ hettich/ hafele to be Used instead of handle. The item to include drawer unit (comprising of 3 Nos. of drawers upto 400 mm wide) in table and Footrest 75 X 50 mm made of 2nd class teakwood member to be fixed in table finished	Each	1.00		0.00
4.5	Providing and placing Lunch room table 1500 x 750 x 750mm having following specification:- Top made of 18mm thick EDHMR board over hard wood frame work finished with 1.0mm thick laminate of approved shade. All exposed edges sealed with steam beech wood moulding of size 65mm x 37mm. Leg supports and bracing panel made of 18mm thick EDHMR board double layer (cut to shape) as per design finished with 1.0mm &1.25mm thick laminate of approved shade. All exposed edges of board shall be finished with steam beech wood edging. All wood work to be finished with two or more coats of PU polish over sealer. All complete as per approval of architect/ employer.	Nos.	1.00		0.00
4.6	Providing and fixing notice board size 900mm x 1200mm approx. or as required / directed with open able shutter on the front. Made out of 18mm thick EDHMR board frame and outer frame in 65 x 37mm Steam beech wood section, concealed hinges, locking arrangement, glass of (5.5mm thick) with rear panel of SITATEX board, covered with fabric of approved shade. (Basic rate Rs. 150/- per mtr, 48" width) fixed to back ply 6mm thick. All complete including melamine polish in stain of required shade. All complete as per design and approval of	Each	1.00		0.00
4.0	WORKING COUNTERS/ TABLES TOTAL :				0.00
5.0	STORAGE				
5.1	Providing and fixing 400mm deep low ht. Storage with following specification: -				

S.NO.	DESCRIPTION	UNIT	QTY.	RATE	AMOUNT
	Outer framework i.e. top, sides, shutters, shelving of 18mm thick EDHMR board. Back shall be of 8mm thick EDHMR ply. Storage top shall be finished as mentioned below. All other surfaces exposed to view to be finished with 1.0mm thick Ultra high gloss laminate/ High gloss PU paint. All internal surfaces shall be finished with 0.8mm thick laminate. Skirting shall be finished with 1.0mm thick metallic laminate. All edges of the EDHMR board shall have Steam beech wood edging of 6mm x 19mm . All shutters shall be provided with lock (1 no. for two shutters), auto closing hydraulic hinges (2 nos. per shutter), brass catchers, 150mm long S.S. brush finish handles, 1 no. Intermediate shelf shall rest on studs for adjustable shelving etc. Woodwork protected with melamine polish. Entire surfaces left without lamination to be finished with two or more coats of spirit polish. All complete as per drawing, approval and instructions of the Architect / employer				
a	Storage top shall be finished with 1 mm thick laminate of approved shade.	Sq.Mtr	9.00		0.00
b	Providing & fixing kitchen storage/ low height box cupboards 450mm deep with all sides made with 18mm HDHMR board except back side with 8mm thick HDHMR Board. The front and top & side to be finished with 1 mm thick laminate finish. Shelves to be 18 mm thk. HDHMR at approx. 400 mm distances with 6 mm HDHMR finished with laminate both sides to be fixed at the back. The shutters to be 18mm HDHMR with 1 mm laminate (decorative finish) on all exposed & internal surfaces. All shutters to have 2mm PVC edge binding tape, complete including S.S.(150 mm) long handles magnetic catchers, hinges, locks, tower bolts, etc (Dorma, Hettich, ozone).The item includes interior to be finish with 0.8mm white colour laminate complete to the satisfaction of EI / Architect. Only front elevation to be considered for area calculation. Item shall be modular/ factory made customised as per actual on-site measurements.	Sq.Mtr.	2.00		0.00
5.2	Providing and fixing Louvered Shutter Cabinet for main panel fabricated out of 18 mm thick Fire Retardant MDF (FRMDF) (conform to BS 476 : Part 7 Class 1) finished with putty and fire retardant paint from inside and 1 mm thick laminate of approved make & shade from outside.				
	The item to include powder coated MS louvers in both the shutters of the door of size - 300 mm x 1.2 m				
	The door is to be provided with 12 x 200 mm SS Aldrop, 150 mm SS handles (2 nos), auto closer hinges (3 Nos. per shutter) with necessary screws, hardware. All complete as per approval & instructions of the architect/ employer.				
	Front facia shall be measured for payment. Measurement of height shall be taken from finished floor level up to the finished edge of the cabinet and width shall be from outer edge to outer edge of cabinet. In case of varying heights on either side of partition, average height shall be considered. Measurement shall be taken of the visible front surface (elevation - 2D surface) only.	Sq.Mtr	4.00		0.00
	NOTE:- For Item no.. 5.1, 5.2 Front area shall be measured for the purpose of measurement. For hardware (Ref Hettich (1) Autoclosing hinges Artical No. 9281432 & 9281434				

S.NO.	DESCRIPTION	UNIT	QTY.	RATE	AMOUNT
5.3	Providing and fixing side credenza 4'-6" x 1'-6" x 2' - 4 1/2" with following specification: - Top and edges of the unit shall be finished with 12mm thick Corian as per design Outer framework i.e. top, sides, shutters, shelving of 18mm thick EDHMR board. Back shall be of 8mm thick EDHMR ply. Drawers Base, Back & sides @ 12mm thick EDHMR ply. Front @ double layer, inside of 12mm thick ply, outside 18mm thick EDHMR board. All drawers shall run on hydraulic drawer slides.	Each	3.00		0.00
	All surfaces exposed to view to be finished with 1.0mm thick laminate. Skirting shall be finished with 1.0mm thick metallic laminate. All edges of the EDHMR board shall have Steam beech wood edging of 6mm x 19mm. All complete including lock, auto-closing hydraulic hinges, 6" long S.S. handles, and drawer slides etc. Woodwork protected with melamine polish. Entire surfaces left without lamination to be finished with two or more coats spirit polish. All complete as per drawing, approval and instructions of the Architect / employer.				
5.0	STORAGE TOTAL	:			0.00
6.0	MISCELLANOUS WORK				
6.1	Providing and fixing wall paper on wall, gypsum board ceiling, partition or anywhere else as required with approved adhesive (basic rate of wall paper Rs. 1200/- Sq.m.). All complete as per approval and instructions of the Architect / Engineer-in-charge.	Sq.Mtr	10.00		0.00
6.2	Providing and placing aluminium dust buster mat for entrance door of 19 mm thickness of Euronics/approved make all complete as per the the directions of the Architect/Employer.	Sq.Mtr	2.00		0.00
6.3	Providing and placing SS perforated dustbin with square holes of Euronics/ approved make (Cat No.- AFBR 3FP) of size 200 x 300mm all complete as per directions of Architect / Engineer-in-charge.	Each	5.00		0.00
6.4	Providing and placing in position planter box of size 600mm wide & 450mm high made of 18mm thick EDHMR board. Inside finished with 1.0mm thick laminate and outside finished with 3.5mm thick veneer. Exposed edges of board finished with 6mm thick steam bech wood lipping. All wood work and veneer shall be finished with two or more coats of PU polish over one coat of sealer. All complete as per approval of architect / employer.	Each	3.00		0.00
6.5	Providing and fixing SS LOGO of 450 mm dia. Made of 304 grade stainless steel complete as per approval of client/ architect.	Each	1.00		0.00
6.6	Providing temporary arrangements for functioning of Branch throughout the course of completion of renovation work including temporary shifting of workstations, counters, storages, tables, chairs etc. to enable smooth functioning of the branch during renovation all complete as per the instructions of Architect / Bank's Engineer.	LS	1		0.00

S.NO.	DESCRIPTION	UNIT	QTY.	RATE	AMOUNT
6.7	Dismantling / Demolishing removing existing brick / RCC work , floor tiles, wall tiles, stone, Partition , furniture ,storage (wooden / metal) , door, windows, toilet fitting & fixture , etc. to accommodate the proposed new layout and disposal of unserviceable material to a place permitted by the municipal authorities including making good any damages complete. No unserviceable dismantled material will be allowed to be accumulated at site. Decision of the architect as to what constitute unserviceable material will be final and binding. The amount should include cost for carrying out any other unforeseen items required for the proper execution of the work. All complete as per approval and instructions of the Architect/ employer. Note:- measurement shall be taken of	Sq.Mtr.	65		0.00
	NOTE:- Contractor's are advised to visit the site before quoting for this item. Dismantling to be done in parts as per the instructions with proper support and covering of other areas from dust and falling debris, coordinating with other contractors/ agencies. Including costs of all necessary measures, safety features, nets, scaffolding, lead, lift, cleaning after disposal etc.				
6.8	P/F 10mm thick Glass shelves for BM Cabin with all the necessary fittings as per direction of architect/ Bank.	Sq.Mtr.	2		0.00
6.0	MISCLLANEOUS TOTAL	:			0.00
SUMMARY					
	TOTAL INTERIOR FURNISHING WORKS			Rs.	0.00
	DISCOUNT (IF ANY) (-)			Rs.	0.00
	GRAND TOTAL			Rs.	0.00
	(RUPEES)				