

ESTIMATE FOR INTERIOR WORKS FOR TALUK OFFICE ROAD SIRA (40096)					
<u>S.No.</u>	<u>Item Description</u>	<u>Qty.</u>	<u>Unit.</u>	<u>Rate.</u>	<u>Amount.</u>
	Architects- KULKARNI ASSOCIATES				
	BILL OF QUANTITY for Interior Renovation Works				
I	INTERIOR WORKS:				
A	FIXED FURNITURE:				
1.0	PARTITIONS				
1.1	FULL HEIGHT PARTITIONS - PARTLY GLAZED Providing and fixing metal stud dry wall partition with following specifications: Supporting system comprising of 50x50x1.2mm aluminium hollow box sections at 600mm c/c at floor, middle, door and ceiling level with joints staggered to avoid through joints. The vertical members should touch the ceiling with horizontal ceiling channel at slab / beam bottom. The rate should also include necessary strengthening with studs / tracks or channels at doors and other openings. 12mm Exterior Grade MDF (EG-MDF) Board fixed on both sides with 25mm dry wall screws for the entire height of the partition. Partition fixed with 1.0mm laminate sheet on both sides as per the approved design & pattern including making grooves as per Architectural drawing or as directed by the Engineer-in-charge using approve quality adhesive complete All beech wood members to have minimum two coats of LOW VOC or NO VOC white duco paint finish. All sections used should adhere to the manufacturers guidelines and the contractor has to submit certificate from the manufacturer on usage of their specified sections. Measurement for the partition area shall be considered from floor level to false ceiling level only.	38.01	Sq.M.		
1.2	FULL HEIGHT PARTITIONS - SOLID Same as full height partition partly glazed above but for Fully Solid Partitions without glass panels and other specifications remaining the same. Glass panel area from 1220mm lvl to 2135mm lvl to be replaced with solid partition with 1mm Laminate as per approved design & pattern.	38.09	Sq.M.		
1.3	LOW HEIGHT PARTITIONS This item includes partitions for <u>SWO counters, officer cubicles etc</u> as per the layout plan. Height of the partitions shall be as mentioned in the drawings. Same as full height partition Solid above, but for height of 1220mm from finished floor level, to a neat finish as per drawings and directions etc., complete and including the following: Providing finished section size 70/75 x 8mm thick seasoned second class Teak wood moulding to all exposed edges of partition including applying 2 or more coats of Duco paint including necessary preparatory work for surface preparation with putty, priming coat, sealer coat etc. complete as per sample approved by the Bank. Partition fixed with 1.0mm laminate sheet on both sides as per the approved design & pattern including making grooves as per Architectural drawing or as directed by the Engineer-in-charge using approve quality adhesive complete.	24.92	Sq.M.		
1.4	DOORS IN PARTITIONS				

<u>S.No.</u>	<u>Item Description</u>	<u>Qty.</u>	<u>Unit.</u>	<u>Rate.</u>	<u>Amount.</u>
1.4.1	32MM DOORS IN PARTITIONS - with glass panel: Providing and fixing 32mm thick solid core flush shutter with 85mm x 35mm beech wood frame with rebate alround the jamb and shutter fixed with 1mm Laminate as specified on both sides with glass panel of 8mm clear float glass fixed with 19 x 19mm beading on both sides and glass pasted with 3M privacy film as per design. The rate to include necessary hardware viz., door stopper, door buffer, pair of "H" type handles, Mortise Dead Lock and Euro Profile Cylinder - Key and Knob 70mm SS, SS 2 ball-bearing hinges - (127mm x 76mm x 2.5mm), door closer (all of approved make and quality), ZERO VOC or NO VOC white duco paint finish for all beech wood members, etc., complete as directed.	16.80	Sq.M.		
1.4.2	32MM DOORS IN PARTITIONS : solid Same as 32mm Door in Partitions - with glass panel as per above but for Solid door without glass panel and other specifications remaining the same.	4.20	Sq.M.		
1.4.3	FIRE DOOR FOR UPS ROOM – 900mm-1200mm X 2100mm Providing and fixing in position 120 minutes fire rated 46mm thick Galvanised steel single leaf doors with door frame for opening of size 1000mm x 2100mm with vision panel having test certificate of CBRI or ARAI (covering glass and fittings) of reputed makes.The rate to include labour, conveyance, necessary hardware viz., pair of SS 304 D handles, lock and key, SS 2 ball-bearing hinges - (127mm x 76mm x 2.5mm), concealed door closer (all of approved make and quality), SS 304 kick plate etc. complete as directed.	4.20	Sq.M.		
1.5	WICKET GATE - for SWO Counters Wicket gate specified below may also be used with other low height partitions elsewhere in the branch if required, with height of wicket gate modified suitably. Providing wicket gate made of 32mm solid flush door with alround PVC edge banding / BW lipping and height to match low height partitions. Wicket gate shall be finished with 1.0mm laminate sheet on both faces and shall fixed to partition with 85mm x 35mm beech wood frame on sides with SS hinges as required with handles, stoppers, self lock etc complete. Wicket gate shall have self lock from inside fixed at lower height as per instructions and Bank requirement.	4.50	Sq.M.		
1.6	FIXED GLASS WORKS FOR PARTITIONS : (12MM TOUGHENED GLASS) Providing, making and fixing in position Fixed 12mm toughened glass as fixed glass from Skirting level upto available Ceiling / beam / lintel level and inline with wooden parttions / doors etc as per layout plan. The glass is to be fixed onto the ply/Exterior Grade MDF base with patch fittings and all the edges of the glass to be machine polished for a smooth finish. The work includes cost of all materials, approved hardware, making necessary template before toughening of glass and fixing the same as per site conditions to a neat finished work as per drawings and directions including silicon sealant between glass panels etc., complete.	9.48	Sq.M.		

<u>S.No.</u>	<u>Item Description</u>	<u>Qty.</u>	<u>Unit.</u>	<u>Rate.</u>	<u>Amount.</u>
1.7	<p>12MM TOUGHENED GLASS MAIN ENTRANCE DOOR AND PARTITION DOORS: Providing, making and fixing in position Fixed 12mm toughened glass openable shutters work as per specifications given below and for the openings mentioned. Main Entrance Glass Work comprising of Door opening of approximate size 1830mm x 2135mm - 2440mm in two leaves, and Partition Doors of approximate size 900 - 1065mm x 2135mm - 2440mm. The entire work to be done as per site conditions with following specifications etc., complete as directed.</p> <p>(a) Entrance door - Providing, fixing in position glazed entrance Double door and Single door with patch fitting or approved make (Double Door approx. Size: 1830mm - 1525mm x 2440mm - 2135mm and Single Door approx. Size: 900mm - 1220mm x 2440mm - 2135mm using 12mm toughened glass edge polished. The Door to consist of Heavy Duty Floor spring, Upper Patch, Bottom Patch, Lock Keeper Plate, Euro Profile Cylinder (EPC), "H" Type Handle 32 x 600mm, Door Lock at 915 ht complete as per drawing.</p> <p>(b) The work includes cost of all materials, approved hardware, making necessary template before toughening of glass and fixing the same as per site conditions to a neat finished work as per drawings and directions etc., complete.</p>	7.56	Sq.M.		
2.1	<p>WALL PANELLING IN BANKING HALL /ECORNER Same as Full height Partition - Solid, as per relevant specifications above, but for Wall Panelling. The basic frame work to comprise of 50x25x1.2mm rectangular hollow aluminium section, 12 mm thk Exterior Grade MDF (EG-MDF) cladding as specified, but only on one side, to a neat job as per drawings and directions etc., complete.</p> <p>Providing 18mm thick Exterior Grade MDF jamb for door and window openings of suitable depth as per site conditions and laminated with 1mm thk laminate to match design as per partitions. All beech wood members to have NO VOC or LOW VOC white duco paint finish.</p>	123.64	Sq.M.		
2.2	<p>COLUMN PANELLING Providing and fixing metal stud column panelling with following specifications: Support metal framework on 2 shorter sides made of the following Supporting system comprising of 50x25x1.2mm at rectangular aluminium hollow sections at 600mm c/c at floor, middle, door and ceiling level with joints staggered to avoid through joints. The vertical members should touch the ceiling with horizontal ceiling channel at slab / beam bottom. The rate should also include necessary strengthening with studs / tracks or channels at doors and other openings.</p> <p>12mm EG-MDF fixed on all four sides with 25mm dry wall screws for the entire height of the partition. The 12mm EG-MDF fixed onto the metal framework on the 2 shorter sides and directly onto the column on the 2 longer sides with levelling gattas etc as required. Additional 12mm EG MDF - 100mm high fixed at skirting level Column panelling to be finished as per the following : Skirting level upto 100mm from FFL to have 1.0mm laminate of dark blue colour. From 100mm to 2135mm level to have 12mm MDF Grill board (JALI type MDF sheet) fixed on the EG-MDF on the two longer sides of the column as shown in drawing and painted with white duco paint. The base EG-MDF shall be painted with premium emulsion paint of colour - CORAL RADIANCE-code No 2015 of Asian Apcolite Emulsion or equivalent - before fixing the MDF Grill board.</p>	19.80	Sq.M.		

<u>S.No.</u>	<u>Item Description</u>	<u>Qty.</u>	<u>Unit.</u>	<u>Rate.</u>	<u>Amount.</u>
	Column Panelling to have 6mm toughened lacquered glass - ONE SINGLE PIECE for each side, pasted with adhesive/sealant onto the existing EG-MDF and of blue colour as per Colour Code No. RAL 5017-Traffic Blue - fixed on two shorter sides of the column, to a neat finish as per drawings and directions etc., complete with 12mm x 12mm button beading on the corners. Column Panelling above 2135mm level to have 1mm White colour, Matt finish Laminate on all four sides as shown in drawing. All beech wood members and MDF Grill Board to have minimum two coats of LOW VOC or NO VOC white duco paint finish. All sections used should adhere to the manufacturers guidelines and the contractor has to submit certificate from the manufacturer on usage of their specified sections.				
2.3	WALLPAPER Providing and fixing approved quality wall paper of washable grade including all adhesive, cutting, pasting etc complete. (Basic price Rs 850 per smt excluding tax, transportation, wastage, loading / unloading, etc.,) Note : Measurement will be taken only for wall paper actually pasted at site.	21.00	Sq.M.		
3.1	Grid False Ceiling : Mineral Fibre Tile Providing & Fixing of Mineral Fibre Acoustical Suspended Ceiling System with 15mm Tiles and Exposed GRID. The tiles should have Humidity Resistance (RH) of 90% - 99%, NRC 0.5, Light Reflectance ≥87%, Thermal Conductivity k = 0.052 - 0.057 w/m K, Colour White, Fire Performance UK Class 0 / Class 1 (BS 476 pt The tile shall be laid on Microline / Silhouette profile grid system with 15mm - 16mm white flanges incorporating a 6mm central reveal in white/black colour and with a web height of 38mm and a load carrying capacity of minimum 8 Kgs/M2 & minimum pull out strength of 100 Kgs. Microline / Silhouette, Main Runners & Cross Tees to have mitred ends & "birdsmouth" notches to provide mitred cruciform junctions. The T Sections have a Galvanizing of 90 grams per M2 and need to be installed with Suspension system as per manufacturers details. The Instalation to comprise main runner spaced at 1200mm centres securely fixed to the structural soffit using US Boral / Gyproc / Armstrong suspension system (specifications below) at 1200mm maximum centre. The First/Last suspension system at the end of each main runner should not be greater than 450mm from the adjacent wall. Flush fitting 1200mm long cross tees to be interlocked between main runners at 600mm centre to form 1200 x 600 mm module. Cut cross tees longer than 600mm require independent support. 600 x 600mm module to be formed by fitting 600mm long flush fitting cross tees centrally between	157.16	Sq.M.		
	the 1200 mm cross tees. Perimeter trim to be Wall angles of size 3000mm x 19mm x 19mm, secured to walls at 450 mm maximum centres.				

<u>S.No.</u>	<u>Item Description</u>	<u>Qty.</u>	<u>Unit.</u>	<u>Rate.</u>	<u>Amount.</u>
3.2	<p>PLAIN GYPSUM FALSE CEILING</p> <p>Providing and fixing Concealed Grid suspended ceiling system of 12.5mm Gypsum Boards / Standard Plaster Boards fixed to ceiling Frame Work as per manufacturers instructions and details for a concealed grid key lock suspended ceiling system consisting of following:</p> <p>27 x 37 x 1.6mm Soffit Clip, 5mm suspension rod / 25 x 10 x 0.5mm Ceiling Angle, adjustable spring loaded suspension clip / 2.64mm dia Connecting Clip, 20 x 28 x 30 x 0.5mm Perimeter Channel, Top Cross Rail of 3000mm long of 0.55BMT Furring Channel / 15 x 45 x 15 x 0.9mm Intermediate Channel and 4000mm long made of 0.5mm BMT the Top Cross Rail / 80 x 26 x 0.5mm Ceiling Section to be suspended from ceiling at every 1200mm and Furring / Intermediate Channel to be fixed to Top Cross Rail / Ceiling Section at every 600mm to make a grid of 1200 x 600mm.\</p> <p>All sections used should adhere to the manufacturers guidelines and the contractor has to submit certificate from the manufacturer on usage of their specified sections.</p> <p>Further the rates to include cutouts for lighting fixtures / AC grilles / Fire Alarm Detectors etc., along with necessary strengthening and supports for fixing of these. The board joints are to be flush finished with jointing compound and paper tape etc., complete as directed.</p> <p>The ceiling shall be finished with 2 coats of premium emulsion paint over primer putty etc complete. Rates to include vertical faces in false ceiling upto 150mm as per drawing etc. completed as directed.</p>	97.36	Sq.M.		
4.0	STORAGE UNITS:				
4.1	<p>LOW HEIGHT STORAGE UNITS</p> <p>Providing, making and placing in position Storage Units of 1220mm high abutting wall and 760mm high as back credenza or abutting partition made in 18mm EG-MDF to all members except table top and 25mm block board for table top and 8mm EG-MDF for backing sheet . The top and front facia of the storage unit to have 1mm thick laminate. All other exposed faces of the unit to have 1mm Laminate as specified and all unexposed faces to have 0.8mm Laminate. NO VOC or LOW VOC white duco paint finish for all wooden members and all necessary hardware viz., 'W' or wing hinges, locks, handles, tower bolts etc., and PVC edge banding / BW lipping 20mm x 6mm etc., as per drawings and directions etc., complete.Storage units shall have a internal horizontal shelf of 19mm block board finished with 0.8mm laminate on both sides with PVC edge banding / BW lipping polished melanine finish.</p>	36.51	Sq.M.		

<u>S.No.</u>	<u>Item Description</u>	<u>Qty.</u>	<u>Unit.</u>	<u>Rate.</u>	<u>Amount.</u>
B	LOOSE FURNITURE:				
5.1	BRANCH HEAD TABLE: Table : 1800 x 900mm x 760mm Side Runner : 1065 - 1220mm x 450mm x 760mm Providing, making and placing in position Executive Table and Side Table with following specifications. Main Table and side Table top and to be made in 25mm block board with 6mm thick acrylic solid surface (Corean) . including 10mm glass top to shape 1 1/2" hole cut for wire manager; cables etc. The front side of the table to have a inverted " C " made with 2 x 18mm thick EG-MDF cladded with pvc edge strip on the front and the verticals towards the modesty panel. The modesty panel to have 18mm EG-MDF cladded with 6mm thk toughened lacquered glass in blue colour as specified. The " L " shaped table top on the back side to have 50mm edge alround and to be cladded with 1mm thick laminate. All other members to be with 18mm EG-MDF and all exposed faces of the table to have 1mm thick lamiante as specified. All the edges of 18mm EG-MDF to have PVC edge banding / BW lipping 20mm x 6mm maline polished. One readymade CPU trolley with castors. One Molded Key Board Tray with mouse pad with channels etc., One Three Drawer Unit made with 18mm EG-MDF and 12mm EG-MDF . The unit to have 3nos equal drawers. The rate to include all necessary hardware viz., telescopic drawer channels, handles, locks, etc., and edges finished with PVC edge banding / 20mm x 6mm beech wood edge lipping etc.	1.00	Each.		
	Side Table having one pedestal unit with 450mm wide having one drawer & one shutter with 1no internal shelf made with 18mm EG-MDF and 19mm plywood all laminated and with necessary hardware viz., ' W ' hinges, handles, locks, tower bolts, etc., and PVC edge banding / 20mm x 6mm beech wood edge lipping etc. All the unexposed faces to have 0.8mm Laminate. Ready Made Modular Foot Rest - 400mm x 350mm x 65mm. The cost to include all materials, labour etc., for a finished item of work as per drawings and directions etc., complete.				
5.2	OTHER OFFICER's EXECUTIVE TABLES: Table : 1500 x 760mm x 760mm Side Runner : 915 - 1050mm x 450mm x 760mm Providing, making and placing in position Executive Table and Side Table with following specifications. Main Table and side Table top to be made in 25mm block board with 1mm thk laminate of shade and pattern on top. The front side of the table to have a inverted " U " made with 2 x 18mm thick EG-MDF finished with 1.0mm laminate incuding the verticals towards the modesty panel. The modesty panel to have 18mm EG-MDF cladded with 1mm Laminate as specified. The " L " shaped table top on the back side along with side tabe to have 49mm edge alround, which is to be achieved by adding a 75mm piece of 18mm EG-MDF to the table top from bottom. All other members to be with 18mm EG-MDF and all exposed faces of the table to have 1.0mm laminate as specified. All the edges of 18mm EG-MDF to have 20mm x 6mm beech wood lipping /PVC edge banding. Table top to be provided with equal sized 8mm thk clearfloat glass with edges polished. One readymade CPU mobile pedestal. One Molded Key Board Tray with channels etc. One Three Drawer Unit made with 18mm EG-MDF and 12mm EG-MDF .	7.00	Each.		

<u>S.No.</u>	<u>Item Description</u>	<u>Qty.</u>	<u>Unit.</u>	<u>Rate.</u>	<u>Amount.</u>
	<p>The unit to have 3 equal drawers. The rate to include all necessary hardware viz., telescopic drawer channels, handles, locks, etc., and 20mm x 6mm beech wood /PVC edge banding etc.,</p> <p>Side Table having one pedestal unit with 450mm wide having one drawer & one shutter with 1 no internal shelf made with 18mm EG-MDF and 19mm plywood with necessary hardware viz., ' W ' hinges, handles, locks, tower bolts, etc., and 20mm x 6mm beech wood /PVC edge banding etc and finished with 1.0mm laminate</p> <p>Table top to be provided with equal sized 8mm thk clearfloat glass with edges polished. All the unexposed faces to have 0.8mm Laminate.</p> <p>Ready Made Modular Foot Rest - 400mm x 350mm x 65mm.</p> <p>The cost to include all materials, labour etc., for a finished item of work as per drawings and directions etc., complete.</p>				
5.3	<p>CLERK TABLE</p> <p>Same as Officer and Executive table above but for Table top size 1375mm x 610mm x 760mm (h) but without side runner and other specifications remaining the same.</p>	1.00	Each.		
5.4	<p>GRAHAK MITRA / TECH MITRA TABLE:</p> <p>Size : 1200 x 600mm x 760mm</p> <p>Providing, making and placing in position Grahak Mitra Table with following specifications.</p> <p>Main Table Top to have 25mm block board. The vertical supports of the table is to be made with two 18mm EG-MDF finished with 1mm Thk Laminate.</p> <p>The modesty panel to have 18mm EG-MDF clad with 1mm Laminate as specified.</p> <p>All other members to be with 18mm EG-MDF and all exposed faces of the table to have 1mm Laminate as specified to be used. All the edges of 18mm EG-MDF to have 20mm x 6mm beech wood /PVC edge banding.</p> <p>One readymade CPU mobile pedestal.</p> <p>One Molded Key Board Tray with channels etc.,</p> <p>One pedestal of 400mm width having Three Drawer Unit made with 18mm EG-MDF and 12mm EG-MDF. The unit to have one vertical filing drawer at bottom and two equal drawers on top. The rate to include all necessary hardware viz., telescopic drawer channels, handles, locks, etc., and 20mm x 6mm beech wood /PVC edge banding etc.,</p> <p>Table top to be provided with equal sized 8mm thk clearfloat glass with edges polished.</p> <p>All the unexposed faces to have 0.8mm Laminate.</p> <p>Ready Made Modular Foot Rest - 400mm x 350mm x 65mm.</p> <p>The cost to include all materials, labour etc., for a finished item of work as per drawings and directions etc., complete.</p>	1.00	Each.		

<u>S.No.</u>	<u>Item Description</u>	<u>Qty.</u>	<u>Unit.</u>	<u>Rate.</u>	<u>Amount.</u>
5.5	<p>SINGLE WINDOW COUNTERS:- Counter : 1500-1650mm x 900-975mm x 760mm, Side Runner : 1050-1200mm x 450mm x 760mm- Providing, making and placing in position Single Window Counters along with necessary Half height partitions above (The partitions will be measured and paid as per Half Height Partitions) with following specifications and as per dimensions specified.</p> <p>Table top of main table and side table to be made in 25mm block board with 6mm thick acrylic solid surface (Corean) and double thickness at edges alround. The acrylic soild surface to continue in the front side with curvature from the front table top to the modesty panel in front with cove lighting provision.</p> <p>All other members to be with 18mm EG-MDF / 2 Nos. of 6mm Flexi Plywood in curvature (which should be achieved with a frame work of 50mm x 50mm sal wood frame to be fixed from the front modesty panel / apron and the bottom of this niche to have provision of cove lighting with LED strips) and all exposed faces of the table to have 1mm thk laminate as specified in the drawing to be used.</p> <p>Front of SWO Counter to have about 100mm high skirting made of 12mm EG-MDF board fixed at floor level and finished with 1.0mm laminate of dark blue colour.</p> <p>All the edges of 18mm EG-MDF to have 20mm x 6mm beech wood /PVC edge banding.</p> <p>One readymade CPU trolley with castors.</p> <p>One Molded Key Board Tray with mouse pad with channels etc.</p>	5.00	Each.		
	<p>One Three Drawer Unit made with 18mm EG-MDF and 12mm EG-MDF. The unit to have 3nos equal drawer and each drawer shall be fixed with self locks. Drawers shall have Cash Denomination Partitions made of 12mm ply laminated. The rate to include all necessary hardware viz., telescopic drawer channels, handles, hinges, etc., and 20mm x 6mm beech wood /PVC edge banding etc.</p> <p>One Side Table with shutters made with 25mm block board top and 18mm EG-MDF for all other members with necessary hardware viz., ' W' hinges, SS handles, locks, SS tower bolts, etc., and 20mm x 6mm beech wood /PVC edge banding etc and finished with 1.0mm laminate.</p> <p>All the unexposed faces to have 0.8mm Laminate.</p> <p>Ready Made Modular Foot Rest - 400mm x 350mm x 65mm.</p> <p>All wooden members to have minimum two coats of NO VOC or LOW VOC white duco paint finish.</p> <p>Each Single Window Counter to have half height partitions on either sides as per item 1.2 above.</p> <p>Each Single Window Counter to have provision for 12mm thick toughened glass in the front and sides as per relevant item measured separately.</p> <p>The cost to include the " L " shaped Single Window Counter and to include all materials, hardware, labour for a neat and finish job as per drawings and directions etc., complete.</p> <p>The Corean sheets/area shall be measured separately under relevant item elsewhere in this BOQ.</p>				
6.0	<p>12MM TOUGHENED GLASS DIVIDERS FOR SINGLE WINDOW COUNTERS:- Providing, making and fixing in position 12mm thick toughened clear float glass dividers in the front side of half height partitions of Single Window Counters of approximate size 1650mm x 500mm - 100mm in tapered shape. All the edges of the glass to be polished for a smooth finish and the glass is to be fixed with " D " brackets from above skirting level. The cost to include all materials, labour, hardware etc., for a neat finished job as per drawings and directions etc., complete.</p>	4.00	Each.		

<u>S.No.</u>	<u>Item Description</u>	<u>Qty.</u>	<u>Unit.</u>	<u>Rate.</u>	<u>Amount.</u>
7.0	12MM TOUGHENED GLASS FOR FRONT PORTION OF SINGLE WINDOW COUNTERS (TRANSACTION SIDE):- Providing, making and fixing in position 12mm thick toughened glass in the front side and shall be in 2 nos of separate sizes. Lower part shall be fixed with a glass panel of size 1500-1650 x 380mm with a central cut out of 200mm x 150mm. Uppper part shall be fixed with a glass panel of size 1500-1650 x 450mm. A gap of 50mm shall be maintained between the two glass panels. All the edges of the glass to be polished for a smooth finish and the glass is to be fixed with " D " / "L" brackets as required. The cost to include all materials, labour, hardware etc., for a neat finished job as per drawings and diretions etc., complete.	5.63	sqm		
8.0	12MM TOUGHENED GLASS ON LOW HEIGHT PARTITIONS BETWEEN SINGLE WINDOW COUNTERS: Providing, making and fixing in position 12mm thick toughened glass in sizes as per design with cut out of 200mm x 150mm at position to match Voucher tray. All the edges of the glass to be polished for a smooth finish and the glass is to be fixed with " D " brackets. The cost to include all materials, labour, hardware etc., for a neat finished job as per drawings and diretions etc., complete. Glass size shall be as per length of low height partiton after leaving about 300mm solid portion at both ends Item includes providing Voucher tray of size 200 x 200, made of 19mm BB-laminated with BW lipping /PVC edge banding etc and fixed onto the low partition with all hardware etc complete	4.32	Sq.M.		
9.1	FLOOR MOUNTED WRITING DESK: Providing, making and placing in position Wall Mounted Circular Writing Desk 900mm dia x 760mm with following specifications. A Octogonal support boxing is to be made 450mm at floor level tapering upwards to 600mm at 900mm from floor made in 12mm EG-MDF cladded with 1mm Laminate. A top to be provided at 900mm level from floor to be made with 25mm Block Board cladded with 1mm Laminate which will have verticals made with 12mm EG-MDF cladded with 1mm Laminate upto the table top level of 1050mm from floor level. The Writing Desk Circular Top to have 12mm thk toughened glass with 25mm chamfered bull nosing alround. All members to be with 12mm / 18mm EG-MDF and all exposed faces to have 1mm Laminate as specified. All the edges of 12mm / 18mm EG-MDF to have 20mm x 6mm beech wood /PVC edge banding. All the unexposed faces to have 0.8mm Laminate. The cost to include all materials, labour etc., for a finished item of work as per drawings and directions etc., complete.	1.00	Nos / each		

<u>S.No.</u>	<u>Item Description</u>	<u>Qty.</u>	<u>Unit.</u>	<u>Rate.</u>	<u>Amount.</u>
9.2	WALL MOUNTED WRITING DESK:- Providing, making and placing in position Wall Mounted Writing Desk 760mm x 300mm x 450mm with following specifications. The entire unit is to be made with 18mm EG-MDF clad with 1mm Laminate as per drawing. The Writing Desk to have 12mm thick toughened clear float glass with 25mm chamfered bull nosing around at top fixed with SS supports. All members to be with 18mm EG-MDF and all exposed faces to have 1mm Laminate as specified. All the edges of 12mm / 18mm EG-MDF to have 20mm x 6mm beech .wood /PVC edge bandingAll the unexposed faces to have 0.8mm Laminate OR and members of beech wood to have minimum two coats of NO VOC or LOW VOC white duco paint finish. The cost to include all materials, labour etc., for a finished item of work as per drawings and directions etc., complete.	1.00	Nos / each		
10.0	CASH COUNTING TABLE 2.30mX1.5mX0.75m Providing & fixing CASH COUNTING Table. Table top to be made of 19mm thk BWR Block Board with additional 19mm thk BWR BB at edges for increasing the thickness of the table top. Table main and intermediate supports to be made of 1.5" x1.5" thk wooden frame work at 1'-6" c/c on bothsides covered with 6mm thk BWR plywood , table edges to be fixed with wood beading [teak wood or equi.] of size 2"x1.5" thk with a cornice design as shown in the drawing. Table to have foot rest of 4"x2" size , fixed to the table supports. All outer exposed surface of table to be covered with approved 1mm thk Laminate with necessary SS inlays and. All as per drawings and/or instructions of the architect. All materials to be approved by the architects.	1.00	No.		
11.00	VEDIO CONFERENCE TABLE- 23' X 8' X 2'6" Providing & fixing Traphizoidal shape Conference Table . Table top to be made of 19mm thk BWR Block Board with additional 19mm thk BWR BB at edges for increasing the thickness of the table top. Table main and intermediate supports to be made of 1.5" x1.5" thk wooden frame work at 1'-6" c/c on bothsides covered with 6mm thk BWR plywood, table edges to be fixed with wood beading [teak wood or equi.] of size 2"x1.5" thk with a cornice design as shown in the drawing. Table to have foot rest of 4"x2" size, fixed to the table supports. All outer exposed surface of table to be covered with approved 4mm thk veneer with necessary SS inlays and grooves and finished with melamine polish. Frames with openable shutters to be provided to run wiring below the table top and in apron and wire-managers to be provided as shown in the drawing. Cost inclusive of fixing 12mm thk clear float glass with edges machine polished in the centre of the table , fixed to the table with wood beading. All as per drawings and/or instructions of the architect.. All materials to be approved by the architects. SIZE 23'-00"X8'-0"	1.00	No.		
C	OTHER WORKS:				
12.0	ROLLER BLINDS Providing and fixing in position of Roller Blinds of approved Fabric of Hunter Douglas / Mac / Vista Levalor make or approved equivalent of approved shade etc., as directed. Basic Rate 1100/sqm excluding GST transportation etcc	24.30	Sq.M.		

<u>S.No.</u>	<u>Item Description</u>	<u>Qty.</u>	<u>Unit.</u>	<u>Rate.</u>	<u>Amount.</u>
13.0	WOODEN FLOORING Providing and fixing laminated wooden flooring as per and equivalent to the following:- Providing and fixing laminated wooden flooring with AC-4 GRADE and with plank size apprx 1200 x 200 and having locking arrangement at plank joints. Flooring to be laid on a underlayer of foam with all accessories like end profile, Transition profile, reducer, stair nosing etc complete. Skirting to be included in the item. INSTALLATION: It is important to ensure the sub floor on which the planks are being laid is smooth, flat & hard & free from moisture, greases, etc. In case of uneven sub floor the same should be leveled by self leveling compound. The tongue & groove joints shall be glued together using recommended adhesive. The installation shall be undertaken as per the manufacturer's installation instructions. (Basic price Rs 1300 per sqmt excluding tax, transportation,wastage, loading / unloading, etc.,)	11.40	Sq.M.		
14.0	PLASTIC EMULSION PAINTING Cleaning the surface of the wall & then applying one coat of altex putty followed by one coat of primer & then applying second coat of putty to give smooth finish exactly in line and level & then finally applying a minimum of two coats of NO VOC or LOW VOC Plastic Emulsion Paint of approved shade to give a neat finish including cost of all materials necessary scaffolding etc., complete for walls & ceiling.	1067.50	Sq.M.		
15.0	TEXTURE PAINTING Cleaning the surface of the wall & applying TEXTURE PAINT of Asian Paints - Royale Play (Special Effects) or Berger - Silk Illusions in approved design and shade - with Base coat and Top coat including all primer, putty, necessary materials, labour, tools and plants, etc complete as per manufacturers specifications.	24.00	Sqm		
16.0	FROSTED FILM STICKERS Providing and fixing in position self adhesive frosted film stickers on glass partitions as per drawings and heights mentioned, of Harmony / 3M or equivalent approved make. The rate is for finished item of work etc., complete as directed.	24.00	Sq.M.		
17.00	POP COVERING Providing and spreading POP layer of 3mm to 5mm over the existing vitrified flooring and removing the same after completion of the Interior work including cleaning the floor etc., complete as directed	250.00	Sq.M.		
18.0	DRESSING MIRROR Providing and fixing Dressing Mirror with 4mm mirror of approx size 760 x 1220mm pasted on 12mm EG-MDF sheet and fastened to wall surface with SS studs including polished /chamfered edges for mirror, PVC edge banding for EG-MDF and all accessories etc complete.	2.00	Nos / each		

<u>S.No.</u>	<u>Item Description</u>	<u>Qty.</u>	<u>Unit.</u>	<u>Rate.</u>	<u>Amount.</u>
19.0	ACP CLADDING Supplying and fixing aluminium composite cladding with skin material 0.5 mm thick aluminium sheet cover material natural polyethylene aluminium cladding panel fixed with extruded aluminium basis frame (50x25x1.5mm) angle cleats, weather sealants, rivets, GI brackets all as approved, using suitable bolts on structural steel work including necessary accessories complete in all respects including all labour charges, scaffolding, tools and plants etc., complete for finished item of work but excluding cost of structural steel fabrication, if any. ACP Cladding - 4 mm thick.	14.74	Sq.M.		
20.00	ACP PARTITIONS Supplying and fixing aluminium partition with skin material 0.5mm thk aluminium sheet cover material natural polyethylene aluminium cladding panel fixed on one side and 12mm asbestos sheet on another side with extruded aluminium basis frame (50x50x1.5mm) angle cleats, weather sealants, rivets, GI brackets all as approved, using suitable bolts on structural steel work including necessary accessories complete in all respects including all labour charges, scaffolding, tools and plants etc. complete.	11.00	Sqm		
21.0	LACQUERED GLASS WORK FOR LAUNGE Providing and fixing in position 12mm toughened lacquered glass (colour - same as per laminate for skirting) for glass partition. The work to include making necessary template for all the glasses and then cutting the glass to correct size, making all the necessary holes, cuts etc., and then toughening the same. The cost to include all hardware required viz., single corner patch, bracket etc., The approximate size of each glass will be 1525mm (h) x 830mm (w) subject to site conditions. The rate is for a finished item of work etc., complete as directed.	1.44	Sq.M.		
22.0	SHIFTING EXISTING COUNTERS / CABINS Dismantling and shifting existing counters, tables, partitions etc and temporarily re-erecting in alternate location on the same floor, or upper/lower floor as per site, including counters, partitions, glass, doors, wicket gate, loose tables, storage units etc complete and made suitable for Bank's temporary working during the project execution period. for medium branch - with upto 7 banking counters + cabins, loose tables etc	1.00	LS		
23.0	CLEARANCE OF DEBRIS Clearance of Debris and all Waste materials generated during the execution of the work by Vendors of ALL TRADES, including loading, unloading, carting away, transportation and disposal to suitable location as per site conditions etc complete (Measurment shall be for Number of Loads of tempo / mini truck actually carried away and duly certified by Bank authorities / Security with GATE PASS.)	10.00	loads		
24.0	ROLLING SHUTTER PAINTING Providing and applying three coats of 1st quality enamel paint including scraping the surface clean.	27.00	Sqm		
25.00	SHUTTER BOXING WITH TRAP DOOR Providing & fixing ..shutter boxing in position made of 9mm ply with framing of Aluminium Tube sections of min 50mm x 25.4mm and 20 gauge 600mm C/C both ways.Laminate thickness of 1 mm ,minimum. Laminate Brand & Shades to be as per bank's approval. Trap door will be 19 mm marine ply finished with Laminate with required accesories & locking arrangement, complete as directed by Engineer.	8.40	Sqm		

<u>S.No.</u>	<u>Item Description</u>	<u>Qty.</u>	<u>Unit.</u>	<u>Rate.</u>	<u>Amount.</u>
26.0	6mm thk SOLID ACRYLIC SHEET (COREAN) ON PLYWOOD/MDF Surface Providing and fixing 6mm thk Solid Acrylic Surface sheets (COREAN) onto the existing BB / Exterior Grade MDF / plywood base with all necessary adhesives and including cutting, chamfering, chasing, buffing, polishing etc complete. The finished surface shall be seamless and in perfect line and level complete all as per manufacturers standard for the finished product. For more than 150mm wide sheet	15.09	Sq.M		
27.0	Dismantling existing kadappa tiles flooring, Dismantling existing ceramic tiles flooring/dadoing Item includes transportation of debris to Muncipal yard.	479.60	Sqm		
28.0	VITRIFIED TILES FLOORING (3mm spacers+ Epoxy grouting) : Providing and fixing 800mm x 800 mm type (approx.)VITRIFIED Tiles of approved make, shade and pattern as shown in the drwng. / as aproved by Architect. In CM 1:4 /tile on tile addeshive in proper line and level using 3mm PVC tiles spacers to maintain uniform joint gaps. Joint shall be cleaned, dried and filled with epoxy grout . Rate shall be inclusive of providing and laying necessary PCC and Cement Mortar/tile on tile adhesive for a thickness of 3" and including pop covering on the new flooring for the protection of tiles with base covering plastic.NOTE : Recessed floor for 3M floor mat (of size 4' x 2' x 12mm) should be made at the entrance. Basic Rate of Tiles 650/sqm excluding GST,Transportation etc.	375.77	Sqm		
29.0	Providing and laying VITRIFIED TILE skirting / risers of approved shade and make in CM 1:4 in proper line and level. The skirting should be flushed with the level of P. O. P. Punning on wall with 1/4" groove. Rate shall be inclusive of providing and laying necessary backing material and joint filling compound of the same shade of the tiles. 4" HIGH Basic Rate of Tiles 650/sqm excluding GST,Transportation etc. (item includes 3mm spacers filled with epoxy grouts.)	93.90	Rmt		