

**FINANCIAL BID OF INTERIOR WORK FOR STATE BANK OF INDIA,
DAULATPUR CHOWK BRANCH (50163), HIMACHAL.**

S.N.	DESCRIPTION OF ITEM	QTY.	UNIT	RATE	AMOUNT
1	WALL PANELING :-				
	Providing and fixing Paneling (ground floor & first floor) over the existing wall made out of framework of 50 mm X 25 mm - 18 gauge section un anodised Aluminium (as per requirement) frame work @ 16" to 24" c/c vertically & horizontally.The frame work to be clad with 8.0 mm thick BWP grade ply (MR Grade ISI Mark) and 1.0 mm thick laminate (make Aica, Greenlam, Century) as per pattern. The skirting shall be finished with 1mm thk brushed steel finsih lamiante. Also 3" X 1/2" teak wood section shall be provided on exposed surfaces. All ply / wood to be treated with wood preservatives of approved ISI quality. All exposed teak wood shall be melamine polish with matching pigment. The rate shall include for providing groves in laminate & wood. Payments shall be made only for exposed surfaces & actual measurement at site, no payment shall be made for paneling behind furniture such as tables, Credenza, storage etc. (including dismantling of existing Wall Paneling and disposing of malba at apporiate place)	1211	Sft.		
2	FULL HEIGHT PARTITION :-				
	Providing and fixing Low Height Partition made of 44 mm X 44 mm X 16 Gauge aluminium extruded sections @ 16" c/c vertically & horizontally. The bottom member shall be aluminium extruded sections of size 65 mm X 44 mm X 16 Gauge. The aluminium extruded sections frame shall be fixed rigidly at floor level with rawl plugs / steel lugs / screw. The frame work to be clad with 8.0 mm thick BWP grade ply (MR Grade ISI Mark) skirting along with 1mm thick laminate of approved make/colour /texture in desired shade, & horizontal/vertical grooves in desired pattern. Rates to include for provision of 35mm thick flush doors covered with 1.00mm thick laminate on both sides, 4nos brass butt hinges heavy on each door, all brass hardware, 6 levers (make Godrej, Hettich, Haffle) lock with decorative steel handles, door stoppers, hudraulic door closer etc. complete with melamine polish on 2nd class teakwood beeding /moulding in desired shade. The cost of doors with necessary hardware locks etc. complete is to be included and measured in this item. Skirting & intermediate bands will be of 1mm thick metallic shade laminate.All ply / wood to be treated with wood preservatives of approved ISI quality. (including dismantling of existing Full Height Partition and disposing of malba at apporiate place)	653	Sft.		
3	LOW HEIGHT PARTITION :-				
	Providing and fixing Low Height Partition made of 44 mm X 44 mm X 16 Gauge aluminium extruded sections @ 16" c/c vertically & horizontally. The bottom member shall be aluminium extruded sections of size 65 mm X 44 mm X 16 Gauge. The aluminium extruded sections frame shall be fixed rigidly at floor level with rawl plugs / steel lugs / screw. The frame work to be clad with 8.0 mm thick BWP grade ply (MR Grade ISI Mark) and 1.0 mm thick laminate (make Aica, Greenlam, Century) as per pattern with 12 mm thick toughened glass on top with 2nd class C.P. teak wood moulding on free end/top of low height partition complete with melamine polish.The skirting shall be finished with 1mm thk brushed steel finsih lamiante. Also 3" X 1/2" teak wood section shall be provided on exposed surfaces. All ply / wood to be treated with wood preservatives of approved ISI quality.(including dismantling of existing Low Height Partition and disposing of malba at apporiate place)	161	Sft.		
4	GYPSUM BOARD FALSE CEILING :-				
	Providing & fixing Gyp Board False Ceiling , in steps, with 12.5mm gyp bord (make Saint Gobbin, India Gypsum/ Gyproc) fixed on cold rolled galvanized steelsection frame as per detailed manufacturer's specifications. The grid consists of a perimeter channel (MF6a of dimensions 20mm x 27mm x 37mm x 3.5M) fixed round the perimeter to receive and of the ceiling section (MF5) and the outer edges to gypboard. The intermediate channel (MF7) of dimensions 15mm x 45mm x 0.9mm x 3.6M) at 1200mm c/c in the one direction and the ceiling section (MF5) of dimensions 80mm x 26mm x 0.5mm x 3.6M) at 450mm c/c in the other direction are connected by a connecting clip (MF9). The grid is suspended with an adjustable strap hanger (MF9). The grid is suspended with an adjustable strap hanger (MF8) of dimensions 25mm x 0.5mm) at 1200mm c/c on both ways from the structural soffit using a soffit cleat and expandable bolts/fasteners. Required cutting for fixtures will be provided. Perimeter Channels (MF7) to be used around the cut outs for light fittings. A/C ducting etc. Inspection doors for AC units will be of phenol bonded ISI marked 12 mm comm. Ply (make Aica, Greenlam, Century) with 1.0 mm laminate. . Ceiling will be finished with tape and jointing compound and primer & coat of plastic emulsion paint, complete in all respect. (including dismantling of existing ceiling and disposing of malba at apporiate place)	1962	Sft.		

5	ARMSTRONG FALSE CEILING :- Providing & fixing Armstrong false ceiling with 600x600x16 mm Fine Fissured Beveled Tegular Edge RH-99 Armstrong false ceiling laid in Armstrong Silhouette (Black) grid system . The frame work comprises of main runner spaced at 1200 mm centres securely fixed to structural soffit by approved hangers at 1200 mm maximum centres. Hangers (G.I. wires 4.0 mm dia) to be fixed by approved roof plug, level adjuster, screws etc. The last runner should not be more than 450 mm from the adjacent wall. Flush fitting 1200mm long cross tee(with double stitching) to be inter locked between main runners at 600mm centres to form 1200x600mm module. Cut cross tees longer than 600mm to be supported independently. 600x600mm module to be formed by fitting 600 mm long flush fitting cross tee centrally between 1200mm cross tees. Perimeter trim to be Armstrong wall angle secured to wall @ 450 mm maximum centres. The rates include making opening for electric fixtures, A.C units etc. (including dismantling of existing ceiling and disposing of malba at apporiate place)	960	Sft.		
6	FRONT LINE COUNTERS (S.W.O.) :- Providing and fixing at site SWO counters each upto 5'0" long, 2'6" high and 3'0" wide, as per design and drawing. SWO counters to be made of 19 mm thick bwp grade ply (MR Grade ISI Mark) with 1.0 mm thick laminate (make Aica, Greenlam, Century) on all outer visible surfaces, with 40 mm X 12 mm thick teak wood beading required all around, as per drawing. Provision for 3" dia. round / 3" square cable manager for computer / electrical cables at appropriate place will be made in the top surface of the counter. The top with Curvilinear profile shall be made out of 19mm thk. comm. ply and finished with 6mm thk. flexi ply as base for laminate sheet as/design with provision for Installation of Lights in bottom. Teak wood lipping will be provided on all the remaining edges of the counter, including bottom touching the floor and the drawers. The counter shall have a keyboard tray of size 600 X 270 with both side laminated board with back support, of EBCO make fixed on channels. Three drawers with autolock on top drawer, running on Telescopic channels of EBCO make, made of 19 mm thick BWP grade ply with 1 mm thick laminate on front face. The sides of the drawers shall be made of 12 mm thick plywood, bottom of 6 mm thick plywood. Non visible/Inside surface i.e. inside leg-space of table, inside drawers shall be finsihed with 1mm thk. white/off white laminate. All exposed Teak wood edges / teak wood lipping beading shall be Spray painted Satin Enamel paint or spirit (natural) polish as required. The drawers shall have partitions for keeping currency notes & the counter should also includes foot rest. A full depth CPU shelf 15" wide shall be provided at left hand side of counter underneath the working top, at 4" above the floor level and 3" away (horizontally), complete in all respects. The provision of swaping machine of green channel size 9"x 6" with lid shall be provided at right side of each counter while facing from front.	19	R.ft.		
7	TABLE (B.M. Cabin):- Branch Manager Table (6'-0"x3'-0"x2'-6") made of 19 mm thk. BWP grade ply (MR Grade ISI Mark) with 1.0 mm thick laminate (make Aica, Greenlam, Century) 12mm thick Corain on all sides for table Front& Top, on all outer visible surfaces 1.0 mm thick laminate, with 40 mm X 12 mm thick teak wood beading all around, as per drawing. The front of the table top shall be projected as per drawing. Provision for 3" dia. round / 3" square cable manager for computer / electrical cables at appropriate place will be made in the top surface of the table. Teak wood lipping will be provided on all the edges of the table, including bottom touching the floor and the drawers. The table shall have a keyboard tray of size 600 X 270 of (Ebco, Harison, Godrej) make fixed on channels. A full depth CPU shelf 15" wide shall be provided at left hand side of counter underneath the working top, which will be made of 19mm thick BWP grade ply finished with laminate 1mm thk. Three lockable drawer running on side mounting drawer slides (channels) of (Ebco, Harison, Godrej) make made of 19 mm thick BWP grade ply with 1mm thick laminate on front face, handle / knob shall be provided. The sides of the drawer shall be made of 12 mm thick plywood / 19 mm ply, bottom of 6 mm thick plywood. A full length foot rest made of hard wood 3" x 1½" section shall be provided at 4" above floor level. Non-Visible/inside surfaces i.e. inside / leg-space of table, inside of drawer / cupboard shall be finished in 1mm thk. laminate of white/off white shade and teak wood edges / lipping / beading shall be Spirit polished or Spray Painted as required.	1	No.		
8	OFFICER TABLE :- B.M. Table: 6'-0" x 3'-0" x 2'-6" as per drawing				

	Officer Manager Table made of 19 mm thk. BWP grade ply (MR Grade ISI Mark) with 1.0 mm thick laminate (make Aica, Greenlam, Century) with its eon all sides for table top, on all outer visible surfaces (except the bottom half of front modesty panel, which shall be finished with 1 mm thick laminate), with 40 mm X 12 mm thick teak wood beading all around, as per drawing. The front of the table top shall be projected as per drawing. Provision for 3" dia. round / 3" square cable manager for computer / electrical cables at appropriate place will be made in the top surface of the table. Teak wood lipping will be provided on all the edges of the table, including bottom touching the floor and the drawers. The table shall have a keyboard tray of size 600 X 270 of (Ebco, Harison, Godrej) make fixed on channels. A full depth CPU shelf 15" wide shall be provided at left hand side of counter underneath the working top, which will be made of 19mm thick BWP grade ply finished with laminate 1mm thk.				
(i)	Service Manager: 5'-0" x 2'-6" x 2'-6" as per drawing	1	No.		
(ii)	Field Officer Table: 4'-6" x 2'-6" x 2'-6" as per drawing	1	No.		
(iii)	Auditor Officer & Messenger Table: 3'-9" x 2'-3" x 2'-6" as per drawing	2	No.		
9	SIDE CREDENZA :-				
	Providing & fixing Side Credenza (1'-3" deep x 2'-6" high) made of 19 mm thick BWP grade ply (MR Grade ISI Mark) and 6 mm thick plywood on back side & 1mm thick laminate(make Aica, Greenlam, Century) of approved shade on top horizontal surface & vertical visible side only, with teak wood lipping on all edges including bottom touching floor. The credenza will have three drawers, horizontally running on side mounting drawer slides (channels) of EBCO make. The remaining part of the credenza will have cupboard with shutters and one shelf. The shutters with handle / knob and magnetic catcher shall be provided beneath the drawers all non visible/inside surfaces shall be finished with white/off white laminate 1mm thk. and teak wood edges / lipping / beading shall be Spirit polished with matching pigment.				
(i)	3'-0" x 1'-3" x 2'-3"	2	No.		
10	BACK CREDENZA :-				
	Providing & fixing Back Credenza (1'-6" deep x 2'-6" high), made of 19 mm thick BWP grade ply (MR Grade ISI Mark) and 6 mm thick BWP grade plywood on back side & 1mm thk laminate of approved shade on top horizontal surface & vertical visible side only, with teak wood lipping on all edges including bottom touching floor. The credenza will have drawer 4"high, horizontally running on side mounting drawer slides (channels) of (Ebco, Harison, Godrej) make. The remaining part of the credenza will have cupboard with shutters and one shelf. The shutters with handle / knob and magnetic catcher shall be provided beneath the drawers and non-visible/inside surfaces should be finished in 1mm thk. laminate of white/off white shade and teak wood edges / lipping / beading shall be Melamine polished with matching pigment	173	Sft.		
11	LOCKER ROOM DRESSING WALL:-				
(i)	Providing & fixing 5 mm thick looking Mirror with beveled edges paneling of approved quality & grade including making of ground of 12mm thick ply (MR Grade ISI Mark) as per design, with 4mm wide vertical or horizontal grooves as per the drawing provided by the Architect.	9	Sft.		
(ii)	Providing & fixing dressing cabinet in ply & laminate of size (4'-0" x 1'-6" x 1'-6") with drawers on both sides & square puffi (1'-6" x 1'-6") in center with leather on top complete in all respects as per the drawing provided by the Architects.	4.5	Sft.		
12	12 MM TOUGHEND GLASS DOOR :-				
	Providing & fixing frameless fully glazed 12.0 mm thk. toughend float glass (Saint gobain, Asahi, Modigaurd) doors, single leaf glazed Toughned door of size approximately, 1200 to 700mm X 2100 mm all sides edge grained, polished to be fixed on patch fittings, the door to be fitted horizontally / vertically as per instructions. The cost including cutting, making holes, cutouts in glass of required shape and size to accommodate fitting etc. the rate shall include necessary etching film / logo all inclusive, complete. NOTE: Rates include Top pivot, Top patch fitting(s), Bottom patch fitting(s), Corner / Central lock(s) with strike plate, Floor spring machine (Ozone, Dorma, Godrej), 2'-0" SS door handle, 304 grade (both sides) in door - pair, etc. all complete in all respect.	100	Sft.		
13	12 MM TOUGHEND GLASS PARTITIONS :-				

	Providing & fixing frameless fully glazed 12 mm thk. toughend float glass (Saint gobain, Asahi, Modigaurd) partition of size - as per site all sides edge grained, polished to be fixed with necessary patch fittings (Ozone, Dorma, Godrej) the glazing to be to be fitted horizontally / vertically as per instructions. The cost including cutting, making holes, cutouts in glass of required shap and size to accomodate fittings and fixing the fixtures, screws, sealant wherever required and SS cover over patch fittings, etc. the rate shall be include nesserydecorative film / logo all inclusive, complete. Glass partition will be fixed at bottom & top with patch fittings(as required) , SS U- channel of 12x25mm to be grouted with floor.	160	Sft.		
14	ALUMINIUM PARTITION FOR ELECTRICAL PANEL :-				
	Providing and fixing at site aluminium partition for the electrical panel as per the design and drawing. The carcass frame shall be made of 44 mm X 44 mm X 16 Gauge aluminium extruded sections , and clad with cemented board (Bision, Zykrone, Everest) 6 mm thick on one side. All stiles and rails for the openable shutters shall be made of 83 mm X 40 mm X 16 Gauge aluminium extruded sections and clad with cemented board 6 mm thick .The shutters shall be mounted on the hinges .The cabinet shall be complete with all necessary hardwares like locks, handles, catchers, tower bolts etc. The cemented board shall be finished with 2 coats of primer putty filling to desired smoothness and finished with two coats of plastic paint of desired shade and colour on all internal surface. All the outer visible surfce shall be finished with 1.0 mm thick laminate of approved color and shade using the recommended adhesive.	110	Sft.		
15	FIRE DOOR :-				
	Door to System room - Fire rated steel door (make Godrej, Aditya, Rawji) including frame - 2 (Two) Hrs Metal test certificate will be provided issued from GQMC. a). Frame - Providing and fixing fire resistant door frame of section 100 x 50 mm having built in rebate out made up of 1.2 mm GPSP Sheet duly powder coated / 16 SWG G.I. sheet (zinc coating not less than 120 gm / sqm) duly filled with vermiculite based concrete mix, suitable for mounting 120 minutes fire rated door shutters. The frame is fitted with intumescent fire seal strip of size 10 x 4 mm (minimum) all-round the frame and fixing with dash fastener of approved size and make, including apply a coat of approved brand fire resistant primer etc. complete as per direction of Engineer – in charge (including Dash fasteners). b). Shutter - Providing and fixing Metal Door Shutter 46 mm thk. made up of 0.8mm thick GPSP Sheet. Glazed fire resistant door shutters of 120 minutes fire rating conforming to IS : 3614 (Part – II), tested and certified as per laboratory approved by Engineer – in – charge, with suitable mounting on door frame, the entire shutter filled insulation material / Honeycomb craft paper of 160gsm (zinc coating not less than 120 gm/m2) and fixing with necessary stainless steel ball bearing hinges of approved make, provision of Fire Rated Wired Glass size of glass 300 X 200 including applying a coat of approved fire resistant primer etc. all complete as per direction of Engineer – in charge. The work includes providing and fixing following hardware for fixing to above door Hinges 4X3X3 (Min. 3Nos), Pull Handle 19 X 250mm -Pair, Dead Lock, (Godrej Night Latch Lock) Fasteners Hilti 10 X 92mm - (Min - 10Nos.)	42	Sft.		
16	FLUSH DOOR (WOODEN) :-				
	Providing and fixing wooden Choukhat (2" x4") & Flush Door(1.5" thick) made of Partal Wood inside & 1 mm laminate on both the surfaces , with necessary vertical or horizontle grooves 6mm thick, including steel handle, hinges, tower bolts & hudraulic door closer etc.complete in all respect,as/drgs provided by the Architect.including accessory	5	No.		
17	VOUCHER STAND :-				
	Providing and fixing Voucher Stand of size 4'-0" X 1'-6" X 3'-6" with 3 nos. storage units of forms with 12 mm glass top fixed with 3" SS spacer. Space for housing vouchers of size 1'6" W, 1'-0" D & 9" H is also provided on the top and on side (L-shaped, wall hung) including provision of Pass Book, Cheque Drop & Suggestion Box as per drawings made of 19 mm thick BWP grade ply (make Aica, Greenlam, Century) with 1.0 mm thick laminate to be fixed and ¾" x ¼" teak wood lipping on two visible sides on it All exposed Teak wood edges / teak wood lipping / beading shall be spirit polished with matching pigment. etc. & to be fixed on the wall.cost of spacers ect. all inclusive complete.	1	No.		
18	TEXTURE PAINT :-				
	Providing & applying a coat of RUSTIC textured finish in white color (Asian, Nerolac, Berger) on walls and columns. The rate shall include scrapping, leveling & preparing the surface with (Jk, Asain, Birla white) putty. Applying 1 coat of texture over a coat of primer & applying 2 or more coats of plastic emulsion paint of approved shade to give even & uniform surface, including cleaning of floor, surface etc. complete.	554	Sft.		
19	A.C.P. SHEET WALL PANELING / CLADDING :-				

	Providing and fixing 4.0mm thick pvdf coated exterior grade A.C.P.. sheet paneling over Anodised Aluminium frame work of size 1-1/2" x 1-1/2" @ 2'-0" c/c bothways. including openable shutter where required.the work shall include the cost of all necessary hardware e.g m.s hinges. magnetic catcher,aluminium tower bolts-6" long long etc.	524	Sft.		
	TOTAL INTERIOR WORK				
	Less Salvage Value For Old Items (As per site conditions)				
1	WOODEN PARTITION	890	Sft.		
2	ALUMINUM PARTITION	128	Sft.		
3	COUNTERS	46	R.ft.		
4	TABLES	15	Each		
	LESS TOTAL				
Note:	(Bank reserves the right not to dispose of above items as per salvage value)				
	TOTAL INTERIOR WORK				
	GST shall be paid extra as applicable				
	Seal & Signature of Vendor				

