

FINACIAL BID OF BOUNDARY WALL CIVIL WORK FOR STATE BANK OF INDIA, FOUNTAIN CHOWK, CIVIL LINES, LUDHIANA.

SN.	DESCRIPTION OF ITEM	QTY.	UNIT	RATE (Rs.)	AMOUNT (Rs.)
1	GRANITE :-				
	Providing and laying 18mm thick Lopatto / Flamed Finish Granite on main entrance steps with 1.5" moulding over 20 mm (average) thick base of cement mortar 1:4(1 cement :4 coarse sand) laid and jointed with cement slurry and pointing with white cement slurry admixed with pigment of matching shade including rubbing, curing, nosing and polishing etc. all complete as specified and directed by the Architect	1150	Sq.ft		
2	PLASTER & FINISHINGS :-				
	Repairs to plaster 1:4 (1 cement : 4 fine sand) of thickness 12 mm to 18 mm in patches of area 2.5 sq.meters including removing the old plaster wherever required and cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete as per direction of Engineer-in-Charge. With cement mortar 1:4 (1 cement : 4 fine sand)	8750	Sq.ft		
3	TEXTURE PAINT :-				
	Providing & applying a coat of PARLINA textured finish in white color (Asian, Nerolac, Berger) on walls and columns. The rate shall include scrapping, leveling & preparing the surface with (Jk, Asain, Birla white) putty. Applying 1 coat of texture over a coat of primer & applying 2 or more coats of plastic emulsion paint of approved shade to give even & uniform surface, including cleaning of floor, surface etc. complete.	8750	Sft.		
4	PLASTIC EMNULSION PAINT:-				
	Applying three or more coats of Plastic Emulsion Paint (Asian, Nerolac, Berger) of approved shade including making of ground, rubbing, filling of putty base preparation etc. In case where the surface has been white/color washed, the old white/color wash shall be entirely removed and surface broomed/scrapped down before the newPaint is applied. Rates include cleaning of splashes, stains on floor, window panes etc and scaffolding, if required and for all heights.	8750	Sq.ft		
5	ENAMEL PAINT:-				
	Applying 2 or more coats of enamel paint (Asian, Nerolac, Berger) on Cash Room Gate & Locker Room Main Gate to give even & uniform surface.	3170	Sq.ft		
6	CHEQUERRED PRECAST CEMENT TILE :-				
	Providing & fixing chequerred precast cement tile 22 mm thick in footpath & courtyard, jointed with neat cement slurry mixed with pigment to match the shade of tile, including rubbing and cleaning etc. complete, on 20mm thick bed of cement mortar 1:4 (1 cement:4 coarse sand)	1770	Sq.ft		
7	GALVANIZED STEEL SHEET (BLUE COLOUR)				

	Providing corrugated G.S. sheet roofing including vertical / curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead, including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (up to any pitch in horizontal/ vertical or curved surfaces), excluding the cost of purlins, rafters and trusses and including cost of scaffolding & cutting to size and shape wherever required.	1135	Sq.ft		
8	DISMANTLING :-				
	Dismantling of Slab/brick wall/ Stone wall/ concrete flooring & disposal of building rubbish, malba, similar unserviceable, dismantled or waste materials by mechanical means, including the loading/unloading/carrying of material from 3rd floor to ground floor, transporting, unloading to approved municipal dumping ground.	1	Lumsum		
	TOTAL				
	G.S.T as applicable will be paid extra by the bank				
	Seal & Signature Of Vendor				