

FINANCIAL BID OF CIVIL WORK FOR STATE BANK OF INDIA, HOLIDAY HOME (PART-2), AMRITSAR.

SN.	DESCRIPTION OF ITEM	QTY.	UNIT	RATE	AMOUNT
1	VITRIFIED TILES FLOORING:-				
	Providing and laying Anti Skid floor tiles 300mm x300mm (Marble series- Johnson, Kajaria, Nitco) with water absorption less than 0.08% and conforming to IS:15622, laid on 20 mm thick cement mortar 1:4 (1 cement: 4 coarse sand) jointing with grey cement slurry @3.3 kg/sqm. Including dismantling of existing floor tiles if any and disposing of malba from site at appropriate place. Cutting wooden/ aluminum doors to match new floor level. The tiles must be cut with the zero chipping diamond cutter only . Laying of tiles will be done with the notch trowel, plier, wedge, clips of required thickness, leveling system and rubber mallet for placing the tiles gently and easily.	5225	Sq.ft		
2	GRANITE :-				
	Providing and laying 18mm thick Lopatto / Flamed Finish Granite on main entrance steps with 1.5" moulding over 20 mm (average) thick base of cement mortar 1:4 (1 cement : 4 coarse sand) laid and jointed with cement slurry and pointing with white cement slurry admixed with pigment of matching shade including rubbing, curing and polishing etc. all complete as specified and directed by the Architect.	1185	Sq.ft		
3	S.S. RAILING :-				
	Providing and fixing stainless steel Grade 304 railing (Jindal, Hindalco, Bharat) made of Hollow tubes, channels, plates etc., including welding, grinding, buffing, polishing and making curvature (wherever required) and fitting the same with necessary stainless steel nuts and bolts complete, i/c fixing the railing with necessary accessories & stainless steel dash fasteners , stainless steel bolts etc., of required size, on the top of the floor or the side of waist slab with suitable arrangement as per the drawings provided by the Architect, (for payment purpose only weight of stainless steel members shall be considered excluding fixing accessories such as nuts, bolts, fasteners etc. (Including dismantling of Existing Railing and disposing of malba from site at appropriate place)	96	Rn.ft		
4	PLASTIC EMNULSION PAINT:-				
	Applying three or more coats of Plastic Emulsion Paint (Asian, Nerolac, Berger) of approved shade including making of ground, rubbing, filling of putty base preparation etc. In case where the surface has been white/color washed, the old white/color wash shall be entirely removed and surface broomed/scrapped down before the newPaint is applied. Rates include cleaning of splashes, stains on floor, window panes etc and scaffolding, if required and for all heights.	16190	Sq.ft		
5	COLLAPSIBLE/KANCHI GATE :-				
	Providing & fixing in position collapsible steel shutters with vertical channels 20x10x2 mm & braced with flat iron diagonals 20x5 mm size, with top & bottom rail of T-iron 40x40x6 mm, with 40mm dia steel pulleys, complete with bolts, nuts, locking arrangement, stoppers, handles, including applying a priming coat of approved steel primer:- (Including dismantling of Existing Collapsible Kanchi Gate and disposing of malba from site at appropriate place)	75	Sq.ft		
6	ENAMEL PAINT (WOODEN DOOR & WINDOW) :-				
	Applying 2 or more coats of enamel paint (Asian, Nerolac, Berger) on Wooden Door & Wooden windows to give even & uniform surface.	4160	Sq.ft		
7	ENAMEL PAINT (M.S. GRILL):-				
	Applying 2 or more coats of enamel paint (Asian, Nerolac, Berger) on Collapsible m.s. kanchi gate, m.s. Grill & m.s. Railing to give even & uniform surface.	2480	Sq.ft		
8	EXTERIOR WEATHER PROOF EMULSION PAINT:-				

	Applying three or more coats of Exterior Weather Proof Emulsion Paint (Asian, Nerolac, Dulux) of approved shade including making of ground, rubbing, filling of putty base preparation etc. In case where the surface has been white/color washed, the old white/color wash shall be entirely removed and surface broomed/scrapped down before the newPaint is applied. Rates include cleaning of splashes, stains on floor, window panes etc and scaffolding, if required and for all heights.	15650	Sq.ft		
9	REMOVAL & REINSTALLION A.C. OUTDOOR UNITS:-				
	Removal & installation of existing all A.C. outdoor unit on terrace including labour complete in all respect as and when required any no. of times.	1	Lumsum		
	TOTAL				
	LESS SALVAGE VALUE FOR OLD ITEMS (As per site conditions)				
1	COLLAPSIBLE/KANCHI GATE	75	Sq.ft		
2	M.S. RAILING	96	Rn.ft		
	LESS TOTAL				
Note:	(Bank reserves the right not to dispose of above items as per salvage value)				
	TOTAL				
	G.S.T as applicable will be paid extra by the bank				
	Seal & Signature Of Vendor				