

**BOQ FOR REPLACEMENT/REPAIRING WORK FOR EXTERNAL WATER PLUMBING WORK AT ORC BHANGAGARH**

<b>SN</b>	<b>Description of items</b>	<b>Unit</b>	<b>Qnty</b>	<b>Rate(Rs.)</b>	<b>Amount(Rs.)</b>
1	<p>Supplying fitting and fixing approved <b>uPVC Pipes</b> of different sizes, with all necessary 'R' brand or similar approved P.V.C. Fittings such as bend, tee, elbow, reducer, nipple, plug, long screw fitting, clamps etc. complete at all levels including below G.L. as directed and specified.<i>(for all the blocks)</i>.<b>The rate also includes cost for installation of brass valve with all the necessary fittings for each block seperately .</b></p> <p>(A) Exposed or in trenches</p> <p>SUPREME/ PRINCE/ SFMC BRAND or other equivalent approved brand (High presure pipe Sch-40)</p> <p>Exposed or in trenches</p>				
a	a) 80 mm dia	rm	170		
b	b) 65 mm dia	rm	120		
c	c) 40 mm dia	rm	459		
d	d) 25 mm dia	rm	50		
2	<p>Excavation of trench of size 450 mm x 450 mm (depth) by means of excavation and dismantling the exsting P.C.C work for crossing the UPVC water pipe line to different blocks by guarding the side with 10"brick wall finsihed with plastering work and filling of sand wherever required .The trench should be block with MS angle 80 mm x 80 mm to spacing @ 20mm to witstand the load of the water tankers and other commercial vehicle.The rate also includes finishing of the trench and its surrounding complete in all respect for smooth vehicular activities</p>	rm	30		
<b>Total Cost</b>					

**Rates are exclusive of GST**