

PRICE BID FOR INTERIOR & FURNITURE WORKS					
AT KHONSA BRANCH ARUNACHAL PRADESH					
SN	Description of items	Unit	Quantity	Rate (Rs.)	Amount (Rs.)
1	<p>Supply and installing new <b>SWO Counters</b> at the ground floor of overall size <b>1650 mm X 1800 mm X 750 mm</b>, including cost of <b>side credenza (1200 mm x 450 mm x 750 mm)</b> made up of 19 mm thick Block board of approved brand all around and finished with laminate of not less than 0.8 mm thick of approve colour, brand and shade. The cost to include three drawers of 375 mm wide made up of 6mm/12mm ply of approved brand on right hand side of the table on telescopic slider with partitions for keeping of notes of different denominations, a keyboard tray 250 mm wide, CPU stand, foot rest as designe and direction by bank. The credenza unit should have openable/sliding shutter cupboard and intermediate horizontal shelves made in 12 mm thick plywood. All exposed edges to have teak wood bidding/lipping stained to match the desk and melamine finished. All inner surface to be finished with mat finish enamel paint of approve brand. The works to include all hardwares such as: castors, brass hinges, ball catchers, fully extendable drawer slides, auto locks, handles etc. of Godrej or approved make. Locks to be of single control type. Design and detail of the counters shall be as per Bank's new uniform colour, layout &amp; elevation policy, <b>with curvature on front</b> with flexi ply. <b>Counter &amp; Credenza top to be provided with 8mm thick glass</b> duly finished on edges and necessary cut to accommodate wires, edges to be m/c polished, with ms powder coated wire manager, complete as directed by EIC and placement as per layout given. Rate shall include dismantling of existing items if any.</p> <p>Ply/Block Board Make: MR Grade of Century/ Green/Archidply/Gattani/Kitply or equivalent. Laminate Make: Greenlam/Centurylam/Archidlam/Merinolam or equivalent.</p>	Each	4		
2	<p>Providing &amp; fixing <b>counter Front 12 mm thick float glass</b> with polished edges, fixed with necessary S.S Brush finish brackets support on wooden partition as directed. Rate shall includes fixing of frost film as per design &amp; directed, cost of studs, making cut-outs for transaction and voice hole. Rate shall include dismantling of existing items if any.</p>	SQM	6		
3	<p>Providing &amp; Fixing <b>12 mm thick float glass</b> of size <b>320mm (width) x 1100mm (height)</b> &amp; tapering towards bottom as per the design and shape as shown in Bank's new uniform colour, layout &amp; elevation policy, fixed with silicon and T.W beading support on wooden partition as directed, on either sides of SWO as per design. Rate shall includes etching of glass as directed by bank. All edges of glass shall be duly beveled &amp; polished as directed complete. Rate shall include dismantling of existing items if any. Make: Saintgobin/ Modiguard or equivalent.</p>	SQM	2		
4	<p>Supply and installing of size - <b>2100 mm x 1800 mm x 750 mm</b> including cost of side credenza (1200mm x 600mm x 750 mm) for <b>Branch Manager</b> at <b>first floor</b> made up of 19mm thick Block board all around, finished with not less than 0.8 mm thick laminate of colour, shade &amp; brand as approved. The table cost to include (pedestal), three drawers of 450 mm wide made with 6mm/12mm ply on right hand side on telescopic slider and a keyboard tray 250mm wide, CPU stand, foot rest as per design and direction by bank. The credenza unit should have openable/sliding shutter cupboard and intermediate horizontal shelves made in 12 mm thick plywood. All exposed edges to have teak wood lipping/ bidding of required size stained to match the desk and melamine finished. All inner surface to be finished with mat finish enamel paint of approve brand. The works to include all hardwares such as: castors, brass hinges, ball catchers, fully extendable drawer slides, auto locks, handles etc. of Godrej or approved brand. Locks to be of single control type. Design and detail of the table shall be as per direction of EIC. All the surfaces to be in laminate finish &amp; 8 mm thick glass duly finished to be placed on top of table &amp; credenza and necessary cut-out to accommodate wires, edges to be m/c polished, with ms powder coated wire manager complete as per Bank's new uniform colour, layout &amp; elevation policy. Rate shall include dismantling of existing item if any.</p> <p>Ply/Block Board Make: MR Grade of Century/ Green/Archidply/Gattani/kitply or equivalent. Laminate Make: Greenlam/Centurylam/Merinolam/Archidlam or equivalent.</p>	Each	1		
5	<p>Supplying and installing <b>Staff Tables</b> at the first floor of overall size - <b>1500 mm X 1800 mm x 750 mm</b> including cost of <b>side credenza (1050 mm x 450 mm x 750 mm)</b> made up of 19 mm thick block board of approved brand all around and finished with not less than 0.8 mm thick laminate colour, brand and shade as approved by the Bank. The table cost to include (pedestal) three drawers of 375 mm wide made with 6mm/12mm ply on right hand side on telescopic slider, a keyboard tray 250mm wide with CPU stand and foot rest as per design and direction by Bank. The credenza unit should have openable/sliding shutter cupboard and intermediate horizontal shelves made in 12 mm thick plywood. All exposed edges to have teak wood lipping/bidding of required size, stained to match the desk and melamine finished. All inner surface to be finished with mat finish enamel paint of approve brand. The works to include all hardwares such as: castors, brass hinges, ball catchers, fully extendable drawer slides, auto locks, handles etc. of Godrej or approved make. Locks to be of single control type. Design and detail of the table shall be as per direction of EIC. All the surfaces to be in laminate finish &amp; <b>8 mm thick glass duly finished to be placed on top of table &amp; credenza</b> and necessary cut-out to accommodate wires, edges to be m/c polished, with ms powder coated wire manager complete as per Bank's new uniform colour, layout &amp; elevation policy. Rate shall include dismantling of existing items if any.</p> <p>Ply/Block Board Make: MR Grade of Century/ Green/Archidply/Gattani/kitply or equivalent. Laminate Make: Greenlam/Centurylam/Merinolam/Archidlam or equivalent.</p>	Each	7		
6	<p>Low ht storage unit: Providing and fixing storage units of size 450 mm x 750 mm, made up of 19 mm thick block board of approved brand on top &amp; vertical support and finished with not less than 0.8 mm thick laminate of approved brand on side and top. The storage units shall have openable/sliding shutters made up of 19mm thick plywood and finished in 1 mm thick laminate of approved shade. The storage units shall have intermediate horizontal and vertical shelves made in 12 mm thick plywood. All exposed edges to have teak wood lipping/bidding of required size, stained to match the desk and melamine finished. All inner surface to be finished with mat finish enamel paint of approve brand. The works to include all hardwares such as: castors, brass hinges, ball catchers, locks, handles etc. of Godrej or approved make. Rate shall include dismantling of existing storage if any. Ply/Block Board Make: MR Grade of Century/ Green/Archidply/Gattani/kitply or equivalent. Laminate Make: Greenlam/Centurylam/Merinolam/Archidlam or equivalent.</p>	RM	28		
7	<p>Fabricating and fixing <b>column/wall paneling</b> of BM Chamber with 12 mm thick ply finished with not less than 0.8 mm thick laminate of approved shade &amp; brand over framework at spacing not exceeding 600 mm both ways (horizontal and vertical.) Panelling framework to be secured to wall surface / column surface Design and detail shall be as per direction of EIC and Bank's new uniform colour, layout &amp; elevation policy. Ply/Block Board Make: MR Grade of Century/ Green/Archidply/Gattani/kitply or equivalent. Laminate Make: Greenlam/Centurylam/Merinolam/Archidlam or equivalent.</p>	SQM	77		

8	<p>Fabricating and fixing <b>full height solid partition</b>, made of 12 mm ply approved brand both side and to be finished with not less than 0.8 mm thick laminate of approved brand, colour and shade over 50 mm x 50 mm ( thickness not less than 1.5 mm) aluminium section framework of approved brand at spacing not exceeding 600 mm both ways (horizontal and vertical). Frame should be firmly fixed to the ceiling. All exposed edge shall be covered with teakwood bidding/lipping of required size with polishing complete in all respect. <b>Payment will be made for the area upto false ceiling only. Rate shall include dismantling of existing partition if any.</b></p> <p>Ply/Block Board Make: MR Grade of Century/ Green/Archidply/Gattani/kitply or equivalent. Laminate Make: Greenlam/Centurylam/Merinolam/Archidlam or equivalent.</p>	SQM	22		
9	<p>Fabricating and fixing <b>full height semi glazed partition</b>, made of 12 mm ply of approved brand in both side and to be finished with not less than 0.8 mm thick laminate of approved brand, colour and shade over 50 mm x 50 mm ( thickness not less than 1.5 mm) aluminium section framework at spacing not exceeding 600 mm both ways (horizontal and vertical). Frame should be firmly fixed to the ceiling. Middle portion at 900 mm to 2100 mm height shall have 6 mm thick plain float glass (Make: Saintgobin/Modigurd) fixed with 10 mm thick teak wood moulding duly polished. All exposed edge shall be covered with teakwood lipping/bidding with polishing complete in all respect. Payment will be made for the area upto false ceiling only. Rate shall includes etching of glass as required by bank. Rate shall include dismantling of existing partition if any.</p> <p>Ply/Block Board Make: MR Grade of Century/ Green/Archidply/Gattani/kitply or equivalent. Laminate Make: Greenlam/Centurylam/Merinolam/Archidlam or equivalent.</p>	SQM	18		
10	<p>Providing and fixing <b>Low Height Semi Glazed Partitions (LHSGP) (Total height 4.0 feet except for Cash Counter with 5 feet height)</b> made of 6 mm ply of approved brand in both side and to be finished with 1.00 mm thick laminate of approved brand, colour and shade over 50 mm x 50 mm (thickness not less than 1.5 mm) framework of approved brand at spacing not exceeding 600 mm both ways (horizontal and vertical). <b>Top portion from 2.5 feet to 4.0 feet height shall have 12 mm thick plain float glass (up to 5 feet for Cash counter) (Make: Saintgobin/Modigurd)</b> fixed with 10 mm thick teak wood moulding duly polished as per designe and direction by bank. All exposed edge shall be covered with teakwood lipping with polishing complete in all respect. Rate shall includes making provision for fixing of counter top 12 mm glass on its edges with necessary fixing arrangement as directed. Rate shall includes etching of glass as required by bank. Rate shall include dismantling of existing partition if any.</p> <p>Ply/Block Board Make: MR Grade of Century/ Green/Archidply/Gattani/kitply or equivalent. Laminate Make: Greenlam/Centurylam/Merinolam/Archidlam or equivalent.</p>	SQM	32		
11	<p>Providing and fixing <b>Solid doors shutter</b> made up of 38 mm thick block board of approved brand and quality, finished both side with not less than 0.8 mm thick laminate of approved brand, colour and shade. Door shall includes Godrej Mortise lock, two nos of 125 mm brass handle, 250 mm long tower bolt, brass door stoper, three nos 125 mm brass heavy hinge, hydraulic door closer of Godrej or approve make. All exposed edge shall be covered with teakwood lipping with polishing complete all respect. Rate shall includes etching of glass as required by bank.</p> <p>Ply/Block Board Make: MR Grade of Century/ Green/Archidply/Gattani/kitply or equivalent. Laminate Make: Greenlam/Centurylam/Merinolam/Archidlam or equivalent.</p>	SQM	4		
12	<p>Providing and fixing <b>Semi glazed doors shutter</b> made up of 38 mm thick block board of approved brand and quality, finished both side with not less than 0.8 mm thick laminate of approved brand, colour and shade. Middle portion at 900 mm to 2100 mm height shall have 6 mm thick plain float glass (Make Saintgobin/Modigurd) fixed with 10 mm thick teak wood bidding duly polished N C lacquer as per design and direction by bank. Door shall includes Godrej Mortise lock, two nos of 125 mm brass handle, 250 mm long tower bolt, brass door stoper, three nos 125 mm brass heavy hinge, hydraulic door closer of Godrej or approve make. All exposed edge shall be covered with teakwood lipping with polishing complete all respect. Rate shall includes etching of glass as required by bank.</p> <p>Ply/Block Board Make: MR Grade of Century/ Green/Archidply/Gattani/kitply or equivalent. Laminate Make: Greenlam/Centurylam/Merinolam/Archidlam or equivalent.</p>	SQM	8		
13	<p><b>MAIN GATE</b> : Providing and fixing <b>glazed door</b> made of 12 mm thick float glass with frosted film fixed in between top &amp; bottom rail and side stile of plywood framework of size 125 mm x 50 mm. The framework to be finished with not less than 0.8 mm thick laminate on both side. Glass to have acid etched design pattern with logo as directed. Doors to be mounted on heavy duty floor spring/door closer. Rate shall includes all hardwears such as: Two nos S.S. finish handle, lock, door stoper, hinge, tower bolt etc. of approved make.</p>	SQM	4		
14	<p>Providing &amp; fixing in position <b>Aluminium Composite Panel (ACP) / Shutter boxing</b> Panelling with framing in 600 mm C/C both ways. Minimum 3 mm thick ACP to be fixed over the freamework with 3M or equivalent adhesive and mirror screw in 600 width panels or distributed equally. Joints to be finished with Silicon based sealant. Aluminium foil thickness to be min 0.20 mm on both sides.</p> <p>Make: Alubond, Eurobond, Fujibond, Alcobond or equivalent ISO certified or approved brands to be used.</p>	SQM	13		
15	<p><b>False ceiling</b> : Providing and fixing suspended <b>false ceiling</b> with <b>600x600 mm size &amp; 12mm thick</b> mineral fiber ceiling tiles of <b>Armstrong dune</b> or approved make. Suspender, frame work as per manufacturer's specifications. The item to include cost of making necessary cut-outs for lights/air-conditioning grills as per design direction by bank.</p>	SQM	28		
16	<p><b>Gypsum board false ceiling</b> : Providing and fixing suspended 12mm thick <b>Gypsum board false ceiling</b> with GI framework of standard gauge and as per the specifications of <b>India Gypsum Co.</b> The rate to include painting with lustre paint and making necessary design,pattern &amp; cut outs for light fittings, cove light etc. complete as per design direction by bank.</p>	SQM	19		
17	<p>Providing &amp; fixing in place 100 mm. <b>Vertical blinds with scotch guard</b> of approved make, quality and colour shade &amp; pattern. Rate shall include necessary fittings, scotch guard treatment on both sides etc. complete. The overlaps should be uniform &amp; adequate.</p>	SQM	25		
18	<p>Supplying and Providing <b>Dining Table</b> of size <b>1800 mm x 1200 mm x 750 mm height</b>.Top shall be made of 18 mm thick plywood with additional 18 mm thick Ply wood patta of required width on edges with 1.0 mm thick laminate on top of approved shade and brand. Exposed edge to be finished with teak wood beading of required size. Supports of the Table shall be made of wooden members of required size in a Design as directed. All surfaces not laminated shall be lacquer polished.</p> <p>Ply/Block Board Make: MR Grade of Century/ Green/Archidply or equivalent. Laminate Make: Greenlam/Centurylam/Archidlam or equivalent. Wooden support: 1st class Local wood.</p> <p>Exposed edges of Table Top shall be made 36 mm thick by providing additional 18 mm thick ply wood patta of required width.</p>	Each	1		

19	<p><b>Full Height Storage Unit:</b> Providing and fixing storage units of size <b>450 mm (W) x 2100 mm (H)</b> as per the layout, made up of 19 mm thick block board of approved brand on top &amp; vertical support and finished with 1.00 mm thick laminate of approved brand on side and top. The storage units shall have openable/sliding shutters made up of 19 mm thick plywood and all inner surfaces shall be finished in 0.8 mm thick laminate of approved shade. The storage units shall have intermediate horizontal and vertical shelves made in 12 mm thick plywood. All exposed edges to have teak wood lipping/bidding of required size, stained to match the desk and melamine finished. The works to include all hardwares such as: castors, brass hinges, ball catchers, locks, handles etc. of Godrej or approved make. Rate shall include dismantling of existing storage if any.  Ply/Block Board Make: MR Grade of Century/ Green/Archidply/Gattani/kitply or equivalent.  Laminate Make: Greenlam/Centurylam/Merinolam/Archidlam or equivalent.</p>	SQM	6		
20	<p>Wall painting with <b>Plastic Emulsion Paint</b> on the walls inside &amp; outside at the ground floor the branch premise with two coats, having VOC (Volatile Organic Compound) content less than 50 grams/ litre, of approved brand and manufacture after application of one coat of <b>Primer</b>.The rate also includes application of <b>Wall Putty</b> wherever required to achieve even and smooth surface, shade and colour. (<b>Asian/ Berger</b>)</p>	SQM	451		
21	<p>Dsimantling and removing existing SWO counters and Accountant work stations present near entry area of the banking hall at the ground floor along with BM chamber partitions, table and low height cabinets as per the branch requirement so as to create a bigger space in the banking hall for the customers. The process involves manual and mechanical means including labour charges, dumping of the waste materials as per local by laws. The item also includes repair of tiles at the affected portion in terms of filling by putty/ white cement in the holes.</p>	JOB	1		
<b>Cost for the Branch Interior &amp; Furniture works (excluding GST)</b>					