

**BOQ FOR BARRICADING WORK - SBI LHO AMARAVATHI****Project: For Construction of buildings for Amaravati Local Head Office and other outfits at Amaravati**

PMC: Rdx Architects



S.No	Description	Area	Unit	Rate	Amount
1	<b>CLEARING JUNGLE SURFACE DRESSING:</b> Clearing jungle including uprooting of rank vegetation, grass, brushwood, trees and saplings of girth up to 30 cm measured at a height of 1.0 m above ground level, surface dressing of the ground including removing vegetation and inequalities not exceeding 15 cm deep, and disposal of rubbish with a lead up to 50 m and lift up to 1.5 m, complete in all respects as directed by the Engineer-in-Charge, in all kinds of soil.	12,141	Sqm		
2	<b>EXCAVATION WORK:</b> Excavation of pits (600 mm x 600 mm x 600 mm) size in Soil by mechanical means (Hydraulic excavator) /manual means over areas including getting out and disposal of excavated earth off the site as per approval from the local governing Authority, including necessary permission at site.	42	Cum		
3	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level : 1:3:6 (1 Cement : 3 Coarse Sand (Zone-III) derived from natural sources : 6 Graded Stone Aggregate 20 mm nominal size derived from natural sources)	32	Cum		
4	Centering and shuttering including strutting, propping etc. and removal of form for :				
	Foundations, footings, bases of columns, etc. for mass concrete	54	Sqm		

## BOQ FOR BARRICADING WORK - SBI LHO AMARAVATHI

**Project: For Construction of buildings for Amaravati Local Head Office and other outfits at Amaravati**

PMC: Rdx Architects



6	<p>Providing, fabricating, cutting, hoisting, and fixing structural steel members in position, including applying one coat of approved steel primer.</p> <ul style="list-style-type: none"> <li>Includes supply and installation of: <ul style="list-style-type: none"> <li>- Vertical members with MS base plates 250 × 250 × 5 mm</li> <li>- Horizontal steel tubes 50 × 50 × 4 mm for barricade members</li> <li>- 50 × 50 × 4 mm tubes for framing of gates</li> <li>- 40 × 40 × 5 mm angle bracing</li> <li>- ISMC 150 mm side posts for gates</li> <li>- ISMC 100 mm vertical members for barricades</li> </ul> </li> <li>Also applicable for gratings, frames, guard boxes, ladders, brackets, gates, and similar works, all complete as per drawings and specifications</li> </ul>	18988	KG		
	In gratings, frames guardbox, ladders, brackets, gates and similar works	1759	KG		
7	BLUE GALVALIUM SHEET: Providing and fixing 0.8 mm thk. pre-coated galvalume corrugated /plane sheet of approved make.	1,350	Sqm		
8	PROJECT INFORMATION BOARD Providing and fixing a 2.0 m × 1.0 m project information board with 16G MS sheet on 40×40×5 mm MS frame, supported on 75 mm NB MS posts in PCC blocks, primed (IS 2074), painted (IS 2932), with weatherproof polyurethane lettering/logos, bottom edge 600 mm above ground, as per approved design.	2	Nos		
	<b>TOTAL COST</b>				