

**PROPOSED BOQ FOR SUPPLY, INSTALLATION, TESTING AND COMMISSIONING OF 15 PASSENGER (1020 KG) HYDRAULIC LIFT (G+1) FLOOR & ITS ALLIED WORKS ALONGWITH 5 YEARS COMPREHENSIVE AMC IN STATE BANK OF INDIA, CPPC BRANCH, REVA PARISAR AT BHOPAL**

IT. No.	PART-'A' (PRICE BID) Description of Items ( For one first year all maintenance terms, conditions is applicable without AMC cost under defect liability period)	Qty	Unit	Rates	Amount
1	Supply, installation, testing and commissioning of 15 passenger(1020 KG) hydraulic lift (G+1) floor and its allied works (MS fabrication & civil works as per site requirement) as per mentioned specifications alongwith approval from Electrical Safety Department (MP. Govt, Bhopal). Before quooting the rate, contractor/vendor should visit the site to understand actual site condition & its requirement. Type of Elevators:- Hydraulic Lift Nos. of elevator/ Speed:-One / 0.3MPS Passenger/Load:-15/1020 Kg Stop & Opening:-2 stop & 2 openings G+1 Control/ Operation Simplex :- Microprocessor Based 2 Speed Control Platform Size :- 1800mm X 1500mm X 2100mm Clear Entrance :- 1000mm X 2000mm SS Glass Auto Door Car Enclosure :- SS Hairline Finish glass Cabin Landing door:- 1000mm X 2000mm SS Glass Auto Door Cabin inside width:- 1800 mm Cabin inside depth:- 1500 mm Cabin height:- 2200 mm Car panel finish:- SS-304, 1.2mm Decorative LED light, blower fan, mirror, handrail 16mm etc CeilingDecorative, Granite Flooring, For Emergency power failure:- UPS Other featuresSeven Segment Display ,voice annouciator, Call Register Indicator Hydraulic power pack:- Main/ Aux. supply system, 415 V, three phase, 50 Hz AC/230 v, single phase, Over head, As per Site Conduction req. service door, With hook No required 3500mm RCC Pit 300mm, MS frame 150 X 150 X 5 MM, all surrounding covered with 3mm external ACP wonder etc.	1	Nos		
	<b>AMOUNT OF LIFT- (PART 'A'):-</b>				
2	<b>FULLY COMPREHENSIVE ANNUAL MAINTENANCE CONTRACT (AMC) (PART- 'B') :-</b> Rates to be quoted by the Agency/contractor for fully comprehensive AMC inclusive of all hydraulic lift, power pack, lift car and allied MS fabrication and civil works associated with lifts with all electrical, mechanical, electronic and hydraulic components associated with lift for above works for next five years after the defect liability period of one year.				
2.1	For 1st Year amount fully comprehensive AMC of above hydraulic lift and its allied works complete in all respect	1	Nos		
2.2	For 2nd Year amount excuding civil works	1	Nos		
2.3	For 3rd Year amount excluding civil works	1	Nos		
2.4	For 4th Year amount excluding civil works	1	Nos		
2.5	For 5th Year amount excluding civil works	1	Nos		
	<b>AMOUNT OF AMC (2.1 + 2.2 + 2.3 + 2.4 + 2.5 ) (PART-'B')</b>				
	<b>GRAND TOTAL (PART-'A' + PART' B')</b>				
	<b>GST to be paid additionally</b>				