

PRICE BID OF FURNISHING WORK OF PADAMPUR BRANCH

No	Description	Unit	Qty	Rate	Amount
1	Dismantling the counters, wall and column panelling etc complete includig buy-back of the items and cleanung the premiesies	<i>job</i>	-1.00	5000	-5000
2	SWO Counter(5'x3'x2'6" and side unit of 3' to 3'6"x16"x30") : Made with 19mm MR grade BB table top, sides and 12mm thick ply on front modesty panel; with three equal depth drawer units (400x450 with depth as directed by engineer) with auto locking system, telescopic sliding channels, one PVC KBT, cable manager. Customer side shall be rounded with 6mm flexi ply (350 to 400mm depth) followed by 6mm ply duly supported on each side by a profile frame of 19mm BB and as directed by engineer. Round / curve shape shall be made after 3' width of table top. 12mm glass shall be provided at 2'6" distance thus leaving 6" for customer desk space. (Cost of glass shall be paid extra). All the exposed surfaces shall be finished with 1mm thick laminate bi-colour as directed by engineer. If PVC laminates are provided, the cost of this laminte shall be deducted from the bill)	no	3	20000	60000
3	P&F PVC flexible laminate in the SWO counter top with suitable adhesive for PVC laminates inlcuding pasting, pasting and finishing without any joints (5' x4' including rounding portion and 5'x2" to 3' on the bottom edge and mouldng to edge sides.	sqm	12	800	9600
4	BM table 6'x3'00"x2'6"along with side unit of 18"x42": Made with 19mm MR grade BB in table top, sides with one drawer unit (400x450x150mm) and one cup board with shutter. The side unit shall have one shutter with provision of storage units . All necessary hardware's, locks, handles, hinges, PVC KBT of approved make shall be provided including foot rest. Front modesty panel shall be 12mm MR grade ply. All exposed surfaces shall be finished with 1mm thick laminate. Inside surface of table and side units shall be polished.	no	1.00	21000	21000
5	Officers table 5'x2'6"x2'6"along with side unit of 18"x36": Made with 19mm MR grade BB in table top, sides with one drawer unit (400x450x150mm) and one cup board with shutter. The side unit shall have one shutter with provision of storage units . All necessary hardware's, locks, handles, hinges, PVC KBT of approved make shall be provided including foot rest. Front modesty panel shall be 12mm MR grade ply. All exposed surfaces shall be finished with 1mm thick laminate. Inside surface of table and side units shall be polished.	no	1	19000	19000
6	Staff Table 42"x24" x2'6": Made with 19mm MR grade block board in table top, sides with one drawer unit of 400x450x150mm with one drawer along with sliding channels and one cup board with shutter. All necessary hardware, locks, hinges handles, PVC KBT of approved make shall be provided including foot rest. Front modesty panel shall be 12mm MR grade ply. All exposed surfaces shall be finished with 1mm thick laminate. Inside surface of table units shall be polished. Edges shall be finished with 6mm teak wood lipping and polished for smoothness. Drawers shall be finished with lipping polished.	no	2.00	8000	16000

7	Full height and Low height Partition: (64mm thick) Providing and fixing solid and glazed partition made with GI Channel section 50mmx25mmx0.55mm thick spaced at 600mmx600mm grid and duly finished with 6 mm MR grade ply and 1mm thick laminate (colour & shade approved by engineer as solid/ teak wood / texture premium quality on each side. The frame shall be properly anchored at true ceiling, wall/ column sides and floor with long screws at 900mm centres. The glass panel shall be 5.5 to 6 mm thick duly supported by 6 mm MR ply and finished with laminate.	sqm	41	2800	114800
8	Column and Wall panelling: P&F 12mm MR grade BB on all sides of column with full threaded screws and pasting 1mm thick laminated with premium quality textured finish bi colour as approved by engineer. Make: MDF interior grade: century/Green/ Kit ply, Laminate: Century/ Marino/Green/ equiv as approved.	sqm	30.00	1900	57000
9	Column and Wall panelling: P&F 9mm MR grade BB on all sides of column and wall surfaces with backing ply frame of 19mm with full threaded screws and pasting 1mm thick laminated with premium quality textured finish bi colour as approved by engineer. 1200 mm height in FO, BM sies area, etc	sqm	30.00	1700	51000
10	Wall panelling with Ply board: Providing and fixing aluminium frame 25mmx40mmx0.80mm with a grid of 600mmx600mm duly anchored with wall screws to the walls and finished with 9mm MR grade Ply and 1mm thick laminate of approved colour and shade. Make: MR Ply: Kit ply/Century/Mayoor/Green and laminate: Kit ply/Century/Green/Marino	sqm	10.00	1900	19000
11	Storage units 450mm deep: Made with 19mm MR grade Block board on all five sides and 6mm backing ply. Vertical separators shall be provided at each 3' Centres with door leaf of each shutter of 18" wide supported by auto closing hinges. All inside surface shall be finished with 0.80mm thick laminate. Exposed surface including shutter edges shall be finished 1mm laminate of approved shade. Hardware like locks, handles shall be provided.	sqm	10	8000	80000
12	P&F 30mm thickness MR grade flush door finished with 6mm thick teak wood lipping on all edges duly polished, three SS Hinges for each door, one door stopper, one cylindrical lock per door finished with 1mm thickness laminates on both sides of approved shade and colour (solid and glazed with 5.5mm thickness float glass).	sqm	7.00	4208	29456
13	P&F 12.5mm thick Gypsum false ceiling of India Gypsum / Saint gobain make which includes G I perimeter channels , GI runners with perimeter of ceiling, screw fixed to brick work/ partition with the help of Nylon sleeves and screws at specified enters. Then suspending GI intermediate channels from the soffit at specified centres with ceiling angle fixed to soffit with GI cleat and steel expansion fasteners, ceiling section having knurled web etc complete. GI channels, runners etc shall be IS marked. Ceiling frame shall be rigidly fixed to the wall, RCC rigidly so that it will not fall down while fixing boards, providing lights, electrical cables, pipes etc.	sqm	85	750	63750

14	P&F modular grid pvc LAMINATED GYPSUM CEILING TILES of Indian Gypsum make/ saintgobai/equiv as approved and 600x600 x8mm as specified by manufacturer. Installation to comprise main runner at 1200 centres fixed to structural outfits and perimeter channe as per manufacturers specification and it hall be rigidly fixed to the wall, RCC rigidly so that it will not fall down while fixing boards, providing lights, electrical cables, pipes etc. Provision shall be made for light fitting, fire equipment, CCTV equipment. Extra support shall be given if necessary as per site requirement.	sqm	60	950	57000
15	Dismantling the brick work of any thickness and disposal of rubbish	cum	1.43	2000	2860
16	P&L brick work with locally available good quality bricks in cement mortar 1:4 (1 cement: 4 coarse sand) upto 12m level including curing, etc complete	cum	1.00	6192	6192
17	P&L half brick work in cement mortar 1:4 (C:CS) with locally available good quality bricks.	sqm	25	950	23750
18	Finishing the wall with cement plaster with cement mortar 12mm to 15mm thk complete.	sqm	60	273	16380
19	Dismantling tiles in walls and floors exposing brick works	sqm	40	150	6000
20	P&L wall and floor tiles 300x300 and 300x450 (Wall tiles or any suitable size) with backing mortar 15mm and gouting the joints with white cement in line and levels etc complete.	sqm	65	1000	65000
21	Finishing the walls and ceilings with primer in two or more coats including scrappng he surface etc complete of Asian/ Berger	sqm	400	26	10400
22	Putty to wall and ceilings including gypsum ceilings with a minimum of 1m thickness in a line and level and scrapping the surface to make it good adhesion for paints.	sqm	400	80	32000
23	Finishing the wall surface with tractor emulsion paint of Asian/ equiv as approved by engineer in charge with roller finish in two or more coats	sqm	400	60	24000
24	Enamel paint with primer in two or more coats	sqm	20	120	2400
25	P&F 12mm thick pre edge polished bevelled plain glass in table top of counters, tables, side units	sqm	5	2000	10000
26	P&F 12mm thick pre-polished Toughned glass to swo counters and ATM	sqm	5	4000	20000
27	P&F 12mm toughened glass in fixed position with patch fittings, duly supported at top, bottom and sides as directed by engineer with edge polish. Cost of extra member for fixing glass (Aluminium sections, ply, door frames shall be paid extra.	sqm	4	4500	18000
28	P&F 12mm toughened glass in Main entrance door with patch fittings , SS handles of 200mm duly supported by pivot at top and bottom with floor springs and top chord aluminium powder coated section as directed by engineer with edge polish. Cost of floor spring and alu section shall be paid extra.	sqm	2.1	7000	14700
29	P&F frosted film of Garware make of approved design pattern, shade and colour to glass panels including cleaning glass panels etc complete.	sqm	15.00	600	9000
30	P&F floor springs to glass door including cutting the floors (granite/ tiles/ concrete floors) and embedding the floor springs and grouting the area by approved tile adhesive matching with existing floors complete.	no	1.00	5500	5500

31	P&F door closer two speed of Godrej/Dorma/Ebco/Dorset as approved with all accessories to the doors.	no	2	1500	3000
32	P&F mortise lock with handles, with all fixed accessories (SS colour) to the doors.	no	1	2000	2000
33	Supplying and Fixing Godrej Night Latch for SWO Doors outside opening 7 lever brown colour	no	2	1400	2800
34	Plumbing items that includes fixtures, pipes, labour component 30% and profit 15%. Contractor should submit the bill of the materials purchased	ps	1	100000	100000
35	P&F aluminium section door with 6mm cement board as shutter including aluminium frame work, handles, etc complete for UPS room	sqm	2.10	4000	8400.00
36	Full height and Low height Partition: (64mm thick) Providing and fixing solid and glazed partition made with GI Channel section 50mmx25mmx0.55mm thick spaced at 600mmx600mm grid and duly finished with 8 mm evereat non combustible fire resistant fiber cement board on each side. The frame shall be properly anchored at true ceiling, wall/ column sides and floor with long screws at 900mm centres.	sqm	39	3600	140400
37	Foot rest made of 19mm ply as per engineers instruction	no	7	800	5600
38	CPU Trolley of made with 19mm block board duly laminated of size matching with CPU including clearance on each side.	no	7	900	6300
39	P&F wall/ column mounted writing desk having size of 4'x1'6"x8"depth with slots spaced @8" centers made of MR grade 19mm Block board on all sides and 6mm backing ply with slots of 8"x8"spaced @ 8"centers.All surfaces shall be laminated with 1mm thick laminates with edges teak wood lipping duly polished.	rm	1.00	2000	2000
40	Preparation of in-built layout drawing & mentioning the dimension of partitions, counters, panelling and marking locational reference in the measurement sheet and submission of drawing in PDF format along with the bill.	no	1	5000	5000
41	P&F pin up notice board made of 12mm backing ply duly laminated on one side and other sided sandwiched with 12mm soft board. The soft board is covered by a light blue fabric (Rs 250 per rm) and the stripped with teak wood lipping all-around include edges with hooks for hanging.	sqm	1.20	3200	3840
42	Complain box of standard size with shutters made with 19mm ply and laminates, locks etc complete	no	2	1200	2400
43	P&F Zebra blinds of approved brand and colour in all windows and BM chambers of standard make with all accessories	sqm	8	2200	17600
44	18mm Granite partition wall for urinal including polishing all edges etc complete	sqm	3	3200	9600
45	Sal wood frame work panelled with 6mm ply and duly laminated with blue colour	sqm	8	1200	9600
46	P&F 2nd class Sal wood frame 100mm x 75mm fixed to the walls or side partition as per site conditions with hold fasts including polishing the surface, rebating etc complete.	meter	18	900	16200
47	P&F WPC frame work of 75mmx50mm for toilet door frames 75mm fixed to the walls or side partition as per site conditions with hold fasts including polishing the surface, rebating etc complete.	meter	26	1000	26000
48	Chipping the existing concrete flooring to receive the tiling area	sqm	160	30	4800

49	P&L premium quality joint free double charged 600x600mm vitrified tile as per sample approved by engineer in charge laid in cement mortar 15mm to 20mm base (1;5) and as per site conditions in proper line, level and pattern as directed by engineer including surface preparation, cleaning the joints etc complete. The surface shall be cured sufficiently. Work shall be executed at any level and height. Rate includes providing and laying PCC 1:2:4 wherever required to make the surface in line and level. (Make: Somany/ Kajaria/ Johnson/ Nitco/ as per sample approved) Basic price : Rs 700 per sqm and above. Tile adhesive : Sika/ Fosroc/ Roff/Balendura as approved by engineer). No cement shall be used. Floor shall be chipped or hacking to make the proper bonding	sqm	160	1100	176000
50	P&L plain cement concrete 1:2:4 (1 cement: 2Coarse sand; 4 graded stone aggregate 20mm and down) including centring, shuttering in walls, foundations, copings, bed blocks, window sills, floors, etc as directed by engineer upto plinth and 12m level	cum	0.65	4860	3159
51	P&L in position reinforced cement concrete of mix 1:1.5:3 (1 cement: 1.5 coarse sand: 3 graded stone aggregate 20mm and down) including centring and shuttering, finishing but excluding cost of reinforcement for lintels, kitchen slabs, chajjas etc complete upto 12m level	cum	0.5	8394	4197
52	P&L steel reinforcement for RCC work including straightening, cutting, bending, placing in position and binding all complete upto 12m level	Kg	50	77	3850
53	Providing and fixing 30mm thick WOOD PLASTIC COMPOSITE (WPC) door including two ball bearing hinges, teak wood lipping with all accessories etc complete as directed by Engineer. Make: Black cobra/ Kit ply/ SNG as approved. Toilets and utility area.	sqm	4	4647	18588
54	Shifting of Gold and cash safe heavy weight including dismantling RCC embedding work and placing in the desired location	no	2	5000	10000
55	Supplying manpower for shifting of old records, files, almirahs, storage cabinets etc to a desired position as per instruction of engineer in charge	each	20	700	14000
56	Embedding of safe with RCC work in CC 1:1.5:3 with 6" spacing inbetween two safes	cum	5	9000	45000
57	Dismantling existing collapsible shutter of safe room and stacking at site	no	1	2500	2500
58	P&F 1mm thick MS sheet sliding shutter with frame and diagonal braces 40x40x6mm angle iron, 3mm MS gusset plate T iron angle hinges, handles as instructed by engineer including two or more coats of primer as directed by engineer.	sqm	2.80	4000	11200
59	S&F in position collapsible steel shutters with vertical channels 20x10x2 mm and braced with flat iron diagonals 20x5 mm size, with top and bottom rail of T-iron 40x40x6 mm, with 40 mm dia steel pulleys, complete with bolts, nuts, locking arrangement, stoppers, handles, including applying a priming coat of approved steel primer.	sqm	4.00	4200	16800
60	Dismantling electrical connection to counters, tables and making temporary arrangement for counters without affecting regular running of counters and customers. Work shall be executed through licensed electrician contractor empanelled by Bank	ps	1.00	7000	7000

61 Anti termite treatment to walls and floors through 12mm dia holes using pressure njecting with chemicas of approved quality diluted in water as per manufacturers specification for termite treatet. Holes shall be spaced @ 300 mm centers and to be filied with cement mortar. Contractor should submit a completion certificate from BM. Warranty 3 yrs

sqm

350.00

120

42000

Total cost excluding GST

1578622

Quote %age of total cost

%

0%

0

Total cost excluding GST

1578622

	Material Recommended	Brand Recommended
1	Block Board, Ply, MDF, Flush door	Greenply (Ecotech), Globe Ply, Century (Sainik), Kitply (Vista) MR grade.
2	Autolatch	Ebco, Godrej/Ozone
3	Gypsum ceiling	India Gypsum, Saint-Gobain, Gypstar
4	Grid ceiling	Armstrong, Saingobain /India gypsum
5	Hardware fittings	Ebco, Godrej, Hettich, Hafle
6	Plumbing materials	Hindware, Parryware, Cera, Jaquar
7	Tiles	Johnson, Nitco, Kajaria, Somany,
8	Miscellaneous materials	Engineer's Discretion

If required brands are not available, contractor may use other equiv brand available for use at site.