



STATE BANK OF INDIA
LHO, MAHARASHTRA

SHIFTING OF SBI NACHANGAON BRANCH
BOQ

				ES1
Sl. No.	Item Description	Qty	Unit	Rate
1	Supply and erection of 25mm dia PVC drain water piping (4kg/sq.cm.) upto just above ground level for all ACs including Split ACs and its insulation using 4 mm thick nitrile rubber sleeve insulation.	40	m	
2	Supply and Installation of 1.5 Tonne Capacity Hi Wall mounting 5 Star rated Inverter Split AC with cordless remote and Copper Condensor Coil. (with copper piping & cabling upto 3metre) (High Wall Split AC). Insulation using nitrile rubber insulation with Teflon taping. (1-BM & 2-ATM)	5	No.	
3	Supply and laying of additional copper refrigerant piping (double circuit) for Split Airconditioners (additional length beyond 3 Metre)	30	Mtr.	
4	Control Cabling between Indoor & Outdoor Units for Non VRF Split Acs	40	Mtr.	
5	Supply and installation of powder coated ready made metallic stand for mounting ODU of Split Airconditioners.	5	Nos.	
6	Supply and Installation of 4 kVA V-Guard Stabiliser with metallic enclosure.	5	Nos.	
7	Supply and installation of 1 to 12 hour user selectable Electronic timer for the alternate operation of ATM Airconditioners.	1	No.	
8	AMC for 5 Years	37.5	tr	
	TOTAL AMOUNT FOR THE AC WORKS			

IMATE
Amount