No.	Discription	Qty.	Units	Rate	Amoun
ı	Supply of High Wall & Cassette				
	Supply of Split Air Conditionara				
Α	Supply of Split Air-Conditioners				
1.0	Supplying & providing of Hi-wall Inverter Split Type AC with high wall mounted indoor and out door unit. having eco friendly refrigerant. Including indoor unit outdoor unit. and cordless remote Machine shall				
	have copper condensor Unit , Make: Daikin/ hitachi /				
	carrier / blue star / voltas Mitsubishi Heavy Industries				
	/Toshiba [Mini 5 Star rating as per BEE Guide Line 2022]				
	Indoor (fan coil) unit shall be Wall Mounted type comprising of Fan, Two way air discharge and 2 Row Deep DX coil with finned copper tubes, T-Flow Fan unit with direct drive Motor; Unit shall have proper insulated & leak proof condensate base connected.				
	The outdoor (condensing unit) shall be of Corrosion resistant Galvanized powder coated or equivalent Sheet steel low vibration assembly installed on suitable vibration isolators and comprising of energy efficient Rotary / Reciprocating				
	compressor with copper condenser coils only				
	The units shall be installed on MS angle iron frame welded structure ( <u>Sepatate item</u> ) with duly with anti-corrosive paint (Expoxy) - Vibration Isolated pad with 2 side GI sheet.  The above specified units shall be supplied as per following schedule installed at				
	locations as mentioned in the layout  The unit will comparising of suitable electrcial panal with capactior connector				
	strip clamps etc.				
	All machines shall be white in color				
1.2	Supply of 1.5 TR H.W. Hi-wall Inverter Split (5* BEE Guide Line 2022)	3.00	Nos.		
1.3	Supply of 1.0 TR H.W. Hi-wall Inverter Split (5* BEE Guide Line 2022)	2.00	Nos.		
	Total of Part "I" / "A"			Rs.	
Α	Supply of Cassette Air-Conditioners				
1 N	Supply of Ceiling Mounted 4-way Cassette type				
1.0	Supply & providing of 4 way Inverter Cassette Type AC ceilling mounted cassette unit with indoor and out door having eco friendly refrigerant. Including indoor unit outdoor unit. decorative grille and cordless remote Machine shall have copper condensor Unit , Make:				
	Daikin/ Mitsubishi Heavy Industries/Toshiba [Mini 5 Star rating as per BEE Guide Line 2022]				
1.1	3.00 Tr. For Main Hall	2.00	Nos.		
	Sico III G. Main Hair	2.00	1103.		
	Total of Part "A"			Rs.	

No.	Discription	Qty.	Units	Rate	Amount
l	Total of Supply of A.C. units I.E. "I": "A"+"B"			Rs.	
II	Low Side Work for High Wall / Cassatte AC Units				
1.0	Standard Installation of all type of machines including indoor & outdoor machine erection, first Oil & Gas charging, installation & commissioning Including top and plug, vacucumissing, nitrogen pressure testing (as applicable).				
	The rate shall include 4.0 mtr. of refregerent pipe with nitrile insulation & electrical cabelling for each machine.				
1.1	High wall spilt units of various capacities				
1.1.1	1.5 TR. / 1.0 TR	5.00	Nos.		
1.2	Cassatte units of various capacities				
1.2.1	3.0 tr	2.00	Nos.		
2.0	P & F of UPVC drain lines				
2.0	7.7.2.2.2.2.4.3.1.2.2.2.2.2.2.2.2.2.2.2.2.2.2.2.2.2.2				
	P & F of insulated UPVC drain lines (SCH 40) having density of 6 kg./cm2 (Beyond 4.0				
	R.Mtr. for each split ac Machine) with 6 mm Nitrile rubber for various units in clamping				
	manner above false ceiling & in concealed manner below false ceiling level. From the				
	structural ceiling it should hanged using self threaded rods or shall be fixed on wall /				
	beam etc. with clamps & the distance between 2 clamps shall be less than 1 meter. It				
	shall not be placed over the false ceiling nor it shall be fixed with				
	alse ceiling members.It shall be laid required gradient for easy disposal of the drain				
	water & testing shall be done before filling the zaries. The drain line shall not be laid in				
	the floor (except toilets & other utility areas where there are no electrical lines in the				
	floor). All drain pipes of split / Cassatte / HAT air-conditioners should be UPVC of 25				
	mm / 32 mm in size and it should be connected to the nearest rain water pipeline / NT				
• •	as per the site condition				
2.1	25 mm size as per machine requirement	5.00	R.Mtr.		
2.2	32 mm size as per machine requirement	25.00	R.Mtr.		
3.0	P & L Refrigerant copper piping				
	P & L Refrigerant copper piping with <b>0.80 mm</b> wall thickness, laid between indoor &				
	outdoor unit as per OEM's specifications (Beyond 4.0 R.Mtr. for each Machine) duly				
	insulated with Class "O" fire retardant 6 mm sleeve type elastomeric nitrite rubber				
	insulation. The item also includes copper electrical flexible cable of appropriate				
	Alu. foil membrane shall be applied to provide resistance against breakdown due to UV				
	radiation for exposed portion of the rubber insulation with Nitrogen testing (totally sealed				
	- in case of proposed machine). It shall be in total clamping manner above false ceiling				
	& in total concealed manner below false ceiling level. From the structural ceiling it should				
	hange or shall be fixed on wall / beam etc. with clamps & the distance between two				
	clamp shall be less than 1 meter.				
	It shall not be placed over the false ceiling nor it shall be fixed with false ceiling				
	members. The diameter / guage of the ref. pipe shall be as per the specifications				
	of the Manufacturing company (OEM) only for each type of machine.				

No.	Discription	Qty.	Units	Rate	Amount
	for 1.0 tr. & 1.5 tr. High wall split with with control cabelling of 3 Core Copper flexible Electrical cable as recommended by manufacturing company.	28.00	R.Mtr.		
3.3	for3.0 tr. Cassatte unit with control cabelling of 4 Core 4 Sq mm Copper flexible Electrical cable as recommended by manufacturing company.	30.00	R.Mtr.		
4.0	P & F of M.S. platform for Split & Cassatte Condensing units.				
4.1	P & F of M.S. platform for Condensing units. It shall be of cage type with required space for servicing purpose & shall have safety railing, fixed to the out side wall. It shall be made out of M.S channels, angles, flats etc. of appropriate size & thicknesses duly painted with anti corrosive paint. The rate also includes for ladder and scaffolding, installation, retouching the surfaces with rich plain cement concrete etc. comp. The entire item has to be executed as/req. of the machine & site condition in total cooridantion. The item also includes providing 10 lever Pad locks for each cage. If the cages are prepared in combined manner than appropriate deduction shall be made. for Split AC units	5.00	Nos.		
	for Cassatte AC units				
		2.00	Nos.		
6.0	Civil work related all Airconditioning work  All sort of Civil work required to be executed in order to make the Airconditioning system installed & put in working condition. The item includes, making holes / gaps in walls to pass duct & pipes, making zaries required for various types of drain, refregerent & drain water pipes / lines in walls, floor etc. using cutter machine, including core cutting if required, refinishing on all the side with rich cement mortar to match the surrounding original finised surfaces to put the entire work in order. While crossing the wall, a heavy duty PVC pipe sleve shall be fixed of the total wall thickness & shall be finished from out with rich cement mortar & from inside with white cement. No extra will be paid for any civil work related to Airconditioning work.	1.00	Job		
II	Total of Part "II" - I.E. Low Side work			Rs.	
	Summary of Project				
l	Supply of Various AC Machines			Rs.	
II	Low Side work for various AC machines			Rs.	
	Total of Part "I" + "II"			Rs.	