PROPOSED INTERIOR FURNISHING WORK (LOOSE & FIXED FURNITURE) AT ALTERNATE PREMISES OF STATE BANK OF INDIA FOR DHIMA <u>BRANCH & ATM</u>

SN	Description	Quantity	Unit	Rate	Amount
	Note: Rate should be inclusive of material, labour, tools, machinery, scaffolding, etc. All taxes, transportation etc. complete. (Excluding GST) GST will be paid as A	•			
Ι	FURNISHING WORK				
	FINISHING DETAILS IN NUTSHELL:				
	1) Table Top: 6 mm thick white corian				
	2) Front Appron: Round Corian and 6 mm thick blue lacquered glass fixed with Natural Silicon				
	3) Facing of Drawers: 1.00 mm thick laminate finish				
	The W.S. should have Ready Made Foot Rest. High impact polysterene with crome plated metal structure of approved make.				
	There should be provision for cable manager(Metal Cable Manager) system with necessary cutouts in top surface				
	C.P.U. trolly with castors/roller supports/ Nylon castors.				
	Key board tray with mouse pad made from CRCA steel duly powder coated. It must				
	have built-in slides which, must have a soft palm rest and a stow-away design of				
	mousepad mounted underneath it. All the internal surface (non visible surface) shall be provided with 0.60 mm thick				
	balancing laminate of approved shade etc. complete				
	Heavy duty <u>telescopic full extension</u> sliding channel of approved make shall be used in				
	all drawers. SINGLE WINDOW COUNTER / CASH COUNTER SIZE 5'-0" X 2'-9" with White				
1	corian & blue lacquered glass finishing	3.10	RMT		
1.1	Supplying, fixing and keeping in position single window counter complete as per design and drawing made out of 18 mm thick commercial ply wood of approved make, complete with 19 mm. C.P. Teak wood lipping on all edges wherever required.				
1.2	The cost shall be inclusive of S & F of a drawer unit or drawer & shelf unit with 18 mm thick commercial plywood and with approved make multipurpose Auto Lock in drawer and shelf unit. The cost shall also be inclusive of the following: Size Description: Nos. L B H Writing Top: 2 5'-0" 2'-9" 2'-6" 4 Nos Drawers with pigeon hole: 8 2'-0" 1'-3" 2'-0"				
1.3	Size Description: Nos. L B H Side Credenza: 2 3'-0" 1'-4" 2'-6" Side Credenza(Side Rack/Storage):For S.W Counter Same as above item 1.1 but Side Table Top and edges shall be finished with 6 mmThick White Corian on Top and Edges. All other visible surface shall be finished with 1.00 mm th laminate. Size shall be 3'-0"x 1'-4"x2'-6" ht. With openable shutter as directed				
1.4	Front Glass: Providing and fixing 12 mm thick Toughened float Glass in front portion. The counter will have additional 1 no. 12 mm th. Clear toughten glass of size: 5'-0"x 2' 6" with one number half round cutout for cash transaction and one number circlualr cutout (5" dia) for communication fixed with side partition with S.S. bracket (for two counters). The edges of glass shall have diamont cut polished edges etc. complete to the satisfaction of Architect/Bank's Engineer				
1.5	Working table top and edges shall be finished with 6 mm thick white corian of DUPONT or equivalent approved make as per drawing and direction with all labour and material.				
1.6	Front Appron: 2 nos 6 mm thick flexy ply wood in round shape with 6 mm thick white corian shall be provided at front as per design. All edges should be finished with corian of DUPONT make.				
1.7	Front pannel shall be finished with 6 mm thick 18" high blue lacqured glass of approved make and fixed on 18 mm thick commercial ply wood with Natural Silicon gum as per manufacturer's specification and to be completed as per drawing				
1.8	All wood work shall be laquer polished to a smooth and uniform finish of choice colour and shade.				
1.9	All fittings like S.S. handle, Auto Lock to each drawer and cabinet doors, piano / auto hinges, ball catcher, stopper, metal cable manager etc. should be fixed of approved make.				
1.1	Counter shall be made independent in Length of 5'-0" and properly placed between two partitions. Counter will be measured in RMtr between two partition and paid.				
II	TABLES				<u> </u>
	Note : for all work stations				
	FINISHING DETAILS IN NUTSHELL:				
	 Table Top: 1.0 mm thick Dark laminate & Burma Teak beading on Edges with polished. 				
	2) Front Appron & Sides: 1.0 mm thick Dark Laminate				
	3) Facing of Drawers: 1.00 mm thick laminate finish				
	The W.S. should have Ready Made Foot Rest. High impact polysterene with crome				
	plated metal structure of approved make.			I	

1

There should be provision for cable manager(Metal Cable Manager) system with necessary cutouts in top surface C.P.U. trolly with castors/roller supports/ Nylon castors. Key board tray with mouse pad made from CRCA steel duly powder coated. It must have built-in slides which, must have a soft palm rest and a stow-away design of mousepad mounted underneath it. All the internal surface (non visible surface) shall be provided with 0.60 mm thick balancing laminate of approved shade etc. complete			
necessary cutouts in top surface C.P.U. trolly with castors/roller supports/ Nylon castors. Key board tray with mouse pad made from CRCA steel duly powder coated. It must have built-in slides which, must have a soft palm rest and a stow-away design of mousepad mounted underneath it. All the internal surface (non visible surface) shall be provided with 0.60 mm thick			
C.P.U. trolly with castors/roller supports/ Nylon castors. Key board tray with mouse pad made from CRCA steel duly powder coated. It must have built-in slides which, must have a soft palm rest and a stow-away design of mousepad mounted underneath it. All the internal surface (non visible surface) shall be provided with 0.60 mm thick			
have built-in slides which, must have a soft palm rest and a stow-away design of mousepad mounted underneath it. All the internal surface (non visible surface) shall be provided with 0.60 mm thick			
mousepad mounted underneath it. All the internal surface (non visible surface) shall be provided with 0.60 mm thick			
All the internal surface (non visible surface) shall be provided with 0.60 mm thick			
paranong rammate of approved Shade etc. complete			
Heavy duty telescopic full extension sliding channel of approved make shall be used in			
all drawers.			
MANAGER TABLE SIZE: 6'-0" X 2'-9" X2'-6" HT. with Side Credenza & Laninate			
	.00	NO	
follows			
Supplying and installation of Table as per the following description : Size 6'-0" x 2'-9".			
Table top shall be made from 18 mm thick commercial ply wood with 1.0 mm thick Laminate with necessary intermediate support. Table top shall be supported by 18 mm			
thick commercial ply wood with wooden framing. Drawers of size of 1'-3" x 2'-0" x 2'-6"			
2.1 shall be provided using 18 mm thick commercial ply wood having 4 Nos drawers as			
directed with heavy duty telescope sliding channel of approved make , grouplock, S.S.			
Handle. Ready made metal Key board with mouse pad of approved make shall be			
provided. Exposed surfaces of darwers shall have laminate, All internal surface will have 0.60 mm thick balacing laminate			
Apron (Modesty Panel) made from 18 mm thick ply wood finished with laminate as			
per drawing			
Table side made from 18 mm thick ply wood with 1.0 mm thick Laminate finish shall			
2.3 be provided in a pattern as per drawing. Laminate to be provided on all visible surfaces.			
Drawer Fascia made out of 18 mm thick Plywood. The sides/back/base of drawers be			
made of 12 mm thick Ply wood & Bottom of drawers shall be of 6 mm thick ply wood.			
fixing laminate on front side and all the internal surfaces shall be 0.60 mm thick			
2.4 balancing laminate. The drawers to be fitted with Telescopic sliding channel with SS			
Group locks of approved make and 100 mm long brush finish Stainless Steel handles			
for each drawer. All the edges of Drawer Fascia be provided with teak wood edge bending with lagueer polished etc complete as directed.			
Table shall have stand for keeping CPU and metalic cable Manager shall be provided 2.5 in table top. All exposed edges of teak wood shall have polished with smooth edges &			
corners			
2.6 Exposed edges of Table Top, Leg panel & Side Shelf shall be made 36 mm thick by			
providing additional 18 mm thick ply wood patta of required width.			
2.7 All the internal surface (non visible surface) shall be provided with 0.60 mm thick			
balancing laminate of approved shade. etc. complete. All the surface without laminate / balancing laminate shall be lacquered polished of			
2.8 approved shade			
Side Credenza Size 4'-0" x1'-6" x 2'-6" ht. Openable shutter with 1.00 mm thick			
Laminate finish on Top , front, sides, shutter and 35 mmx 6 mm thick Burma Teak			
2.9 beading on Top Edges. Laminate to be provided only on visible surface etc complete as follows. Only Front elevation will be measured for payment purpose. (For BM &			
Officer's) Rate for length Less then 3'-3"			
2 10 Exposed edges of Sides, Table Top shall be made 36 mm thick by providing additional			
18 mm thick ply wood patta of required width.			
All the internal surface (non visible surface) shall be provided with 0.60 mm thick			
balancing laminate			
Same as details of above Item-no-2A but Size: 4'-3"x2'-6" without side credenza &			
3 with 4 Nos Drawer Unit with 1.0 mm thick Laminate finish on all exposed surfaces 2.	.00	NO	
4 GRAHAK MITRA TABLE OF 2'-6" WIDE with PU coating finish 1.	.50 F	RMT	
Same as details of above item no 2A but Size 2'-6" wide with storage unit in Table	.50 [XIVI I	
with 4mm thick MDF board + Blue and white PU Coating finishing on all exposed			
visible surface as per drawing and instruction of Architect/Bank For Grahak Mitra/Tech			
Mitra (Help Desk Table)			
Table top made from 18 mm thick ply wood + 4mm thick MDF board with PU coating finish			

SN	Description	Quantity	Unit	Rate	Amount
4.3	Apron (Front side) made from 18 mm thick ply wood + 4mm MDF board with PU Coating finish				
4.4	Both sides made from 18 mm thick ply wood + 4mm MDF board with PU Coating finish				
4.5	3" thick Partition above working table top made from 18 mm thick+6 mm thick ply wood with necessary framing with 4mm thick MDF board + PU Coating finish as per drawing.				
4.6	Exposed edges of Table Top shall be made 36 mm thick by providing additional 18 mm thick ply wood patta of required width.				
4.7	Drawer Storage Unit- 1'-4" W x 2'-0" D, 2 Nos Drawer on top and rest 1 No shutter				
4.8	All the internal surface (non visible surface) shall be provided with 0.60 mm thick balancing laminate FINISHING DETAILS IN NUTSHELL:				
4.5	1) Table Top: 18 mm Thick Plywood with 4 mm thick MDF with High gloss white PU Coating				
	2) Front Appron & Sides: 4mm thick MDF with High gloss white/blue PU Coating 3) Facing of Drawers: 1.0 mm thick Laminate finish				
5	Supplying and installation Dressing Table with Puffy as follows. Dressing Table shall have 1'-6" x 4'-0" size 5mm thick mirror with 1 1/2" x 3" T.W frame and 12 mm thick BWR plywood 2'-0" x 6" size with 1 mm thick laminate on top and having polished edges / bottom supported by brass bracket 2 Nos. as directed. Puffy shall be made of using TW member of size 2"x2" and 18 mm th.plywood for seat support. Seat shall be padded with 4" foam covered with hession cloth and upholstered with Approved shade and quality fabric. Basic price of fabric shall be Rs.400 per Rmt. Visible wooden support shall be polished. Size of Puffy shall be 1'6"x1'6".	1.00	NO		
6	Supplying and installation 3'-0" x 1'-9"x 1'-3" height Center Tepoy as follows.	1.00	NO		
	Providing and making open box structure type Tepoy made out of 36 mm (2X18) thick plywood with all over 1.0 mm thick laminate finish provided with bevelled & diamond polished edges 12mm thick glass top supported on 75 mm X 25 mm SS studs complete as directed.				
7	Same as above item no. 5, but size 1'-9" x 1'-9" x 1'-3" height for Corner Tepoy	2.00	NO		
8	CUSTOMER WRITING DESK Writing Desk Size 3'-0" L x 1'-3" x (0'-6"+3'-0") ht.	1.00	NO		
	Verticle Sides and bottom shall be made out of 36 mm (2X18) thick Commercial plywood and back side 12 mm thick ply wood with Laminate on Top and Edges on all sides including inside divisions. Top shall be made from 12mm th Thoughend glass with polished edges making different divisions by 18 mm thick glass / plywwod with laminate on both side for slips or forms as per detail drawing and inststruction complete. Laminate to be provided on all visible surface				
Ш	Storage/Boxing cabinets of All Heights				
9	STORAGE CABINET with Top & Front laminate finished. Storage of any height Storage of Size 3'-3"x1'-4" x 2'-6"/3'-0" ht. Openable shutter with 1.00 mm thick Laminate finish on Top, front, sides, shutter and 35 mmx6 mm thick Burma Teak beading on Top Edges. Laminate to be provided only on visible surface etc complete as follows. Only Front elevation will be measured for payment purpose. Rate for length Less then 3'-3" Same details as above Item No-2A, with all external surfaces to be finished with Laminate (approved shades)	10.00	SQMT		
	FINISHING DETAILS IN NUTSHELL: 1) Top: Dark Laminate & Burma Teak beading on Edges with pilishade 2) Front Appron & Sides: Dark Laminate/Frosty white Laminate as per design & instructions				
10	P/F ELECTRIC CUB BOARD Providing and fixing Electric cup board using 18 mm thick Bison board for inside verticle division, shelves and shutter. Aluminium framing of 50x25x1.20mm thick with 6 mm thick Bison board on both side for outer partition with 1.0 mm thick laminate on all exposed surface and polishing/ synthetic enamal paint on all internal surface. Shutter will have approved make lock, handle, hinges, ball catches & S.S Perforated jali etc.complete as directed. Depth of cup board will be around 1¹-3". Height of shutter will be maximum 7'-0". Only Front elevation shall be measured for payment purpose.	3.00	SQMT		
11	P/F PANTRY PLATFORM CUB BOARD SHUTTER Providing and fixing cupboard shutters below pantry platform using 1 1/2" x 2 1/2" second grade T.W members for frame, 18 mm Tk plywood with 1.0 mm lamiante for shutters. Providing 1/2" th T.W beading all around shutter. Providing S.S hinges, Handles, stoppers and magnetic catch as directed. All the without lamiante surface shall be polished/ synthetic enamal paint as directed complete.Providing and fixing 0.60 mm thick balancing laminate on internal shutter surface	1.10	SQMT		
IV-A	Partitions & Doors The rate to include provision of extra frame work as necessary for skirting and making openings for glazing & Door etc, cutouts for electrical switch plates, switch boxes, light fittings etc making provision for laying conduits as per drawings & direction. LOW HEIGHT PARTITION WORK				
12	LOW HEIGHT PARTITION WORK PIF LOW HEIGHT BOTH SIDE LAMINATE PARTITION FOR BACK SIDE AND IN BETWEEN S.W COUNTER AND CASH CABIN WITH TOUGHENED GLASS	15.20	SQMT		

Providing and fisting law height partition using \$67m x \$5mm x \$5mm tick Aluminum members maximum in grid of 20° x 20° foliong 12 mm tick. MOP Board exterior grade / 6 mm thick ply of approved brand on both side of aluminium framing and fisting 10 mm tick. Imminiar of approved shade on orbit sides, fisting 12 mm tick. International provided color on the provided color on the provided color of	SN	Description	Quantity	Unit	Rate	Amount
Autrinium members maximum in grid of 2-0° x 2°0° stoing 12 mm thick MOP Board existoric grade 6 mm thick by despreade brand on both side of all uniturium framing and floring 1.0 mm thick terminate of approved shade on both sides, fiding 12 mm thick may be a simple of the provided of the body of the control of the provided of the body of the control of the provided of the body of the provided of	-	Providing and fixing low height partition using 50mm x 25mm x 1.50mm thick				
and fixing 1.0 mm thick laminate of approved shade on both sides, fixing 1.2 mm thick transparent houghneed glass as directed. Appropriate polish on exposed stams beach members with laceure polished edges as directed. Laminate to be provided only on For Low height. Single window and Cash cabin partition, Average height of a control of the control of						
transparent loughened glass as directed. Applying pollsh on exposed steam beach members with acquer polished degas as directed. Amainate to be provided only on visible surface. For Low height Single window and dash cabin partition, Average height of For Low height Single window and dash cabin partition, Average height of For Low height Single window and dash cabin partition, Average height of Polymore and Control of the C						
members with lacquer polithed edges as directed. Laminate to be provided only on visible surface. Single window and Cash cabin partition, Average height of settlinon. About 1. Settlinon. A s						
visible surface, For Low height Single window and Cash cabin partition, Average height of						
and continue has be measured and said. Service as letter no 8.1 but PFF 20.1 SZ mm thick float shutter with both ade laminate and the provided of the provided and three brooks half be provided and three brooks						
Same as inem no 8.1 but PF 30.2 32 mm trick fulls shutter with both side laminate including SS hinges with countersunk SS screws, Aproved make Night latch Lock, S.S Handles, Door dispipers, decisionally detected.		For Low height Single window and Cash cabin partition, Average height of				
Same as item no 8.1 but PFF 30 / 32 mm thick flush shutter with both side laminate including Shinges with countersaria Sis serves, Aproved make Night latch Lock, S. S. Handles Door stoppers, decrisor et complete as directed. **Result of the Providing and the Shinges with control of the Shinges with control of the Shinges with control of the Shinges with the Shinges with shall be considered. No extra payment shall be made for members going up to slabibleam bottom. **PROVIDING In Case of varying heights on elimbar raide of partition, average height shall be considered. No extra payment shall be made for members going up to slabibleam bottom. **PROVIDING MITH DOOR CLOSURE** **Providing and fixing both adea laminate full height partly glazed antition using Spine 12 (27 St. 27	12		2.00	COMT		
including SS hinges with countersunk SS servews, Aprroved make Night latch. Lock, S.S. Handles, Door stoppers, doorstopers de complete as directed. IV-B FULL HEIGHT PARTITION WORK Measurement of height shall be taken from finished floor level upto the level of false celling, incase of varying heights on either side of partition, average height shall be not been selected to the side of partition, average height shall be not been selected to the state of partition and shall be not been selected to the state of partition and shall be not been selected to the state of partition and shall be not been selected to the state of partition using 50mm x 1.50mm block Aluminium members in a maximum grid of 2-0° x 2-0° fibring 12 mm block MPC Board exterior grade 16 mm block grid port both sides. I) mm harmate of approved make shall be freed on MPC playwood. Providing and fibring 5.08.0 mm block and thick flush attent both side aliminated and fibring of mm block grid may be shall be freed on MPC playwood. Providing and fibring 5.08.0 mm block grid may be shall be freed on MPC playwood. Provided as directed. Godrei Mcrice lock shall be provided in some shall be provided as directed. Godrei Mcrice lock shall be provided in some shall be recorded in the shall be shal	13		2.60	SQIVII		
IV-B FULL HEIGHT PARTITION WORK						
Measurement of height shall be taken from finished floor level upto the level of false ociling, in case of varying heights on either side of partition, average height shall be considered. No extra payment shall be made for members going up to slab/beam bottom. 14		Handles,Door stoppers, doorstop etc complete as directed.				
Measurement of height shall be taken from finished floor level upto the level of false ociling, in case of varying heights on either side of partition, average height shall be considered. No extra payment shall be made for members going up to slab/beam bottom. 14	11/15	EUL HEIGHT BARTITION WORK				
false ceiling, in case of varying heights on either side of partition, average height shall be considered. No extra payment shall be made for members going up to slabbbasm bottom. PF BOTH SIDE LAMINATE SOLID/ PARTLY GLAZED FULL HEIGHT PARTITION WITH BOOR WITH DOOR CLOSURE Providing and fixing both sides taimslate full height partly glazed partition using 50mm x 25mm x 1.50mm thick Auminium members in a maximum grid of 2-2° x 2-0° fixing 12 mm work with a simulate full height partly glazed partition using 50mm x 25mm x 1.50mm thick Auminium members in a maximum grid of 12-0° x 2-0° fixing 12 mm thick float glass as directed in the partition. Providing and fixing 50/180 mm thick float glass as directed in the partition. Providing and fixing 6 mm thick glass with beading patil. 5° Long 3 Nos stainless steel hinges, cloorstop shall be provided as directed. Godrel Mortice lock shall be provided in door shutter Providing and fixing 10 mm thick float glass as directed in the partition. Providing for mm thick glass with beading patil. 5° Long 3 Nos stainless steel hinges, cloorstop shall be provided as directed. Godrel Mortice lock shall be provided in door shutter Providing and fixing 10 mm thick float shall have lecuper polished as directed. 15 PROVIDING AND FIXING 12 MM THICK TOUGHENED GLASS DIAPHARM FOR SEPARATING TWO MC FOR ELOOSY P JF 12mm th Toughened glass Diapharm between two machines with etching and frosting Films complete as directed. Class edges shall be round moutded and polished as per direction. Glass shall be fixed in wall and floor with necessary suitable patch fittings as directed. Glass edges shall be round moutded and polished as per direction. Glass shall be fixed in wall and floor with necessary suitable patch fittings as directed. Glass edges shall be round moutded and polished as per directed. The providing and laying panelling on wall as pillars having 12 mm thick. MDF Board exterior grade with Auminium framing of 25mm x 12 mm thick thin suitable patch for grade with Auminium framing of 2	IV-B					
shall be considered. No extra payment shall be made for members going up to slabbbasm bottom. 14 PF BOTH SIDE LAMINATE SOLIDI PARTLY GLAZED FULL HEIGHT PARTITION 15 POYORING and fishing both sides laminated full height partly glazed partition using 50mm x.25mm x1.5mm bits. Aluminum members in a maximum grid of 2-07 x-27 biting 12 approved make shall be fixed on MDF / phywood. Providing and fixing 50.08 nm thick float glass as directed in the partition. Providing and fixing 50.08 nm thick float glass as directed in the partition. Providing and fixing 50.08 nm thick flush shutter both side laminated and fixing 6 mm thick glass with beading pattl. 5° Long 3 Nos stainless steel hinges, doorstop shall be provided as directed. Godrey Mortice lock shall be provided in door shutter. Providing and fixing 10-mma/20xneGorde 17 equivalent make door closure. All visible members if not laminated shall have lacquer polished as directed. 15 PROVIDING AND FIXING 12 MM THICK TOUGHENED GLASS DIAPHARM FOR 2.00 SQMT SPRANTING TWO MICFOR ELOOBY 16 PROVIDING AND FIXING 12 MM THICK TOUGHENED GLASS DIAPHARM FOR 2.01 SQMT SPRANTING TWO MICFOR ELOOBY 17 F12mm toughened glass Diapharm between two machines with etching and frosting Films complete as directed. Glass edges shall be round moulded and polished as per direction. Class shall be fixed to make a provided to the fixed in wall and floor with necessary suitable patch fittings as directed. (Area based on outer diameters shall be measured and paid). 16 PARSILLING WORK 17 PARSILLING WORK 18 PARSILLING WORK 19 PARSILLING WORK 19 PARSILLING WORK 10 PARSILLING WORK 10 PARSILLING WORK 10 PARSILLING WORK 10 PARSILLING WORK 11 PROVIDING and fixing fixing the measured and paid). 12 PARSILLING WORK 12 PARSILLING WORK 13 PARSILLING WORK 14 PARSILLING WORK 15 POYORING and fixing fixing the measured for mick with high gloss PU coating over central column having 8mm thick MDF Board exterior grade with Aluminium framing of 25mm shall part the mick blue glossy laminate behind desi						
14 PF BOTH SIDE LAMINATE SOLID PARTLY GLAZED FULL HEIGHT PARTITION WITH DOOR WITH DOOR CLOSURE Providing and fixing both sides laminate full height partily glazed partition using 50mm x 25mm x 15mm thick Munimium members in a maximum grid of 2-0° x 2-0° fixing 12 mm thick MDF Board exterior grade / 6 mm thick ply on both sides,1.0 mm laminate of approved make shall be fixed on MDF / plywood. Providing and fixing 50/80 mm thick float glass as directed in the partition. Providing and fixing 50/80 mm thick float glass as directed in the partition. Providing and fixing 6 mm thick glass with beading patil, 5° Long 3 Nos stainless steel hinges, doorstop, shall be provided as directed. Godre Morte on the provided as directed. Godre Stall be provided as directed. Godre Stall be provided as prediction. Glass shall be fixed in wall and floor with necessary suitable path fittings as directed. (Area based on outer diameters shall be round moulded and polished as per direction. Glass shall be fixed in wall and floor with necessary suitable path fittings as directed. (Area based on outer diameters shall be measured and paid). V PANELLING WORK V PANELLING WORK 7 Providing and lighting panelling on walls & pillars bring 12 mm thick MDF Board exterior grade / 6 mm thick by pand 1.0 mm th laminate fixed on wall & pillars with Aluminium, framing of 25mm x25mm x1.20mm thick at maximum 2-0° c/c bothways on wall and pillar et complete as directed as per design and instruction of Architect. Providing and fixing fixem thick All maximum 2-0° c/c bothways aps per drawing and direction with all labour and material etc complete in thick at maximum 2-0° c/c bothways aps per drawing and direction with all labour and material etc complete in thick at maximum 2-0° c/c bothways aps per drawing and direction with all lights of the particular providing and laying panelling on wal						
WITH DOOR WITH DOOR CLOSURE						
Providing and fixing both sides laminate full height partly glazed partition using 50mm x 25mm x 15mm thick Munimium members in a maximum grid of 2°C x°C x°C fixing 12 mm thick MDF Board exterior grade / 6 mm thick ply on both sides, 1.0 mm laminate of approved make shall be fixed on MDF / plywood. Providing and fixing 50x80 mm thick float glass as directed in the partition. Providing and fixing 50x80 mm thick float sides is shutter both side laminated and fixing 6 mm thick glass with beading part, 5°C Long 3 Nos stainless steel hinges, doorstop shall be provided as directed. Godrej Mortice lock shall be provided in door shutter Providing and fixing Torma/Ozone/Godrej or equivalent make door closure. All visible members if not laminated shall have lacquery polished as directed door shutter. Providing and fixing Torma/Ozone/Godrej or equivalent make door closure. All visible members if not laminated shall have lacquery polished as directed. 15 PROVIDING AND FIXING 12 MM THICK TOUGHENED GLASS DIAPHARM FOR SEPARATING TWO MC FOR ELOGEY P. Fr. 12mm th Toughened glass Diapharm glass and the crush machines with ectaing and separate closure of the control of the c	14		17.40	SQMT		
mm thick MDF Board exterior grade / 6 mm thick pty on both sides, 1.0 mm laminate of approved make shall be fixed on MDF / physood. Providing and fixing 5.00 f.0 mm thick float glass as directed in the partition. Providing and fixing of 5 mm thick glass with beading pattl, 5° Long 3 Nos stainless steel hinges, doorstop shall be provided as directed. Godrej Mortice lock shall be provided in door shutter-Providing and fixing from the partition of the provided as directed. Godrej Mortice lock shall be provided in door shutter-Providing and fixing 10 mm the shall have leacure posished as directed. Godrej Mortice lock shall be provided in door shutter-Providing and fixing 10 mm the shall have leacure posished as directed. Glass shall be fixed to stain the shall have leacure posished as directed. Glass shall be fixed to stain the shall have leacure posished as directed. Glass directed. Glass shall be fixed in wall and floor with necessary suitable patch fittings as directed. Glass directed. Glass edges shall be round moulded and polished as per direction. Glass shall be fixed in wall and floor with necessary suitable patch fittings as directed. Glass directed. Glass shall be fixed in wall and floor with necessary suitable patch fittings as directed. Glass shall be fixed in wall and plilar etc. 16. PF Wall panelling with laminate finishing for wall and Pillar etc. 17 Providing and laying panelling on walls & pillars having 12 mm thick MDF Board exterior grade of mm thick ply and 1.0 mm th laminate fixed on pillar with all shoul and with 1 mm thick blue glossy laminate fixed on pillar with aluminium framing of 25 mm 25mm x1.20 mm thick at maximum 2-0° c/c bothways on wall and pillar etc complete as directed as per design and instruction of Architect. 17 Providing and fixing 8mm thick MDF Board exterior grade with 3 M winy glossy flims with printed design fixed on wall with all labour and material etc complete. 18 Panelling for Display wall with 3M Winyi glossy Flim with printed design providing and plying panelling						
approved make shall be fixed on MDF / plywood. Providing and fixing 5.0/8.0 mm thick float glass as directed in the partition. Providing and fixing door shutter using 32 mm thick flush shutter both side laminated and fixing 6 mm thick glass with beading patit. 5° Long 3 Nos stainless steel hinges, doors of shall be provided as directed. Godre Mortice lock shall be provided in door of shutter. Providing and fixing 10-mm/20cm/60de; 1° ce quivalent make door closure. All visible members if not laminated shall have lacquer polished as directed. 15 PROVIDING AND FIXING 12 MM THICK TUOHENED GLASS DIAPHARM FOR SEARATING. TWO MC FOR ELOBY P. F12 mm throughened glass Diapharm between two machines with etching and frosting Films complete as directed. Class edges shall be round moulded and polished as per direction. Class shall be fixed in wall and floor with necessary suitable patch fittings as directed. (Area based on outer diameters shall be measured and paid). V PANELLING WORK 16 PIF Wall panelling with laminate finishing for wall and Pillar etc. Providing and laying panelling on walls 8, pillars having 12 mm thick MDF Board exterior grade / 6 mm thick ply and 1.0 mm h laminate fixed on wall 8 pillars with Adminitum faming of Zimmore. Zim		x 25mm x 1.50mm thick Aluminium members in a maximum grid of 2'-0" x 2'-0" fixing 12				
float glass as directed in the partition. Providing and fixing for mithick glass with beading path, 5° Long 3 Nos stainless steel hinges, doorstop shall be provided as directed. Godrey Mortice lock shall be provided in door shutter-Providing and fixing 10 mm thick glass with beading path, 5° Long 3 Nos stainless steel hinges, doorstop shall be provided as directed. Godrey Mortice lock shall be provided in door shutter-Providing and fixing 10 mm and the provided in door shutter-Providing and fixing 10 mm and 10						
thick flush shutter both side laminated and fixing 6 mm thick glass with beading patit. 5' Long 3 Nos stailness steel hings, doors pshall be provided as directed. Godre Mortice lock shall be provided in door shutter.Providing and fixing 'Pormal/Cozne/Gorde'; or equivalent make door closure. All visible members if not laminated shall have lacquer polished as directed. 15 PROVIDING AND FIXING 2 MM THICK TOUGHENED GLASS DIAPHARM FOR SPARATING. TWO MC FOR ELODBY 9' P! Turn th Toughened glass Diapharm between two machines with etching and frosting Films complete as directed. Class sedges shall be round moulded and polished as per direction. Class shall be fixed in wall and floor with necessary suitable patch fittings as directed. (Area based on outer diameters shall be measured and paid). V PANELLING WORK 16 PF Wall panelling with laminate finishing for wall and Pillar etc. Providing and laying panelling on walls 8, pillars having 12 mm thick MDF Board exterior grade / 6 mm thick by and 1.0 mm h laminate fixed on wall 8 pillars with Aluminium faming of 2 mm thick things and things a						
S Cong 3 Nos stainless steel hinges, doorstop shall be provided as directed. Godreg Mortice lock shall be provided in door shutter-Providing and fixing "Dorma/Cozone/Godrej" or equivalent make door closure. All visible members if not laminated shall have lacquer polished as directed. 15 PROVIDING AND FIXING 12 MM THICK TOUGHENED GLASS DIAPHARM FOR SEPARATING TWO MICP FOR E-LOOSE. 9 FF 12mm it Toughened glass Diapharm between two machines with etching and frosting Films complete as directed. Glass deges shall be round moulded and polished as per direction. Glass shall be fixed in wall and floor with necessary suitable patch fittings as directed. (Area based on outer diameters shall be measured and paid). V PANELLING WORK 16 PF Wall panelling with laminate finishing for wall and Pillar etc. Providing and laying panelling on walls & pillars having 12 mm thick MDF Board exterior grade / 6 mm thick ply and 1.0 mm th laminate fixed on wall & pillars with Aluminium. framing of 25mmx25mmx1.20mm thick at maximum 2-0° o'c bothways on wall and pillar etc complete as directed as per design and instruction of Architect. Providing and fixing 8mm thick MDF Board exterior grade with jail work with high gloss PU coating over central column having 8mm thick MDF Board texterior grade covered with 1 mm thick blue glossy laminate fixed on pillar with aluminium framing of 25mm x25mm x120 mm thick at maximum 2-0° o'c bothway as per drawing and direction with all labour and material etc complete. (Rate shall be including CNC cutting jail work and 1 mm thick blue glossy laminate behind design lail work as directed) 18 Panelling for Display wall with 3M Vinyl glossy Film with printed design Providing and laying panelling on wall having 8 mm th MDF Board exterior grade with 3M Vinyl glossy films with printed design fixed on wall with Aluminium framing of 25mmx25mmx1.20mm thick at maximum 2-0° o'c bothways etc. complete as directed. panelling as per design and instruction of Architect. MDF board to be finished with 0.60 mm thick						
"Dormal/CzonelGodrej" or equivalent make door closure. All visible members if not laminated shall have lacquer polished as directed. 15 PROVIDING AND FIXING 12 MM THICK TOUGHENED GLASS DIAPHARM FOR SEPARATING TWO MIC FOR ELJOBEY P /F 12 mm th Toughened glass Diapharm between two machines with etching and frosting Films complete as directed. Glass edges shall be round moulded and polished as per direction. Glass shall be fixed in wall and floor with necessary suitable patch fittings as directed. (Area based on outer diameters shall be measured and paid). V PANELLING WORK V PANELLING WORK Providing and laying panelling on walls & pillars having 12 mm thick MDF Board exterior grade / 6 mm thick ply and 1.0 mm th laminate fixed on wall & pillars with Aluminium framing of 25mm/25mm/1.20mm thick at maximum 2:0" of c bothways on wall and pillar etc complete as directed as per design and instruction of Architect. Providing and fixing 8mm thick MDF Board exterior grade with jall work with high gloss PU coating over central column having 8mm thick MDF Board Exterior grade covered with 1 mm thick this egiossy laminate brised on pillar with alluminium framing of 25mm x25mm x1.20 mm thick at maximum 2:0" of c bothways as per drawing and direction with all abour and material etc complete. (Rate shall be including CNC cutting jall work and 1 mm thick blue glossy laminate behind design pill work as directed) Providing and laying panelling on wall having 8 mm th MDF Board exterior grade with 3M vinyl glossy films with printed design fixed on wall with Aluminium framing of 25mm/25mm/25mm thick at maximum 2:0" of c bothways etc. complete as directed, panelling as per design and instruction of Architect, MDF board to be finished with 0.60 mm thick laminate or paniling on wall having 8 mm th MDF Board exterior grade with 3M vinyl glossy films with printed design fixed on wall with Aluminium framing of 25mm x 25mm x 1.20 mm thick at maximum 2:0" of c bothways etc. complete as directed, panelling as per design and instruction						
Is aminated shall have lacquer polished as directed. ProViDios AnD FixING 12 MM THICK TOUGHENED GLASS DIAPHARM FOR 2.00 SOMT Prif Tarm in Toughened glass Diapharm between two machines with etching and frosting Films complete as directed. Class edges shall be round moulded and polished as per direction. Class shall be fixed in wall and floor with necessary suitable patch fittings as directed. (Area based on outer diameters shall be measured and paid). V PANELLING WORK 16 PiF Wall panelling with laminate finishing for wall and Pillar etc. 17.30 SOMT Providing and laying panelling on walls. & pillars having 12 mm thick MDF Board exterior grade / 6 mm thick ply and 1.0 mm th laminate fixed on wall & pillars with Aluminium. framing of ZemmxZemmx2. Journal to bothways on wall and pillar etc complete as directed as per design and instruction of Architect. Providing and fixing 8 mm thick MDF Board exterior grade with jall work with high gloss PU coating over central column having 8 mm thick MDF Board Exterior grade covered with 1 mm thick blue glossy laminate fixed on pillar with aluminium framing of 25mm x25mm x1.20 mm thick at maximum 2-0° c/c bothway as per drawing and direction with all labour and material etc complete. (Rate shall be including CNC cutting Jall work and 1 mm thick blue glossy laminate behind design pall work as directed) Providing and laying panelling on wall having 8 mm th MDF Board exterior grade with 3M viryl glossy flims with printed design. Providing and laying and instruction of Architect. MDF board to be finished with 0.60 mm thick laminate or panile grow with a lawing 8 mm thick blue glossy laminate bened by a law of the providing and laying panelling on wall having 8 mm th MDF Board exterior grade with with printed design fixed on wall with Aluminium framing of 25mm x25mm x1.20 mm thick at maximum 2-0° c/c bothways etc. complete as directed panelling as per design and instruction of Architect. MDF board to be finished with 0.60 mm thick laminator providing and pilying Wall four s		,				
PROVIDING AND FIXING 12 MM THICK TOUGHENED GLASS DIAPHARM FOR SEARATING TWO MIC FOR ELOOBY P /F 12mm th Toughened glass Diapharm between two machines with etching and frosting Films complete as directed. Glass edges shall be round moulded and polished as per direction. Glass shall be fixed in wall and floor with necessary suitable patch filtitings as directed. (Area based on outer diameters shall be measured and paid). V PANELLING WORK 10 P/F Wall panelling with laminate finishing for wall and Pillar etc Providing and laying panelling on walls & pillars having 12 mm thick MDF Board exterior grade / 6 mm thick ply and 1.0 mm to laminate fixed on wall & pillars with Aluminium framing of 25mmx/25mmx1 20mm thick at maximum 2-0" c/c bothways on wall and pillar etc complete as directed as per design and instruction of Architect. Providing and fixing 8mm thick MDF Board exterior grade with jall work with high gloss PU coating over central column having 8mm thick MDF Board Exterior grade with 1 mm thick blue glossy laminate fixed on pillar with aluminium framing of 25mmx 25mm x1 20 mm thick at maximum 2-0" c/c bothway as per drawing and direction with all fabour and material etc complete. (Rate shall be including CNC cutting jall work and 1 mm thick blue glossy laminate behind design jall work as directed) Providing and laying panelling on wall having 8 mm th MDF Board exterior grade with 3M vinyl glossy films with printed design fixed on wall with Aluminium framing of 25mmx25mmx120mm thick at maximum 2-0" c/c bothways etc. complete as directed. panelling as per design and instruction of Architect. MDF board to be finished with 0.60 mm thick talmination praining 5M film. Only Front elevation area shall be measured for payment purpose. Exposed edges of Display wall four side shall be made 36 mm thick by providing additional required thickness MDF patta of required with. Providing and laying panelling on wall having 8mm th MDF Board exterior grade with PU coating fixed on wall with Bluer white high gloss PU Coat						
SEPARATING TWO MC FOR E-LOOBY P. F. Turm th Toughend glass Dispharm between two machines with etching and frosting Films complete as directed. Glass edges shall be round moulded and polished as per direction. Glass shall be fixed in wall and floor with necessary suitable patch fittings as directed. (Area based on outer diameters shall be measured and paid). V PANELLING WORK 16 PJF Wall panelling with laminate finishing for wall and Pillar etc Providing and laying panelling on walls & pillars having 12 mm thick MDF Board exterior grade / 6 mm thick ply and 1.0 mm th laminate fixed on wall & pillars with Aluminium, framing of 25mm/25mmx1.2 mm thick at maximum 2-0° c/c bothways on wall and pillar etc complete as directed as per design and instruction of Architect. Providing and fixing 8mm thick MDF Board exterior grade with jall work with high gloss PU coating over central column having 8mm thick MDF Board Exterior grade covered with 1 mm thick blue glossy laminate fixed on pillar with aluminium framing of 25mm x25mm x1.20 mm thick at maximum 2-0° c/c bothways as per drawing and direction with all labour and material etc complete. (Rate shall be including CNC cutting jall work and 1 mm thick blue glossy laminate behind design jall work as directed) 18 Panelling for Display wall with 3M winyl glossy Film with printed design Providing and laying panelling on wall having 8 mm th MDF Board exterior grade with 3M winyl glossy films with printed design fixed on wall with Aluminium framing of 25mmx25mmx1.20mm thick at maximum 2-0° c/c bothways etc. complete as directed. panelling as per design and instruction of Architect. MDF board to be finished with 0.60 mm thick laminate or paint before laying 3M film. Only Front elevation surface area shall be measured for payment purpose. Exposed edges of Display wall four side shall be made 36 mm thick by providing additional required thickness MDF patts of required with. Providing and laying panelling on wall having 8mm th MDF Board be thinshed with 0.60 mm thick atmaxim		· ·				
P /F 12mm th Toughened glass Diagharm between two machines with etching and frosting Films complete as directed, Glass edges shall be round moulded and polished as per direction. Glass shall be fixed in wall and floor with necessary suitable patch fittings as directed. (Area based on outer diameters shall be measured and paid). V PANELLING WORK 16 P/F Wall panelling with laminate finishing for wall and Pillar etc Providing and laying panelling on walls & pillars having 12 mm thick MDF Board exterior grade / 6 mm thick ply and 1.0 mm to laminate fixed on wall & pillars with Aluminium. framing of 25mmx25mmx1.20mm thick at maximum 2**0" c/c bothways on wall and pillar etc complete as directed as per design and instruction of Architect . Providing and fixing 8mm thick MDF Board exterior grade with jail work with high gloss PU coating over central column having 8mm thick MDF Board Exterior grade covered with 1 mm thick blue glossy laminate fixed on pillar with aluminium framing of 25mmx25mm x1.20 mm thick at maximum 2**0" c/c bothway as per drawing and direction with all labour and material etc complete. Rate shall be including CNC cutting jail work and 1 mm thick blue glossy laminate behind design all work as directed) Providing and laying panelling on wall having 8 mm th MDF Board exterior grade with 3M virty glossy flims with printed design fixed on wall with Aluminium framing of 25mmx25mmx1.20mm thick at maximum 2**0" c/c bothways etc. complete as directed. panelling are design and instruction of Architect. MDF board to be finished with 0.0 mm thick laminate or paint before laying 3M film. Only Front elevation area shall be measured for payment purpose. Exposed edges of Display wall four side shall be made 36 mm thick by providing additional required thickness MDF patta of required with. Providing and laying panelling on wall having 8mm th MDF Board exterior grade with PU coating fixed on wall with Aluminium framing of 25mmx 25mmx 1.20 mm thick at maximum 2**0" c/c bothways etc. complete as directed. Only	15		2.00	SQMT		
frosting Films complete as directed. Glass edges shall be round moulded and polished as per direction. Glass shall be fixed in wall and floor with necessary suitable patch fittings as directed. (Area based on outer diameters shall be measured and paid). V PANELLING WORK 16 PF Wall panelling with laminate finishing for wall and Pillar etc Providing and laying panelling on walls & pillars having 12 mm thick MDF Board exterior grade / 6 mm thick ply and 1.0 mm th laminate fixed on wall & pillars with Aluminium. framing of 25mmx25mmx120mm thick at maximum 2-0° of co bothways on wall and pillar etc complete as directed as per design and instruction of Architect. Providing and fixing 8mm thick MDF Board exterior grade with jall work with high gloss PU coating over central column having 8mm thick MDF Board Exterior grade covered with 1 mm thick blue glossy laminate fixed on pillar with aluminium framing of 25mm x25mm x12.0mm thick at maximum 2-0° of bothway as per drawing and direction with all labour and material etc complete. (Rate shall be including CNC cutting jali work and 1 mm thick blue glossy laminate behind design jall work as directed) 18 Panelling for Display wall with 3M Vinyl glossy Film with printed design Providing and laying panelling on wall having 8 mm th MDF Board exterior grade with 3M vinyl glossy films with printed design fixed on wall with Aluminium framing of 25mmx25mmx1.20mm thick at maximum 2-0° c/c bothways etc. complete as directed, panelling as per design and instruction of Architect. MDF board to be finished with 0.60 mm thick laminate or paint before laying 3M film. Only Front elevation area shall be measured for payment purpose. Exposed edges of Display wall four side shall be made 36 mm thick by providing additional required thickness MDF patta of required with. Priv WALL PAPERS on Digital wall Providing and laying panelling on wall having 8mm th MDF Board exterior grade with PU coating fixed on wall with Blue of white high gloss provided with a same and provided with a silence						
Testings Strings Str		frosting Films complete as directed. Glass edges shall be round moulded and polished				
Prival panelling with laminate finishing for wall and Pillar etc 12.30 SQMT		'				
160 PiF Wall panelling with laminate finishing for wall and Pillar etc 12.30 SQMT		fittings as directed. (Area based on outer diameters shall be measured and paid).				
160 PiF Wall panelling with laminate finishing for wall and Pillar etc 12.30 SQMT	v	PANELLING WORK				
Providing and laying panelling on walls & pillars having 12 mm thick MDF Board exterior grade / 6 mm thick ply and 1.0 mm th laminate fixed on wall & pillars with Aluminium. framing of 25mmx25mmx1.20mm thick at maximum 2'-0" c/c bothways on wall and pillar etc complete as directed as per design and instruction of Architect. Providing and fixing 8mm thick MDF Board exterior grade with jalli work with high gloss PU coating over central column having 8mm thick MDF Board Exterior grade covered with 1 mm thick blue glossy laminate fixed on pillar with aluminium framing of 25mm x25mm x1.20 mm thick at maximum 2'-0" c/c bothway as per drawing and direction with all labour and material etc complete. (Rate shall be including CNC cutting jall work and 1 mm thick blue glossy laminate behind design jall work as directed) Panelling for Display wall with 3M Vinyl glossy Film with printed design Providing and laying panelling on wall having 8 mm th MDF Board exterior grade with MM will yill glossy films with printed design fixed on wall with Aluminium framing of 25mmx25mmx1.20mm thick at maximum 2'-0" c/c bothways etc. complete as directed, panelling as per design and instruction of Architect. MDF board to be finished with 0.60 mm thick laminate or paint before laying 3M film. Only Front elevation area shall be measured for payment purpose. Exposed edges of Display wall four side shall be made 36 mm thick by providing additional required thickness MDF patta of required width. Providing and laying panelling on wall having 8mm th MDF Board exterior grade with PU coating fixed on wall with Aluminium framing of 25mmx 25mmx 1.20 mm thick at maximum 2'-0" c/c bothways etc. complete as directed. Only front elevation surface area shall be measured for payment. Providing and laying panelling on wall having 8mm th MDF Board exterior grade with PU coating fixed on wall with Aluminium framing of 25mm x 25mm x 1.20 mm thick at maximum 2'-0" c/c bothways etc. complete as directed. Only front elevation surface area shall be measured			12.30	SQMT		
Aluminium, framing of 25mmx25mmx1.20mm thick at maximum 2-0" of bothways on wall and pillar etc complete as directed as per design and instruction of Architect. Providing and fixing 8mm thick MDF Board exterior grade with jali work with high gloss PU coating over central column having 8mm thick MDF Board Exterior grade covered with 1 mm thick blue glossy laminate fixed on pillar with aluminium framing of 25mm x25mm x1.20 mm thick at maximum 2-0" of c bothway as per drawing and direction with all labour and material etc complete. (Rate shall be including CNC cutting jali work and 1 mm thick blue glossy laminate behind design jali work as directed) 18 Panelling for Display wall with 3M Vinyl glossy Film with printed design Providing and laying panelling on wall having 8 mm th MDF Board exterior grade with 3M vinyl glossy films with printed design fixed on wall with Aluminium framing of 25mmx25mmx1.20mm thick at maximum 2-0" of core bothways etc. complete as directed. panelling as per design and instruction of Architect. MDF board to be finished with 0.60 mm thick laminate or paint before laying 3M film. Only Front elevation area shall be measured for payment purpose. Exposed edges of Display wall four side shall be made 36 mm thick by providing additional required thickness MDF patta of required width. 19 Panelling for Digital wall with Blue / white high gloss PU Coating finishing Providing and laying panelling on wall having 8mm th MDF Board exterior grade with PU coating fixed on wall with Aluminium framing of 25mm x 25mm x 1.20 mm thick at maximum 2-0" of bothways etc. complete as directed. Only front elevation surface area shall be measured for payment. PiA WALL PAPERS on Digital wall Providing and applying Wall paper approved by Architect / Bank's Engineer having basic price of Rs 100=00 Per Sa.Ft 21 ALUMINUM COMPOSTEP PANEL FOR E-LOBBY Forviding and fixing 3 mm thick aluminium composite panel of Flexi Bond / Euro Bond / Timex with 0.25 mm foli with 50 mm x 25 mm x 1.20 mm thick aluminium hollow secti						
wall and pillar etc complete as directed as per design and instruction of Architect. Providing and fixing 8mm thick MDF Board exterior grade with jall work with high gloss PU coating over central column having 8mm thick MDF Board Exterior grade covered with 1 mm thick blue glossy laminate fixed on pillar with aluminium framing of 25mm x25mm x1.20 mm thick at maximum 2-0" c/c bothways as per drawing and direction with all albour and material etc complete. (Rate shall be including CNC cutting jall work and 1 mm thick blue glossy laminate behind design jall work as directed) 18 Panelling for Display wall with 3M Vinyl glossy Film with printed design Providing and laying panelling on wall having 8 mm th MDF Board exterior grade with 3M vinyl glossy films with printed design fixed on wall with Aluminium framing of 25mmx25mmx1.20mm thick at maximum 2-0" c/c bothways etc. complete as directed. 270 SQMT 270 SQMT Providing and laying panelling on wall having 8 mm th MDF Board exterior grade with 0.60 mm thick laminate or paint before laying 3M film. Only Front elevation area shall be measured for payment purpose. Exposed edges of Display wall four side shall be made 36 mm thick by providing additional required thickness MDF patta of required width. Providing and laying panelling on wall having 8mm th MDF Board exterior grade with PU coating fixed on wall with Blue / white high gloss PU Coating finishing 4.50 SQMT Providing and laying panelling on wall having 8mm th MDF Board exterior grade with PU coating fixed on wall with Aluminium framing of 25mm x 25mm x 1.20 mm thick at maximum 2-0" c/c bothways etc. complete as directed. Only front elevation surface area shall be measured for payment. P/A WALL PAPERS on Digital wall Providing and fixing 3 mm thick aluminium composite panel of Flexi Bond / Euro Bond / Timex with 0.25 mm foil with 50 mm x 25 mm x 1.20 mm thick aluminium hollow section tray system with minimum 20 mm bending with silicon Dow Coming of GE seal proof - ACP of approved indian make complete as						
Providing and fixing 8mm thick MDF Board exterior grade with jalli work with high gloss PU coating over central column having 8mm thick MDF Board Exterior grade covered with 1 mm thick blue glossy laminate fixed on pillar with aluminium framing of 25mm x25mm x1.20 mm thick at maximum 2'-0' c/c bothway as per drawing and direction with all abour and material etc complete. (Rate shall be including CNC cutting jall work and 1 mm thick blue glossy laminate behind design jall work as directed) Panelling for Display wall with 3M Vinyl glossy Film with printed design and laying panelling on wall having 8 mm th MDF Board exterior grade with 3M vinyl glossy films with printed design fixed on wall with Aluminium framing of 25mmx25mmx1.20mm thick at maximum 2'-0" c/c bothways etc. complete as directed. panelling as per design and instruction of Architect. MDF board to be finished with 0.60 mm thick laminate or pain before laying 3M film. Only Front elevation area shall be measured for payment purpose. Exposed edges of Display wall four side shall be made 36 mm thick by providing additional required thickness MDF patta of required width. 19 Panelling for Digital wall with Blue / white high gloss PU Coating finishing Providing and laying panelling on wall having 8mm th MDF Board exterior grade with PU coating fixed on wall with Aluminium framing of 25mm x 25mm x 1.20 mm thick at maximum 2'-0" c/c bothways etc. complete as directed. Only front elevation surface area shall be measured for payment. PIA WALL PAPERS on Digital wall 20 Providing and applying Wall paper approved by Architect / Bank's Engineer having basic price of Rs 100-200 per Sq.Ft 21 ALUMINUM COMPOSITE PANEL FOR E-LOBBY Providing and fixing 3 mm thick aluminium composite panel of Flexi Bond / Euro Bond / Timex with 0.25 mm foil with 50 mm x 25 mm x 1.20 mm thick aluminium hollow section tray system with minimum 20 mm bending with silicon Dow Coming of GE seal proof -ACP of approved indian make complete as per selection and direction of Architect for f						
gloss PÜ coating over central column having 8mm thick MDF Board Exterior grade covered with 1 mm thick blue glossy laminate fixed on pillar with aluminium framing of 25mm x25mm x1.20 mm thick at maximum 2-0° c/c bothway as per drawing and direction with all labour and material etc complete. (Rate shall be including CNC cutting jali work and 1 mm thick blue glossy laminate behind design jali work as directed) 18 Panelling for Display wall with 3M Vinyl glossy Film with printed design Providing and laying panelling on wall having 8 mm th MDF Board exterior grade with 3M vinyl glossy films with printed design fixed on wall with Aluminium framing of 25mmx25mmx1.20mm thick at maximum 2-0° c/c bothways etc. complete as directed. panelling as per design and instruction of Architect. MDF board to be finished with 0.60 mm thick laminate or paint before laying 3M film. Only Front elevation area shall be measured for payment purpose. Exposed edges of Display wall four side shall be made 36 mm thick by providing additional required thickness MDF patta of required width. 19 Panelling for Digital wall with Blue / white high gloss PU Coating finishing Providing and laying panelling on wall having 8mm th MDF Board exterior grade with PU coating fixed on wall with Aluminium framing of 25mm x 25mm x 1.20 mm thick at maximum 2-0° c/c bothways etc. complete as directed. Only front elevation surface area shall be measured for payment. P/A WALL PAPERS on Digital wall Providing and applying Wall paper approved by Architect / Bank's Engineer having basic price of Rs 100=00 Per Sq. Ft 21 ALUMINUM COMPOSITE PANEL FOR E-LOBBY Providing and fixing 3 mm thick aluminium composite panel of Flexi Bond / Euro Bond / Timex with 0.25 mm foli with 50 mm x 25 mm x 1.20 mm thick aluminium hollow section tray system with minimum 20 mm bending with silicon Dow Coming of GE seal proof - ACP of approved indian make complete as per selection and direction of Architect for front facade for the building. This item will be carried out as per manufact						
direction with all labour and material etc complete. (Rate shall be including CNC cutting jall work and 1 mm thick blue glossy laminate behind design jall work as directed) 18 Panelling for Display wall with 3M Vinyl glossy Film with printed design Providing and laying panelling on wall having 8 mm th MDF Board exterior grade with 3M vinyl glossy films with printed design fixed on wall with Aluminium framing of 25mmx25mmx1 20mm thick at maximum 2°-0" c/c bothways etc. complete as directed. panelling as per design and instruction of Architect. MDF board to be finished with 0.60 mm thick laminate or paint before laying 3M film. Only Front elevation area shall be measured for payment purpose. Exposed edges of Display wall four side shall be made 36 mm thick by providing additional required thickness MDF patta of required width. 19 Panelling for Digital wall with Blue / white high gloss PU Coating finishing Providing and laying panelling on wall having 8mm th MDF Board exterior grade with PU coating fixed on wall with Aluminium framing of 25mm x 25mm x 1.20 mm thick at maximum 2°-0" c/c bothways etc. complete as directed. Only front elevation surface area shall be measured for payment. P/A WALL PAPERS on Digital wall Providing and applying Wall paper approved by Architect / Bank's Engineer having basic price of Rs 100=00 Per Sq.Ft 21 ALUMINUM COMPOSITE PANEL FOR E-LOBBY Providing and fixing 3 mm thick aluminium composite panel of Flexi Bond / Euro Bond / Times with 0.25 mm foil with 50 mm x 25 mm x 1.20 mm thick aluminium hollow section tray system with minimum 20 mm bending with silicon Dow Coming of GE seal proof-ACP of approved indian make complete as per selection and direction of Architect for front facade for the building. This item will be carried out as per manufacturer's specifications. Rate also includes providing trap door shutter with hinges, stoppers etc complete as directed. Design as per Bank standered Drawing and Architect's instructions etc complete. TiMEX - DIAMOND WHITE - 111, NAVY BLUE						
direction with all labour and material etc complete. (Rate shall be including CNC cutting jall work and 1 mm thick blue glossy laminate behind design jall work as directed) 18 Panelling for Display wall with 3M Vinyl glossy Film with printed design 2.70 SQMT Providing and laying panelling on wall having 8 mm th MDF Board exterior grade with 3M vinyl glossy films with printed design fixed on wall with Aluminium framing of 25mmx25mmx1.20mm thick at maximum 2'-0" c/c bothways etc. complete as directed. panelling as per design and instruction of Architect. MDF board to be finished with 0.60 mm thick laminate or paint before laying 3M film. Only Front elevation area shall be measured for payment purpose. Exposed edges of Display wall four side shall be made 36 mm thick by providing additional required thickness MDF patta of required width. 19 Panelling for Digital wall with Blue / white high gloss PU Coating finishing Providing and laying panelling on wall having 8mm th MDF Board exterior grade with PU coating fixed on wall with Aluminium framing of 25mm x 25mm x 1.20 mm thick at maximum 2'-0" c/c bothways etc. complete as directed. Only front elevation surface area shall be measured for payment. P/A WALL PAPERS on Digital wall Providing and applying Wall paper approved by Architect / Bank's Engineer having basic price of Rs 100=00 Per Sq.Ft 21 ALUMINUM COMPOSITE PANEL FOR E-LOBBY Providing and fixing 3 mm thick aluminium composite panel of Flexi Bond / Euro Bond / Timex with 0.25 mm foil with 50 mm x 25 mm x 1.20 mm thick aluminium hollow section tray system with minimum 20 mm bending with silicon Dow Coming of GE seal proof - ACP of approved indian make complete as per selection and direction of Architect for front facade for the building. This item will be carried out as per manufacturer's specifications. Rate also includes providing trap door shutter with hinges, stoppers etc complete as directed. Design as per Bank standered Drawing and Architect's instructions etc complete. TIMEX - DIAMOND WHITE - 11						
Rate shall be including CNC cutting jali work and 1 mm thick blue glossy laminate behind design jali work as directed) Panelling for Display wall with 3M Vinyl glossy Film with printed design 2.70 SQMT	17		4.10	SQMT		
Iaminate behind design all work as directed) 2.70 SQMT						
Panelling for Display wall with 3M Vinyl glossy Film with printed design Providing and laying panelling on wall having 8 mm th MDF Board exterior grade with 3M vinyl glossy films with printed design fixed on wall with Aluminium framing of 25mmx25mmx1.20mm thick at maximum 2'-0" c/c bothways etc. complete as directed. panelling as per design and instruction of Architect. MDF board to be finished with 0.60 mm thick laminate or paint before laying 3M film. Only Front elevation area shall be measured for payment purpose. Exposed edges of Display wall four side shall be made 36 mm thick by providing additional required thickness MDF patta of required width. Panelling for Digital wall with Blue / white high gloss PU Coating finishing Providing and laying panelling on wall having 8mm th MDF Board exterior grade with PU coating fixed on wall with Aluminium framing of 25mm x 25mm x 1.20 mm thick at maximum 2'-0" c/c bothways etc. complete as directed. Only front elevation surface area shall be measured for payment. P/A WALL PAPERS on Digital wall Providing and applying Wall paper approved by Architect / Bank's Engineer having basic price of Rs 100=00 Per Sq. Ft ALUMINUM COMPOSITE PANEL FOR E-LOBBY Providing and fixing 3 mm thick aluminium composite panel of Flexi Bond / Euro Bond / Timex with 0.25 mm foil with 50 mm x 25 mm x 1.20 mm thick aluminium hollow section tray system with minimum 20 mm bending with silicon Dow Coming of GE seal proof - ACP of approved indian make complete as per selection and direction of Architect for front facade for the building. This item will be carried out as per manufacturer's specifications. Rate also includes providing trap door shutter with hinges, stoppers etc complete as directed. Design as per Bank standered Drawing and Architect's instructions etc complete. TIMEX - DIAMOND WHITE - 111, NAVY BLUE - 117 or						
3M vinyl glossy films with printed design fixed on wall with Aluminium framing of 25mmx25mmx1.20mm thick at maximum 2*-0" c/c bothways etc. complete as directed. panelling as per design and instruction of Architect. MDF board to be finished with 0.60 mm thick laminate or paint before laying 3M film. Only Front elevation area shall be measured for payment purpose. Exposed edges of Display wall four side shall be made 36 mm thick by providing additional required thickness MDF patta of required width. 19 Panelling for Digital wall with Blue / white high gloss PU Coating finishing Providing and laying panelling on wall having 8mm th MDF Board exterior grade with PU coating fixed on wall with Aluminium framing of 25mm x 25mm x 1.20 mm thick at maximum 2*-0" c/c bothways etc. complete as directed. Only front elevation surface area shall be measured for payment. P/A WALL PAPERS on Digital wall 20 Providing and applying Wall paper approved by Architect / Bank's Engineer having basic price of Rs 100=00 Per Sq.Ft 21 ALUMINUM COMPOSITE PANEL FOR E-LOBBY Providing and fixing 3 mm thick aluminium composite panel of Flexi Bond / Euro Bond / Timex with 0.25 mm foil with 50 mm x 25 mm x 1.20 mm thick aluminium hollow section tray system with minimum 20 mm bending with silicon Dow Coming of GE seal proof - ACP of approved indian make complete as per selection and direction of Architect for front facade for the building. This item will be carried out as per manufacturer's specifications. Rate also includes providing trap door shutter with hinges, stoppers etc complete as directed. Design as per Bank standered Drawing and Architect's instructions etc complete. TIMEX - DIAMOND WHITE - 111, NAVY BLUE - 117 or	18	Panelling for Display wall with 3M Vinyl glossy Film with printed design	2.70	SQMT		
25mmx25mmx1.20mm thick at maximum 2'-0" c/c bothways etc. complete as directed. panelling as per design and instruction of Architect. MDF board to be finished with 0.60 mm thick laminate or paint before laying 3M film. Only Front elevation area shall be measured for payment purpose. Exposed edges of Display wall four side shall be made 36 mm thick by providing additional required thickness MDF patta of required width. 19 Panelling for Digital wall with Blue / white high gloss PU Coating finishing 4.50 SQMT Providing and laying panelling on wall having 8mm th MDF Board exterior grade with PU coating fixed on wall with Aluminium framing of 25mm x 25mm x 1.20 mm thick at maximum 2'-0" c/c bothways etc. complete as directed. Only front elevation surface area shall be measured for payment. P/A WALL PAPERS on Digital wall Providing and applying Wall paper approved by Architect / Bank's Engineer having basic price of Rs 100=00 Per Sq.Ft 21 ALUMINUM COMPOSITE PANEL FOR E-LOBBY Providing and fixing 3 mm thick aluminium composite panel of Flexi Bond / Euro Bond / Timex with 0.25 mm foil with 50 mm x 25 mm x 1.20 mm thick aluminium hollow section tray system with minimum 20 mm bending with silicon Dow Coming of GE seal proof - ACP of approved indian make complete as per selection and direction of Architect for front facade for the building. This item will be carried out as per manufacturer's specifications. Rate also includes providing trap door shutter with hinges, stoppers etc complete as directed. Design as per Bank standered Drawing and Architect's instructions etc complete. TIMEX - DIAMOND WHITE - 111, NAVY BLUE - 117 or						
panelling as per design and instruction of Architect. MDF board to be finished with 0.60 mm thick laminate or paint before laying 3M film. Only Front elevation area shall be measured for payment purpose. Exposed edges of Display wall four side shall be made 36 mm thick by providing additional required thickness MDF patta of required width. 19 Panelling for Digital wall with Blue / white high gloss PU Coating finishing 4.50 SQMT Providing and laying panelling on wall having 8mm th MDF Board exterior grade with PU coating fixed on wall with Aluminium framing of 25mm x 25mm x 1.20 mm thick at maximum 2'-0" c/c bothways etc. complete as directed. Only front elevation surface area shall be measured for payment. P/A WALL PAPERS on Digital wall Providing and applying Wall paper approved by Architect / Bank's Engineer having basic price of Rs 100=00 Per Sq.Ft 21 ALUMINUM COMPOSITE PANEL FOR E-LOBBY Providing and fixing 3 mm thick aluminium composite panel of Flexi Bond / Euro Bond / Timex with 0.25 mm foil with 50 mm x 25 mm x 1.20 mm thick aluminium hollow section tray system with minimum 20 mm bending with silicon Dow Coming of GE seal proof - ACP of approved indian make complete as per selection and direction of Architect for front facade for the building. This item will be carried out as per manufacturer's specifications. Rate also includes providing trap door shutter with hinges, stoppers etc complete as directed. Design as per Bank standered Drawing and Architect's instructions etc complete. TIMEX - DIAMOND WHITE - 111, NAVY BLUE - 117 or						
mm thick laminate or paint before laying 3M film. Only Front elevation area shall be measured for payment purpose. Exposed edges of Display wall four side shall be made 36 mm thick by providing additional required thickness MDF patta of required width. Panelling for Digital wall with Blue / white high gloss PU Coating finishing Providing and laying panelling on wall having 8mm th MDF Board exterior grade with PU coating fixed on wall with Aluminium framing of 25mm x 25mm x 1.20 mm thick at maximum 2'-0" c/c bothways etc. complete as directed. Only front elevation surface area shall be measured for payment. P/A WALL PAPERS on Digital wall Providing and applying Wall paper approved by Architect / Bank's Engineer having basic price of Rs 100=00 Per Sq.Ft 21 ALUMINUM COMPOSITE PANEL FOR E-LOBBY Providing and fixing 3 mm thick aluminium composite panel of Flexi Bond / Euro Bond / Timex with 0.25 mm foil with 50 mm x 25 mm x 1.20 mm thick aluminium hollow section tray system with minimum 20 mm bending with silicon Dow Coming of GE seal proof - ACP of approved indian make complete as per selection and direction of Architect for front facade for the building. This item will be carried out as per manufacturer's specifications. Rate also includes providing tray door shutter with hinges, stoppers etc complete as directed. Design as per Bank standered Drawing and Architect's instructions etc complete. TIMEX - DIAMOND WHITE - 111, NAVY BLUE - 117 or						
Exposed edges of Display wall four side shall be made 36 mm thick by providing additional required thickness MDF patta of required width. 19 Panelling for Digital wall with Blue / white high gloss PU Coating finishing 4.50 SQMT Providing and laying panelling on wall having 8mm th MDF Board exterior grade with PU coating fixed on wall with Aluminium framing of 25mm x 25mm x 1.20 mm thick at maximum 2'-0" c/c bothways etc. complete as directed. Only front elevation surface area shall be measured for payment. P/A WALL PAPERS on Digital wall Providing and applying Wall paper approved by Architect / Bank's Engineer having basic price of Rs 100=00 Per Sq.Ft 21 ALUMINUM COMPOSITE PANEL FOR E-LOBBY Providing and fixing 3 mm thick aluminium composite panel of Flexi Bond / Euro Bond / Timex with 0.25 mm foil with 50 mm x 25 mm x 1.20 mm thick aluminium hollow section tray system with minimum 20 mm bending with silicon Dow Coming of GE seal proof - ACP of approved indian make complete as per selection and direction of Architect for front facade for the building. This item will be carried out as per manufacturer's specifications. Rate also includes providing tray door shutter with hinges, stoppers etc complete as directed. Design as per Bank standered Drawing and Architect's instructions etc complete. TIMEX - DIAMOND WHITE - 111, NAVY BLUE - 117 or						
additional required thickness MDF patta of required width. 19 Panelling for Digital wall with Blue / white high gloss PU Coating finishing 4.50 SQMT Providing and laying panelling on wall having 8mm th MDF Board exterior grade with PU coating fixed on wall with Aluminium framing of 25mm x 25mm x 1.20 mm thick at maximum 2'-0" c/c bothways etc. complete as directed. Only front elevation surface area shall be measured for payment. P/A WALL PAPERS on Digital wall Providing and applying Wall paper approved by Architect / Bank's Engineer having basic price of Rs 100=00 Per Sq.Ft 21 ALUMINUM COMPOSITE PANEL FOR E-LOBBY Providing and fixing 3 mm thick aluminium composite panel of Flexi Bond / Euro Bond / Timex with 0.25 mm foil with 50 mm x 25 mm x 1.20 mm thick aluminium hollow section tray system with minimum 20 mm bending with silicon Dow Coming of GE seal proof - ACP of approved indian make complete as per selection and direction of Architect for front facade for the building. This item will be carried out as per manufacturer's specifications. Rate also includes providing trap door shutter with hinges, stoppers etc complete as directed. Design as per Bank standered Drawing and Architect's instructions etc complete. TIMEX - DIAMOND WHITE - 111, NAVY BLUE - 117 or						
Providing and laying panelling on wall having 8mm th MDF Board exterior grade with PU coating fixed on wall with Aluminium framing of 25mm x 25mm x 1.20 mm thick at maximum 2'-0" c/c bothways etc. complete as directed. Only front elevation surface area shall be measured for payment. P/A WALL PAPERS on Digital wall Providing and applying Wall paper approved by Architect / Bank's Engineer having basic price of Rs 100=00 Per Sq.Ft 21 ALUMINUM COMPOSITE PANEL FOR E-LOBBY Providing and fixing 3 mm thick aluminium composite panel of Flexi Bond / Euro Bond / Timex with 0.25 mm foil with 50 mm x 25 mm x 1.20 mm thick aluminium hollow section tray system with minimum 20 mm bending with silicon Dow Coming of GE seal proof - ACP of approved indian make complete as per selection and direction of Architect for front facade for the building. This item will be carried out as per manufacturer's specifications. Rate also includes providing trap door shutter with hinges, stoppers etc complete as directed. Design as per Bank standered Drawing and Architect's instructions etc complete. TIMEX - DIAMOND WHITE - 111, NAVY BLUE - 117 or						
Providing and laying panelling on wall having 8mm th MDF Board exterior grade with PU coating fixed on wall with Aluminium framing of 25mm x 25mm x 1.20 mm thick at maximum 2'-0" c/c bothways etc. complete as directed. Only front elevation surface area shall be measured for payment. P/A WALL PAPERS on Digital wall Providing and applying Wall paper approved by Architect / Bank's Engineer having basic price of Rs 100=00 Per Sq.Ft 21 ALUMINUM COMPOSITE PANEL FOR E-LOBBY Providing and fixing 3 mm thick aluminium composite panel of Flexi Bond / Euro Bond / Timex with 0.25 mm foil with 50 mm x 25 mm x 1.20 mm thick aluminium hollow section tray system with minimum 20 mm bending with silicon Dow Coming of GE seal proof - ACP of approved indian make complete as per selection and direction of Architect for front facade for the building. This item will be carried out as per manufacturer's specifications. Rate also includes providing trap door shutter with hinges, stoppers etc complete as directed. Design as per Bank standered Drawing and Architect's instructions etc complete. TIMEX - DIAMOND WHITE - 111, NAVY BLUE - 117 or	1			00117		
PU coating fixed on wall with Aluminium framing of 25mm x 25mm x 1.20 mm thick at maximum 2'-0" c/c bothways etc. complete as directed. Only front elevation surface area shall be measured for payment. P/A WALL PAPERS on Digital wall 20 Providing and applying Wall paper approved by Architect / Bank's Engineer having basic price of Rs 100=00 Per Sq.Ft 21 ALUMINUM COMPOSITE PANEL FOR E-LOBBY Providing and fixing 3 mm thick aluminium composite panel of Flexi Bond / Euro Bond / Timex with 0.25 mm foil with 50 mm x 25 mm x 1.20 mm thick aluminium hollow section tray system with minimum 20 mm bending with silicon Dow Coming of GE seal proof - ACP of approved indian make complete as per selection and direction of Architect for front facade for the building. This item will be carried out as per manufacturer's specifications. Rate also includes providing trap door shutter with hinges, stoppers etc complete as directed. Design as per Bank standered Drawing and Architect's instructions etc complete. TIMEX - DIAMOND WHITE - 111, NAVY BLUE - 117 or	19		4.50	SQMT		
maximum 2'-0" c/c bothways etc. complete as directed. Only front elevation surface area shall be measured for payment. P/A WALL PAPERS on Digital wall 20 Providing and applying Wall paper approved by Architect / Bank's Engineer having basic price of Rs 100=00 Per Sq.Ft 21 ALUMINUM COMPOSITE PANEL FOR E-LOBBY Providing and fixing 3 mm thick aluminium composite panel of Flexi Bond / Euro Bond / Timex with 0.25 mm foil with 50 mm x 25 mm x 1.20 mm thick aluminium hollow section tray system with minimum 20 mm bending with silicon Dow Coming of GE seal proof - ACP of approved indian make complete as per selection and direction of Architect for front facade for the building. This item will be carried out as per manufacturer's specifications. Rate also includes providing trap door shutter with hinges, stoppers etc complete as directed. Design as per Bank standered Drawing and Architect's instructions etc complete. TIMEX - DIAMOND WHITE - 111, NAVY BLUE - 117 or						
area shall be measured for payment. P/A WALL PAPERS on Digital wall Providing and applying Wall paper approved by Architect / Bank's Engineer having basic price of Rs 100=00 Per Sq.Ft 21 ALUMINUM COMPOSITE PANEL FOR E-LOBBY Providing and fixing 3 mm thick aluminium composite panel of Flexi Bond / Euro Bond / Timex with 0.25 mm foil with 50 mm x 25 mm x 1.20 mm thick aluminium hollow section tray system with minimum 20 mm bending with silicon Dow Coming of GE seal proof - ACP of approved indian make complete as per selection and direction of Architect for front facade for the building. This item will be carried out as per manufacturer's specifications. Rate also includes providing trap door shutter with hinges, stoppers etc complete as directed. Design as per Bank standered Drawing and Architect's instructions etc complete. TIMEX - DIAMOND WHITE - 111, NAVY BLUE - 117 or						
P/A WALL PAPERS on Digital wall Providing and applying Wall paper approved by Architect / Bank's Engineer having basic price of Rs 100=00 Per Sq.Ft 21 ALUMINUM COMPOSITE PANEL FOR E-LOBBY Providing and fixing 3 mm thick aluminium composite panel of Flexi Bond / Euro Bond / Timex with 0.25 mm foil with 50 mm x 25 mm x 1.20 mm thick aluminium holws ection tray system with minimum 20 mm bending with silicon Dow Coming of GE seal proof - ACP of approved indian make complete as per selection and direction of Architect for front facade for the building. This item will be carried out as per manufacturer's specifications. Rate also includes providing trap door shutter with hinges, stoppers etc complete as directed. Design as per Bank standered Drawing and Architect's instructions etc complete. TIMEX - DIAMOND WHITE - 111, NAVY BLUE - 117 or						
Providing and applying Wall paper approved by Architect / Bank's Engineer having basic price of Rs 100=00 Per Sq.Ft 21 ALUMINUM COMPOSITE PANEL FOR E-LOBBY Providing and fixing 3 mm thick aluminium composite panel of Flexi Bond / Euro Bond / Timex with 0.25 mm foil with 50 mm x 25 mm x 1.20 mm thick aluminium hollow section tray system with minimum 20 mm bending with silicon Dow Coming of GE seal proof - ACP of approved indian make complete as per selection and direction of Architect for front facade for the building. This item will be carried out as per manufacturer's specifications. Rate also includes providing trap door shutter with hinges, stoppers etc complete as directed. Design as per Bank standered Drawing and Architect's instructions etc complete. TIMEX - DIAMOND WHITE - 111, NAVY BLUE - 117 or						
21 ALUMINUM COMPOSITE PANEL FOR E-LOBBY Providing and fixing 3 mm thick aluminium composite panel of Flexi Bond / Euro Bond / Timex with 0.25 mm foil with 50 mm x 25 mm x 1.20 mm thick aluminium hollow section tray system with minimum 20 mm bending with silicon Dow Coming of GE seal proof - ACP of approved indian make complete as per selection and direction of Architect for front facade for the building. This item will be carried out as per manufacturer's specifications. Rate also includes providing trap door shutter with hinges, stoppers etc complete as directed. Design as per Bank standered Drawing and Architect's instructions etc complete. TIMEX - DIAMOND WHITE - 111, NAVY BLUE - 117 or	20	Providing and applying Wall paper approved by Architect / Bank's Engineer having	6.00	SQMT		
Providing and fixing 3 mm thick aluminium composite panel of Flexi Bond / Euro Bond / Timex with 0.25 mm foil with 50 mm x 25 mm x 1.20 mm thick aluminium hollow section tray system with minimum 20 mm bending with silicon Dow Coming of GE seal proof - ACP of approved indian make complete as per selection and direction of Architect for front facade for the building. This item will be carried out as per manufacturer's specifications. Rate also includes providing trap door shutter with hinges, stoppers etc complete as directed. Design as per Bank standered Drawing and Architect's instructions etc complete. TIMEX - DIAMOND WHITE - 111, NAVY BLUE - 117 or	- 04		F0 00	COLAT		
Timex with 0.25 mm foil with 50 mm x 25 mm x 1.20 mm thick aluminium hollow section tray system with minimum 20 mm bending with silicon Dow Coming of GE seal proof - ACP of approved indian make complete as per selection and direction of Architect for front facade for the building. This item will be carried out as per manufacturer's specifications. Rate also includes providing trap door shutter with hinges, stoppers etc complete as directed. Design as per Bank standered Drawing and Architect's instructions etc complete. TIMEX - DIAMOND WHITE - 111, NAVY BLUE - 117 or	21		56.00	SUMI		<u> </u>
tray system with minimum 20 mm bending with silicon Dow Coming of GE seal proof - ACP of approved indian make complete as per selection and direction of Architect for front facade for the building. This item will be carried out as per manufacturer's specifications. Rate also includes providing trap door shutter with hinges, stoppers etc complete as directed. Design as per Bank standered Drawing and Architect's instructions etc complete. TIMEX - DIAMOND WHITE - 111, NAVY BLUE - 117 or						
front facade for the building. This item will be carried out as per manufacturer's specifications. Rate also includes providing trap door shutter with hinges, stoppers etc complete as directed. Design as per Bank standered Drawing and Architect's instructions etc complete. TIMEX - DIAMOND WHITE - 111, NAVY BLUE - 117 or						
specifications. Rate also includes providing trap door shutter with hinges, stoppers etc complete as directed. Design as per Bank standered Drawing and Architect's instructions etc complete. TIMEX - DIAMOND WHITE - 111, NAVY BLUE - 117 or						
complete as directed. Design as per Bank standered Drawing and Architect's instructions etc complete. TIMEX - DIAMOND WHITE - 111, NAVY BLUE - 117 or						
instructions etc complete. TIMEX - DIAMOND WHITE - 111, NAVY BLUE - 117 or						

Providing and fixing Gypsum board 12.50 mm thick false ceiling in steps and design using Original Indian Gypsum board with original GI sheet section of Gypsteel ULTRA (Gypsteel Ultra shall be used) supporting system in line and level. Finishing the surface and applying 3 coats of Plastic emulsion paint as directed complete. Entire work to be done as per standard specifications of Saint Gobin Gyproc India. After completion of work, certificate from Saint Gobin Gyproc Company shall be submitted along with bill stating that work is satisfactorily completed as per their specification. Note: (1) Rate includes making necessary cut-outs for lighting fixtures (2) Pattas if any shall be measured in SqM and not in RMt and paid in SqM (3) Only finished visible surface area shall be measured for payment. Providing and Fixing of Armstrong Mineral Fibre Accoustical Suspended ceilling system with FINE FISSURED (MICRO LOCK) EDGE TILES With Armstrong Silhouette Exposed Grid Using Silhouette Grid with Fine Fissured microlook Edge Tiles. With necessary Angles at junctions as per company specifications as directed complete. Rate includes necessary cut outs for AC Grills, diffusers light fixtures complete as directed. Cutout for light and Diffusers will be deducted from area. Only Tiles cost will be deducted for payment purpose. After completion of work, certificate from Company to be obtained and submitted with bill that work is carried out as per their specifications. VII SOFT BOARD Providing & fixing soft board for pin up using moulded Steam beach frame of 1" x 1/2" with 6 mm thick commercial plywood on back side and 12mm th soft board on front covered with cloth of selected design of Basic rate of Rs. 150 per Rmt. Steam beach member shall have lacquer polish as directed. VIII ROLLER BLINDS Supplying and fixing Roller Blind Blackout of approved make with selected fabric of approved design and shade. (Basic Price of Rs 135=00 Per Sq.Ft Excluding GST) 16.00 SQMT Froviding and Fixing Frosted polyster film of 3M (Scotch	Amount
Providing and fixing Gypsum board 12.50 mm thick false ceiling in steps and design using Original Indian Gypsum board 21.50 mm thick false ceiling in steps and design using Original Indian Gypsum board with original GI sheet section of Gypsteel ULTRA (Gypsteel Ultra shall be used) supporting system in line and level. Finishing the surface and applying 3 coats of Plastic emulsion paint as directed complete. Entire work to be done as per standard specifications of Saint Gobin Gyproc India. After completion of work, certificate from Saint Gobian Gyproc Company shall be submitted along with bill stating that work is satisfactorily completed as per their specification. Note: (1) Rate includes making necessary cut-outs for lighting fixtures (2) Pattas if any shall be measured in SqM and not in RMt and paid in SqM (3) Only finished visible surface area shall be measured for payment. Providing and Fixing of Armstrong Mineral Fibre Accoustical Suspended ceilling system with FiNE FISSURED (MICRO LOCK) EDGE TILES With Armstrong Silhouette Exposed Grid Using Silhouette Grid with Fine Fissured microlook Edge Tiles. With necessary Angles at junctions as per company specifications as directed complete. Rate includes necessary cut outs for A/C Grills, diffusers light fixtures complete as directed. Cutout for light and Diffusers will be deducted from area. Only Tiles cost will be deducted for payment purpose. After completion of work, certificate from Company to be obtained and submitted with bill that work is carried out as per their specifications. VII SOFT BOARD Providing & fixing soft board for pin up using moulded Steam beach frame of 1" x 1/2" with 6 mm thick commercial plywood on back side and 12mm th soft board on front covered with cloth of selected design of Basic rate of Rs. 150 per Rmt. Steam beach member shall have lacquer polish as directed. VII ROLLER BINDS Supplying and fixing Roller Bilind Blackout of approved make with selected fabric of approved design and shade. (Basic Price of Rs 135=00 Per Sq.F	
Providing and fixing Gypsum board 12.50 mm thick false ceiling in steps and design using Original Indian Gypsum board with original GI sheet section of Gypsteel ULtra Shall be used) supporting system in line and level. Finishing the surface and applying 3 coats of Plastic emulsion paint as directed complete. Entire work to be done as per standard specifications of Saint Gobin Gyproc Company shall be submitted along with bill stating that work is satisfactorily completed as per their specification. Note: (1) Rate includes making necessary cut-outs for lighting fixtures (2) Pattas if any shall be measured in SqM and not in RM and paid in SqM (3) Only finished visible surface area shall be measured for payment. Providing and Fixing of Armstrong Mineral Fibre Accoustical Suspended ceilling system with FINE FISSURED (MICRO LOCK) EDGE TILES With Armstrong Silhouette Exposed Grid Using Silhouette Grid with Fine Fissured microlook Edge Tiles. With necessary Angles at junctions as per company specifications as directed complete. Rate includes necessary cut outs for A/C Grills, diffusers light fixtures complete as directed. Cutout for light and Diffusers will be deducted from area. Only Tiles cost will be deducted for payment purpose. After completion of work, certificate from Company to be obtained and submitted with bill that work is carried out as per their specifications. VII SOFT BOARD Providing & fixing soft board for pin up using moulded Steam beach frame of 1" x 1/2" with 6 mm thick commercial plywood on back side and 12mm th soft board on front covered with cloth of selected design of Basic rate of Rs. 150 per Rmt. Steam beach member shall have lacquer polish as directed. VIII ROLLER BLINDS Supplying and fixing Roller Blind Blackout of approved make with selected fabric of approved design and shade. (Basic Price of Rs 135=00 Per Sq.Ft Excluding GST) 16.00 SQMT EXPOSTED FILM Providing and Fixing Frosted polyster film of 3M (Scotchcal 7725 - 324) or equivalent make over glass surface as per drawing & d	
using Original Indian Gypsum board with original GI sheet section of Gypsteel ULTRA (Gypsteel Ultra shall be used) supporting system in line and level. Finishing the surface and applying 3 coats of Plastic emulsion paint as directed complete. Entire work to be done as per standard specifications of Saint Gobin Gyproc India. After completion of work, certificate from Saint Gobin Gyproc Company shall be submitted along with bill stating that work is satisfactorily completed as per their specification. Note: (1) Rate includes making necessary cut-outs for lighting fixtures (2) Pattas if any shall be measured in SqM and not in RMt and paid in SqM (3) Only finished visible surface area shall be measured for payment. Providing and Fixing of Armstrong Mineral Fibre Accoustical Suspended ceilling system with FINE FISSURED (MICRO LOCK) EDGE TILES With Armstrong Silhouette Exposed Grid Using Silhouette Grid with Fine Fissured microlook Edge Tiles. With necessary Angles at junctions as per company specifications as directed complete. Rate includes necessary cut outs for A/C Grills, diffusers light fixtures complete as directed. Cutout for light and Diffusers will be deducted from area. Only Tiles cost will be deducted for payment purpose. After completion of work, certificate from Company to be obtained and submitted with bill that work is carried out as per their specifications. VII SOFT BOARD Providing & fixing soft board for pin up using moulded Steam beach frame of 1" x 1/2" with 6 mm thick commercial plywood on back side and 12mm th soft board on front covered with cloth of selected design of Basic rate of Rs. 150 per Rmt. Steam beach member shall have lacquer polish as directed. VIII ROLLER BLINDS Supplying and fixing Roller Blind Blackout of approved make with selected fabric of approved design and shade. (Basic Price of Rs 135=00 Per Sq.Ft Excluding GST) 10.00 SQMT FROSTED FILM Providing and Fixing Frosted polyster film of 3M (Scotchcal 7725 - 324) or equivalent make over glass surface as per drawin	
(Gypsteel Ultra shall be used) supporting system in line and level. Finishing the surface and applying 3 coats of Plastic emulsion paint as directed complete. Entire work to be done as per standard specifications of Saint Gobin Gyproc India. After completion of work, certificate from Saint Gobin Gyproc Company shall be submitted along with bill stating that work is satisfactorily completed as per their specification. Note: (1) Rate includes making necessary cut-outs for lighting fixtures (2) Pattas if any shall be measured in SqM and not in RMt and paid in SqM (3) only finished visible surface area shall be measured for payment. Providing and Fixing of Armstrong Mineral Fibre Accoustical Suspended ceilling system with FINE FISSURED (MICRO LOCK) EDGE TILES With Armstrong Silhouette Exposed Grid Using Silhouette Grid with Fine Fissured microlook Edge Tiles. With necessary Angles at junctions as per company specifications as directed complete. Rate includes necessary cut outs for A/C Grills, diffusers light fixtures complete. Rate includes necessary cut outs for A/C Grills, diffusers light fixtures complete. Rate includes necessary cut over the propose. After completion of work, certificate from Company to be obtained and submitted with bill that work is carried out as per their specifications. VII SOFT BOARD Providing & fixing soft board for pin up using moulded Steam beach frame of 1" x 1/2" with 6 mm thick commercial plywood on back side and 12mm th soft board on front covered with cloth of selected design of Basic rate of Rs. 150 per Rmt. Steam beach member shall have lacquer polish as directed. VIII ROLLER BLINDS Supplying and fixing Roller Blind Blackout of approved make with selected fabric of approved design and shade. (Basic Price of Rs 135=00 Per Sq.Ft Excluding GST) 16.00 SQMT EXPROSTED FILM Providing and Fixing Frosted polyster film of 3M (Scotchcal 7725 - 324) or equivalent make over glass surface as per drawing & direction with all labour & materials to the satisfaction of the Architect	
work to be done as per standard specifications of Saint Gobin Gyproc India. After completion of work, certificate from Saint Gobaln Gyproc Company shall be submitted along with bill stating that work is satisfactorily completed as per their specification. Note: (1) Rate includes making necessary cut-outs for lighting fixtures (2) Pattas if any shall be measured in SqM and not in RMt and paid in SqM (3) Only finished visible surface area shall be measured for payment. Providing and Fixing of Armstrong Mineral Fibre Accoustical Suspended ceilling system with FINE FISSURED (MICRO LOCK) EDGE TILES With Armstrong Silhouette Exposed Grid Using Silhouette Grid with Fine Fissured microlook Edge Tiles. With necessary Angles at junctions as per company specifications as directed complete. Rate includes necessary cut outs for AIC Grills, diffusers light fixtures complete as directed. Cutout for light and Diffusers will be deducted from area. Only Tiles cost will be deducted for payment purpose. After completion of work, certificate from Company to be obtained and submitted with bill that work is carried out as per their specifications. VII SOFT BOARD Providing & fixing soft board for pin up using moulded Steam beach frame of 1" x 1/2" with 6 mm thick commercial plywood on back side and 12mm th soft board on front covered with cloth of selected design of Basic rate of Rs. 150 per Rmt. Steam beach member shall have lacquer polish as directed. VIII ROLLER BLINDS Supplying and fixing Roller Blind Blackout of approved make with selected fabric of approved design and shade. (Basic Price of Rs 135=00 Per Sq.Ft Excluding GST) 1.00 SQMT Providing and Fixing Frosted polyster film of 3M (Scotchcal 7725 - 324) or equivalent make over glass surface as per drawing & direction with all labour & materials to the satisfaction of the Architect/Bank as per manufacturer's specification. No deduction will	
After completion of work, certificate from Saint Gobain Gyproc Company shall be submitted along with bill stating that work is satisfactorily completed as per their specification. Note: (1) Rate includes making necessary cut-outs for lighting fixtures (2) Pattas if any shall be measured in SqM and not in RMt and paid in SqM (3) Only finished visible surface area shall be measured for payment. Providing and Fixing of Armstrong Mineral Fibre Accoustical Suspended ceilling system with FINE FISSURED (MICRO LOCK) EDGE TILES With Armstrong Silhouette Exposed Grid Using Silhouette Grid with Fine Fissured microlook Edge Tiles. With necessary Angles at junctions as per company specifications as directed complete. Rate includes necessary cut outs for A/C Grills, diffusers light fixtures complete as directed. Cutout for light and Diffusers will be deducted from area. Only Tiles cost will be deducted for payment purpose. After completion of work, certificate from Company to be obtained and submitted with bill that work is carried out as per their specifications. JII SOFT BOARD Providing & fixing soft board for pin up using moulded Steam beach frame of 1" x 1/2" with 6 mm thick commercial plywood on back side and 12mm th soft board on front covered with cloth of selected design of Basic rate of Rs. 150 per Rmt. Steam beach member shall have lacquer polish as directed. JIII ROLLER BLINDS Supplying and fixing Roller Blind Blackout of approved make with selected fabric of approved design and shade. (Basic Price of Rs 135=00 Per Sq.Ft Excluding GST) K FROSTED FILM Providing and Fixing Frosted polyster film of 3M (Scotchcal 7725 - 324) or equivalent make over glass surface as per drawing & direction with all labour & materials to the satisfaction of the Architect/Bank as per manufacturer's specification. No deduction will	
be submitted along with bill stating that work is satisfactorily completed as per their specification. Note: (1) Rate includes making necessary cut-outs for lighting fixtures (2) Pattas if any shall be measured in SqM and not in RMt and paid in SqM (3) Only finished visible surface area shall be measured for payment. Providing and Fixing of Armstrong Mineral Fibre Accoustical Suspended ceilling system with FINE FISSURED (MICRO LOCK) EDGE TILES With Armstrong Silhouette Exposed Grid Using Silhouette Grid with Fine Fissured microlook Edge Tiles. With necessary Angles at junctions as per company specifications as directed complete. Rate includes necessary cut outs for A/C Grills, diffusers light fixtures complete as directed. 50.00 SMT Cutout for light and Diffusers will be deducted from area. Only Tiles cost will be deducted for payment purpose. After completion of work, certificate from Company to be obtained and submitted with bill that work is carried out as per their specifications. //II SOFT BOARD Providing & fixing soft board for pin up using moulded Steam beach frame of 1" x 1/2" with 6 mm thick commercial plywood on back side and 12mm th soft board on front covered with cloth of selected design of Basic rate of Rs. 150 per Rmt. Steam beach member shall have lacquer polish as directed. //III ROLLER BLINDS Supplying and fixing Roller Blind Blackout of approved make with selected fabric of approved design and shade. (Basic Price of Rs 135=00 Per Sq.Ft Excluding GST) 16.00 SQMT **TROSTED FILM** Providing and Fixing Frosted polyster film of 3M (Scotchcal 7725 - 324) or equivalent make over glass surface as per drawing & direction with all labour & materials to the satisfaction of the Architect/Bank as per manufacturer's specification. No deduction will	
Per their specification. Note: (1) Rate includes making necessary cut-outs for lighting fixtures (2) Pattas if any shall be measured in SqM and not in RMt and paid in SqM (3) Only finished visible surface area shall be measured for payment. Providing and Fixing of Armstrong Mineral Fibre Accoustical Suspended ceilling system with FINE FISSURED (MICRO LOCK) EDGE TILES With Armstrong Silhouette Exposed Grid Using Silhouette Grid with Fine Fissured microlook Edge Tiles. With necessary Angles at junctions as per company specifications as directed complete. Rate includes necessary cut outs for A/C Grills, diffusers light fixtures complete as directed. Cutout for light and Diffusers will be deducted from area. Only Tiles cost will be deducted for payment purpose. After completion of work, certificate from Company to be obtained and submitted with bill that work is carried out as per their specifications. //II SOFT BOARD Providing & fixing soft board for pin up using moulded Steam beach frame of 1" x 1/2" with 6 mm thick commercial plywood on back side and 12mm th soft board on front covered with cloth of selected design of Basic rate of Rs. 150 per Rmt. Steam beach member shall have lacquer polish as directed. //III ROLLER BLINDS Supplying and fixing Roller Blind Blackout of approved make with selected fabric of approved design and shade. (Basic Price of Rs 135=00 Per Sq.Ft Excluding GST) IK PROSTED FILM Providing and Fixing Frosted polyster film of 3M (Scotchcal 7725 - 324) or equivalent make over glass surface as per drawing & direction with all labour & materials to the satisfaction of the Architect/Bank as per manufacturer's specification. No deduction will	
Note: (1) Rate includes making necessary cut-outs for lighting fixtures (2) Pattas if any shall be measured in SqM and not in RMt and paid in SqM (3) Only finished visible surface area shall be measured for payment. Providing and Fixing of Armstrong Mineral Fibre Accoustical Suspended ceilling system with FINE FISSURED (MICRO LOCK) EDGE TILES With Armstrong Silhouette Exposed Grid Using Silhouette Grid with Fine Fissured microlook Edge Tiles. With necessary Angles at junctions as per company specifications as directed complete. Rate includes necessary cut outs for A/C Grills, diffusers light fixtures complete as directed. Cutout for light and Diffusers will be deducted from area. Only Tiles cost will be deducted for payment purpose. After completion of work, certificate from Company to be obtained and submitted with bill that work is carried out as per their specifications. //II SOFT BOARD Providing & fixing soft board for pin up using moulded Steam beach frame of 1" x 1/2" with 6 mm thick commercial plywood on back side and 12mm th soft board on front covered with cloth of selected design of Basic rate of Rs. 150 per Rmt. Steam beach member shall have lacquer polish as directed. //III ROLLER BLINDS Supplying and fixing Roller Blind Blackout of approved make with selected fabric of approved design and shade. (Basic Price of Rs 135=00 Per Sq.Ft Excluding GST) IX FROSTED FILM Providing and Fixing Frosted polyster film of 3M (Scotchcal 7725 - 324) or equivalent make over glass surface as per drawing & direction with all labour & materials to the satisfaction of the Architect/Bank as per manufacturer's specification. No deduction will	
(2) Pattas if any shall be measured in SqM and not in RMt and paid in SqM (3) Only finished visible surface area shall be measured for payment. Providing and Fixing of Armstrong Mineral Fibre Accoustical Suspended ceilling system with FINE FISSURED (MICRO LOCK) EDGE TILES With Armstrong Silhouette Exposed Grid Using Silhouette Grid with Fine Fissured microlook Edge Tiles. With necessary Angles at junctions as per company specifications as directed complete. Rate includes necessary cut outs for A/C Grills, diffusers light fixtures complete as directed. Cutout for light and Diffusers will be deducted from area. Only Tiles cost will be deducted for payment purpose. After completion of work, certificate from Company to be obtained and submitted with bill that work is carried out as per their specifications. VII SOFT BOARD Providing & fixing soft board for pin up using moulded Steam beach frame of 1" x 1/2" with 6 mm thick commercial plywood on back side and 12mm th soft board on front covered with cloth of selected design of Basic rate of Rs. 150 per Rmt. Steam beach member shall have lacquer polish as directed. IN ROLLER BLINDS Supplying and fixing Roller Blind Blackout of approved make with selected fabric of approved design and shade. (Basic Price of Rs 135=00 Per Sq.Ft Excluding GST) IX FROSTED FILM Providing and Fixing Frosted polyster film of 3M (Scotchcal 7725 - 324) or equivalent make over glass surface as per drawing & direction with all labour & materials to the satisfaction of the Architect/Bank as per manufacturer's specification. No deduction will	
(2) Pattas if any shall be measured in SqM and not in RMt and paid in SqM (3) Only finished visible surface area shall be measured for payment. Providing and Fixing of Armstrong Mineral Fibre Accoustical Suspended ceilling system with FINE FISSURED (MICRO LOCK) EDGE TILES With Armstrong Silhouette Exposed Grid Using Silhouette Grid with Fine Fissured microlook Edge Tiles. With necessary Angles at junctions as per company specifications as directed complete. Rate includes necessary cut outs for A/C Grills, diffusers light fixtures complete as directed. Cutout for light and Diffusers will be deducted from area. Only Tiles cost will be deducted for payment purpose. After completion of work, certificate from Company to be obtained and submitted with bill that work is carried out as per their specifications. VII SOFT BOARD Providing & fixing soft board for pin up using moulded Steam beach frame of 1" x 1/2" with 6 mm thick commercial plywood on back side and 12mm th soft board on front covered with cloth of selected design of Basic rate of Rs. 150 per Rmt. Steam beach member shall have lacquer polish as directed. VIII ROLLER BLINDS SQMT SQMT Providing and fixing Roller Blind Blackout of approved make with selected fabric of approved design and shade. (Basic Price of Rs 135=00 Per Sq.Ft Excluding GST) 16.00 SQMT IX FROSTED FILM Providing and Fixing Frosted polyster film of 3M (Scotchcal 7725 - 324) or equivalent make over glass surface as per drawing & direction with all labour & materials to the satisfaction of the Architect/Bank as per manufacturer's specification. No deduction will	
(3) Only finished visible surface area shall be measured for payment. Providing and Fixing of Armstrong Mineral Fibre Accoustical Suspended ceilling system with FINE FISSURED (MICRO LOCK) EDGE TILES With Armstrong Silhouette Exposed Grid Using Silhouette Grid with Fine Fissured microlook Edge Tiles. With necessary Angles at junctions as per company specifications as directed complete. Rate includes necessary cut outs for A/C Grills, diffusers light fixtures complete as directed. Cutout for light and Diffusers will be deducted from area. Only Tiles cost will be deducted for payment purpose. After completion of work, certificate from Company to be obtained and submitted with bill that work is carried out as per their specifications. //II SOFT BOARD Providing & fixing soft board for pin up using moulded Steam beach frame of 1" x 1/2" with 6 mm thick commercial plywood on back side and 12mm th soft board on front covered with cloth of selected design of Basic rate of Rs. 150 per Rmt. Steam beach member shall have lacquer polish as directed. //III ROLLER BLINDS Supplying and fixing Roller Blind Blackout of approved make with selected fabric of approved design and shade. (Basic Price of Rs 135=00 Per Sq.Ft Excluding GST) IK FROSTED FILM Providing and Fixing Frosted polyster film of 3M (Scotchcal 7725 - 324) or equivalent make over glass surface as per drawing & direction with all labour & materials to the satisfaction of the Architect/Bank as per manufacturer's specification. No deduction will	
Providing and Fixing of Armstrong Mineral Fibre Accoustical Suspended ceilling system with FINE FISSURED (MICRO LOCK) EDGE TILES With Armstrong Silhouette Exposed Grid Using Silhouette Grid with Fine Fissured microlook Edge Tiles. With necessary Angles at junctions as per company specifications as directed complete. Rate includes necessary cut outs for A/C Grills, diffusers light fixtures complete as directed. Cutout for light and Diffusers will be deducted from area. Only Tiles cost will be deducted for payment purpose. After completion of work, certificate from Company to be obtained and submitted with bill that work is carried out as per their specifications. VII SOFT BOARD Providing & fixing soft board for pin up using moulded Steam beach frame of 1" x 1/2" with 6 mm thick commercial plywood on back side and 12mm th soft board on front covered with cloth of selected design of Basic rate of Rs. 150 per Rmt. Steam beach member shall have lacquer polish as directed. VIII ROLLER BLINDS Supplying and fixing Roller Blind Blackout of approved make with selected fabric of approved design and shade. (Basic Price of Rs 135=00 Per Sq.Ft Excluding GST) IX FROSTED FILM Providing and Fixing Frosted polyster film of 3M (Scotchcal 7725 - 324) or equivalent make over glass surface as per drawing & direction with all labour & materials to the satisfaction of the Architect/Bank as per manufacturer's specification. No deduction will	
with FINE FISSURED (MICRO LOCK) EDGE TILES With Armstrong Silhouette Exposed Grid Using Silhouette Grid with Fine Fissured microlook Edge Tiles. With necessary Angles at junctions as per company specifications as directed complete. Rate includes necessary cut outs for A/C Grills, diffusers light fixtures complete as directed. Cutout for light and Diffusers will be deducted from area. Only Tiles cost will be deducted for payment purpose. After completion of work, certificate from Company to be obtained and submitted with bill that work is carried out as per their specifications. VII SOFT BOARD Providing & fixing soft board for pin up using moulded Steam beach frame of 1" x 1/2" with 6 mm thick commercial plywood on back side and 12mm th soft board on front covered with cloth of selected design of Basic rate of Rs. 150 per Rmt. Steam beach member shall have lacquer polish as directed. VIII ROLLER BLINDS Supplying and fixing Roller Blind Blackout of approved make with selected fabric of approved design and shade. (Basic Price of Rs 135=00 Per Sq.Ft Excluding GST) 16.00 SQMT FROSTED FILM Providing and Fixing Frosted polyster film of 3M (Scotchcal 7725 - 324) or equivalent make over glass surface as per drawing & direction with all labour & materials to the satisfaction of the Architect/Bank as per manufacturer's specification. No deduction will	
Exposed Grid Using Silhouette Grid with Fine Fissured microlook Edge Tiles. With necessary Angles at junctions as per company specifications as directed complete. Rate includes necessary cut outs for A/C Grills, diffusers light fixtures complete as directed. Cutout for light and Diffusers will be deducted from area. Only Tiles cost will be deducted for payment purpose. After completion of work, certificate from Company to be obtained and submitted with bill that work is carried out as per their specifications. VII SOFT BOARD Providing & fixing soft board for pin up using moulded Steam beach frame of 1" x 1/2" with 6 mm thick commercial plywood on back side and 12mm th soft board on front covered with cloth of selected design of Basic rate of Rs. 150 per Rmt. Steam beach member shall have lacquer polish as directed. VIII ROLLER BLINDS Supplying and fixing Roller Blind Blackout of approved make with selected fabric of approved design and shade. (Basic Price of Rs 135=00 Per Sq.Ft Excluding GST) IX FROSTED FILM Providing and Fixing Frosted polyster film of 3M (Scotchcal 7725 - 324) or equivalent make over glass surface as per drawing & direction with all labour & materials to the satisfaction of the Architect/Bank as per manufacturer's specification. No deduction will	
Using Silhouette Grid with Fine Fissured microlook Edge Tiles. With necessary Angles at junctions as per company specifications as directed complete. Rate includes necessary cut outs for A/C Grills, diffusers light fixtures complete as directed. 50.00 SMT SMT SMT Soft Board Providing & fixing soft board for pin up using moulded Steam beach frame of 1" x 1/2" with 6 mm thick commercial plywood on back side and 12mm th soft board on front covered with cloth of selected design of Basic rate of Rs. 150 per Rmt. Steam beach member shall have lacquer polish as directed. ROLLER BLINDS SUPPlying and fixing Roller Blind Blackout of approved make with selected fabric of approved design and shade. (Basic Price of Rs 135=00 Per Sq.Ft Excluding GST) ROSTED FILM Providing and Fixing Frosted polyster film of 3M (Scotchcal 7725 - 324) or equivalent make over glass surface as per drawing & direction with all labour & materials to the satisfaction of the Architect/Bank as per manufacturer's specification. No deduction will	
Angles at junctions as per company specifications as directed complete. Rate includes necessary cut outs for A/C Grills, diffusers light fixtures complete as directed. SMT Suturt for light and Diffusers will be deducted from area. Only Tiles cost will be deducted for payment purpose. After completion of work, certificate from Company to be obtained and submitted with bill that work is carried out as per their specifications. IN SOFT BOARD Providing & fixing soft board for pin up using moulded Steam beach frame of 1" x 1/2" with 6 mm thick commercial plywood on back side and 12mm th soft board on front covered with cloth of selected design of Basic rate of Rs. 150 per Rmt. Steam beach member shall have lacquer polish as directed. IN ROLLER BLINDS SUPPlying and fixing Roller Blind Blackout of approved make with selected fabric of approved design and shade. (Basic Price of Rs 135=00 Per Sq.Ft Excluding GST) The ROSTED FILM Providing and Fixing Frosted polyster film of 3M (Scotchcal 7725 - 324) or equivalent make over glass surface as per drawing & direction with all labour & materials to the satisfaction of the Architect/Bank as per manufacturer's specification. No deduction will	
necessary cut outs for A/C Grills, diffusers light fixtures complete as directed. Cutout for light and Diffusers will be deducted from area. Only Tiles cost will be deducted for payment purpose. After completion of work, certificate from Company to be obtained and submitted with bill that work is carried out as per their specifications. III SOFT BOARD Providing & fixing soft board for pin up using moulded Steam beach frame of 1" x 1/2" with 6 mm thick commercial plywood on back side and 12mm th soft board on front covered with cloth of selected design of Basic rate of Rs. 150 per Rmt. Steam beach member shall have lacquer polish as directed. III ROLLER BLINDS Supplying and fixing Roller Blind Blackout of approved make with selected fabric of approved design and shade. (Basic Price of Rs 135=00 Per Sq.Ft Excluding GST) IX FROSTED FILM Providing and Fixing Frosted polyster film of 3M (Scotchcal 7725 - 324) or equivalent make over glass surface as per drawing & direction with all labour & materials to the satisfaction of the Architect/Bank as per manufacturer's specification. No deduction will	
Cutout for light and Diffusers will be deducted from area. Only Tiles cost will be deducted for payment purpose. After completion of work, certificate from Company to be obtained and submitted with bill that work is carried out as per their specifications. //II SOFT BOARD Providing & fixing soft board for pin up using moulded Steam beach frame of 1" x 1/2" with 6 mm thick commercial plywood on back side and 12mm th soft board on front covered with cloth of selected design of Basic rate of Rs. 150 per Rmt. Steam beach member shall have lacquer polish as directed. //III ROLLER BLINDS Supplying and fixing Roller Blind Blackout of approved make with selected fabric of approved design and shade. (Basic Price of Rs 135=00 Per Sq.Ft Excluding GST) IX FROSTED FILM Providing and Fixing Frosted polyster film of 3M (Scotchcal 7725 - 324) or equivalent make over glass surface as per drawing & direction with all labour & materials to the satisfaction of the Architect/Bank as per manufacturer's specification. No deduction will	
deducted for payment purpose. After completion of work, certificate from Company to be obtained and submitted with bill that work is carried out as per their specifications. VII SOFT BOARD Providing & fixing soft board for pin up using moulded Steam beach frame of 1" x 1/2" with 6 mm thick commercial plywood on back side and 12mm th soft board on front covered with cloth of selected design of Basic rate of Rs. 150 per Rmt. Steam beach member shall have lacquer polish as directed. VIII ROLLER BLINDS Supplying and fixing Roller Blind Blackout of approved make with selected fabric of approved design and shade. (Basic Price of Rs 135=00 Per Sq.Ft Excluding GST) IX FROSTED FILM Providing and Fixing Frosted polyster film of 3M (Scotchcal 7725 - 324) or equivalent make over glass surface as per drawing & direction with all labour & materials to the satisfaction of the Architect/Bank as per manufacturer's specification. No deduction will	
After completion of work, certificate from Company to be obtained and submitted with bill that work is carried out as per their specifications. VII SOFT BOARD Providing & fixing soft board for pin up using moulded Steam beach frame of 1" x 1/2" with 6 mm thick commercial plywood on back side and 12mm th soft board on front covered with cloth of selected design of Basic rate of Rs. 150 per Rmt. Steam beach member shall have lacquer polish as directed. VIII ROLLER BLINDS Supplying and fixing Roller Blind Blackout of approved make with selected fabric of approved design and shade. (Basic Price of Rs 135=00 Per Sq.Ft Excluding GST) IX FROSTED FILM Providing and Fixing Frosted polyster film of 3M (Scotchcal 7725 - 324) or equivalent make over glass surface as per drawing & direction with all labour & materials to the satisfaction of the Architect/Bank as per manufacturer's specification. No deduction will	
bill that work is carried out as per their specifications. VII SOFT BOARD Providing & fixing soft board for pin up using moulded Steam beach frame of 1" x 1/2" with 6 mm thick commercial plywood on back side and 12mm th soft board on front covered with cloth of selected design of Basic rate of Rs. 150 per Rmt. Steam beach member shall have lacquer polish as directed. VIII ROLLER BLINDS Supplying and fixing Roller Blind Blackout of approved make with selected fabric of approved design and shade. (Basic Price of Rs 135=00 Per Sq.Ft Excluding GST) IX FROSTED FILM Providing and Fixing Frosted polyster film of 3M (Scotchcal 7725 - 324) or equivalent make over glass surface as per drawing & direction with all labour & materials to the satisfaction of the Architect/Bank as per manufacturer's specification. No deduction will	
Providing & fixing soft board for pin up using moulded Steam beach frame of 1" x 1/2" with 6 mm thick commercial plywood on back side and 12mm th soft board on front covered with cloth of selected design of Basic rate of Rs. 150 per Rmt. Steam beach member shall have lacquer polish as directed. III ROLLER BLINDS	
with 6 mm thick commercial plywood on back side and 12mm th soft board on front covered with cloth of selected design of Basic rate of Rs. 150 per Rmt. Steam beach member shall have lacquer polish as directed. Indeed	
covered with cloth of selected design of Basic rate of Rs. 150 per Rmt. Steam beach member shall have lacquer polish as directed. //III ROLLER BLINDS Supplying and fixing Roller Blind Blackout of approved make with selected fabric of approved design and shade. (Basic Price of Rs 135=00 Per Sq.Ft Excluding GST) IX FROSTED FILM Providing and Fixing Frosted polyster film of 3M (Scotchcal 7725 - 324) or equivalent make over glass surface as per drawing & direction with all labour & materials to the satisfaction of the Architect/Bank as per manufacturer's specification. No deduction will	
covered with cloth of selected design of Basic rate of Rs. 150 per Rmt. Steam beach member shall have lacquer polish as directed. //III ROLLER BLINDS Supplying and fixing Roller Blind Blackout of approved make with selected fabric of approved design and shade. (Basic Price of Rs 135=00 Per Sq.Ft Excluding GST) IX FROSTED FILM Providing and Fixing Frosted polyster film of 3M (Scotchcal 7725 - 324) or equivalent make over glass surface as per drawing & direction with all labour & materials to the satisfaction of the Architect/Bank as per manufacturer's specification. No deduction will	
IROLLER BLINDS Supplying and fixing Roller Blind Blackout of approved make with selected fabric of approved design and shade. (Basic Price of Rs 135=00 Per Sq.Ft Excluding GST) 16.00 SQMT	
Supplying and fixing Roller Blind Blackout of approved make with selected fabric of approved design and shade. (Basic Price of Rs 135=00 Per Sq.Ft Excluding GST) 16.00 SQMT FROSTED FILM Providing and Fixing Frosted polyster film of 3M (Scotchcal 7725 - 324) or equivalent make over glass surface as per drawing & direction with all labour & materials to the satisfaction of the Architect/Bank as per manufacturer's specification. No deduction will 6.00 SQMT	
approved design and shade. (Basic Price of Rs 135=00 Per Sq.Ft Excluding GST) 16.00 SQMT FROSTED FILM	
Providing and Fixing Frosted polyster film of 3M (Scotchcal 7725 - 324) or equivalent make over glass surface as per drawing & direction with all labour & materials to the satisfaction of the Architect/Bank as per manufacturer's specification. No deduction will	
Providing and Fixing Frosted polyster film of 3M (Scotchcal 7725 - 324) or equivalent make over glass surface as per drawing & direction with all labour & materials to the satisfaction of the Architect/Bank as per manufacturer's specification. No deduction will	
satisfaction of the Architect/Bank as per manufacturer's specification. No deduction will	
satisfaction of the Architect/Bank as per manufacturer's specification. No deduction will	
The made for any cutting in the film	
or made for any educing in and mills.	
TOTAL COST "A"	