	SCHEDULE OF QUANTITIES							
AIR CONDITIONING WORKS								
AT NEW PREMISES OF LAKKAVARAPU KOTA								
S. No.	Description of item/ work	Quantity	Unit	Rate (in Rs)	Amount (in Rs)			
Α	CASSETTE SPLIT ACs :							
1	Supply of Inverter Model Cassette split Air Conditioners (minimum BEE 3 star rated Airconditioner) with Full Copper Condensor coils and Rotary type compressor sufficiently filled with Ozone friendly R32/ R410 Refrigerant Gas, with 3 mtrs of Copper piping (Covered with 9 mm thick closed cell nitrile rubber foam), Cordless remote & other fasteners etc.							
а	2.0 TR (For Banking Hall)	4	Nos.		0			
2	Installation, Testing & Commissioning of the following Air Conditioners along with the necessary accessories completely as per standards							
а	2.0 TR (For Banking Hall)	4	Nos.		0			
3	Supply & fixing of Support structure for outdoor units made of M S Metallic Structures coated with non rustic paint as per the site conditions with necessary hardware and fasteners for the following AC units.							
а	2.0 TR (For Banking Hall)	4	Nos.		0			
4	Supply, installation, testing and commissioning of Refrigerant Piping (Liquid & Suction Soft Drawn Copper refrigerant piping) covered with Class-1, 9mm thk closed cell nitrile rubber foam wrapped with 0.5mm thick PVC Tape for above Airconditioners for interconnecting the indoor unit and OD Unit, to be suspended from the ceiling (where ever necessary) with proper supports, clamps and a piece of PVC pipe within the clamp to place the copper pipe.	50	Rmt		0			
5	Supply and installation of Electrical & Control Cables of suitable size (Only one length will be will be considered even for multiple lines).		Rmt		0			

В	WALL SPLIT ACs :			
6	Supply of Inverter Model Hiwall split Air Conditioners (BEE 5			
	star rated Airconditioner) with Full Copper Condensor coils and			
	Rotary type compressor sufficiently filled with Ozone friendly R32/			
	R410 Refrigerant Gas, with 3 mtrs of Copper piping (Covered			
	with 9 mm thick closed cell nitrile rubber foam), Cordless remote			
	& other fasteners etc.			
а		1	Nos	0
b		3	Nos	0
	Supply of Voltage Stabilizers for the above Airconditioner as per			-
7	the following ratings.			
а	4 kVA		Nos.	0
b	5 kVA	4	Nos.	0
	Installation, Testing & Commissioning of the following Air			
8	Conditioners along with the necessary accessories completely as			
	per standards			
а	\	1	Nos	0
b	1.0 (1-Ph) TR (For Cash officer Room & ATM)	3	Nos	0
	Supply & fixing of Support structure for outdoor units made of			
9	M S Metallic Structures coated with non rustic paint as per the			
١	site conditions with necessary hardware and fasteners for the			
	following AC units.			
а	, , ,	1	Nos	0
b	(3	Nos	0
	Supply, installation, testing and commissioning of Refrigerant			
	Piping (Liquid & Suction Soft Drawn Copper refrigerant			
	piping) covered with Class-1, 9mm thk closed cell nitrile rubber			
10	foam wrapped with 0.5mm thick PVC Tape for above		Rmt	0
10	Airconditioners for interconnecting the indoor unit and OD Unit, to	20	IXIII	o l
	be suspended from the ceiling (where ever necessary) with			
	proper supports, clamps and a piece of PVC pipe within the			
	clamp to place the copper pipe.			

11	Supply and installation of Electrical & Control Cables of suitable size (Only one length will be will be considered even for multiple lines).		Rmt	0
С	OTHER WORKS:			
12	Supply, installation, testing and commissioning of following size UPVC Drain pipe covered with nitrile rubber foam and PVC tape wrapped on it (for the length within the premises & not required in Out door area), with 'U' trap at the end.			
а	25mm dia, 2 mm thk	85	Rmt	0
b	20mm dia, 2 mm thk	20	Rmt	0
13	Supply and fixing of 40-45 mm PVC casing and caping of non perforated type and White colour finish including laying as per the instructions of Banks Engineer.		Rmt	0
	GRAND TOTAL (A+B):			-

Note:

- 1. GST as applicable shall be paid extra.
- 2. All materials shall be selected by the SBI officials or Engineer-in-charge before execution.
- 3. All the quantities are approx and executed as per site requirement.
- 4. The Bank reserves the right to select any of the brands indicated in the "List of Approved Makes"
- 5. The contractor cannot claim anything extra if the Bank changes the make but within the list of
- 6. Bidder shall visit/ inspect the site before quote.