

**PRICE BID FOR SHEET ROOFING WORKS ON TERRACE OF BANK'S EXISTING BRANCH BUILDING AT
PEERMEDU , IDUKKI DISTRICT**

Sl.No	items of works	Qty	Unit	Rate	Amount
1	Providing concrete base of size 45 x 45 x 60 cms with PCC 1:2:4 using 20 mm metal for fixing the GI pipe post including cost of all materials, scaffolding and curing	60	Nos.		
2	Providing and fixing 2"dia GI pipe (B Class) with anchor plates welded at bottom as directed including painting the pipe with 2 coats of enamel paint over a coat of primer.	45	RM		
3	Providing and fixing 3"dia GI pipe (B Class) with anchor plates welded at bottom as directed including painting the pipe with 2 coats of enamel paint over a coat of primer.	95	RM		
4	Providing and fixing in position welded truss of 30 cm overall depth made out of 32x32x1.6 mm square pipe (TATA Structura make) at top, bottom and interconnecting members welded to the pipes as directed with necessary plates to fix the rafters/ purlins including painting with 2 coats of enamel paint over a coat of zinc chromite primer	245	RM		
5	Providing and fixing in position 14 guage TATA GI sections and the following sizes as rafters welded to the trusses as directed including painting 2 coats of synthetic enamel paint over a coat of primer 4"x 2"sections	85	RM		
6	Providing and fixing in position 25 x 25 mm suare GI rectangulat sections 16 guage thickness TATA structura sections as purlins firmly welded to trusses/ rafters as directed including painting with 2 coats of synthetic enamel paint over a coat of Zinc Chromite primer	405	RM		

7	Providing and fixing in position coloured Aluminium corrugated sheets of 0.45 mm (Jindal/ everlast) using necessary bolts (minimum 4 bolts to each sheet) including cost of all fixtures such as bitumen rubber washer, covering the holes with water proofing ompound etc. Measurement shall be for the actual covered area inclusive of overlaps	530	Sq.m		
8	Providing and fixing in position ridges and valleys of necessary size made from 18 guage GI colour coated sheet and painting as directed including cost of clamps other supports as directed	110	RM		
9	Providing and fixing PVC gutter of size 8"	145	RM		
10	Providing and fixing in position PVC down water pipes 8"dia (4 Kg) (with necessary drop, clamps bottom seat etc. complete	85	RM		
11	Providing and fixing additional MS Framework for Solar panel fixing & Cat walk frame work for solar panel service etc. complete	50	Sq.m		
	TOTAL				-

GST at applicable rates will be extra