

BOQ FOR CONSTRUCTION OF DRAIN COVERS AT ORC BHANGAGARH

Sl.No	Description of items	Unit	Qty	Rate (Rs.)	Amount (Rs.)
1	Clearing and uprooting vegetaion, grass, brush wood, trees and saplings of girth and removal of rubbish etc. the inclusive of disposing the same to dumping ground as specified by GMDA/GMC including coast of all lead, lift, loading, unloading and transportataion complete as directed bt the Engineer-in-charge.	Job	1		
2	Hacking of top drain edge surface and preparing the surface for re-pointing or replastering or brickwork, including disposal of rubbish to the dumping ground as specified by GMDA/GMC, all complete as per direction of Engineer-in-Charge.	sqm	352		
3	Providing and laying in position of reinforced cement concrete of specified grade excluding the cost of centering and shuttering - All work above plinth level : 1:2:4 (1 Cement : 2 coarse sand(zone-III) : 4 graded stone aggregate 20 mm nominal size). Make:Ultra Tech, ACC, Ambuja, Dalmia Bharat or equivalent. The rate is inclusive of applying neat cement slurry for proper binding.	CUM	37		
4	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Mild steel and Medium Tensile steel bar.	Kg	1950		
5	Centering and shuttering including strutting, propping etc. and removal of form for : drain slab.	SQM	30		
6	Brick work with common burnt clay F.P.S (non modular) bricks of class designation 7.5 in cement mortar 1:3 (1 cement: 3 coarse sand) in super structure above plinth level	sqm	190		
7	12mm - 15mm cement plaster of mix: 1:4(1 cement:4 sand) with neat cement slurry finish.	sqm	176		
	Total				

All rates are exclusive of GST