

**PRICE BID FOR CIVIL WORKS AT THE NEW PREMISES OF SBI TWIN TOWERS SMART CITY BRANCH
ERNAKULAM**

SI.No	DESCRIPTION OF WORK	Qty	Unit	Rate	Amount
1	Painting the walls/ ceiling with two coats of plastic emulsion paint of approved make and shade including cleaning the surface over a coat of putty.	200	Sq.M		
2	Painting the walls/ ceiling with two coats of plastic emulsion paint of approved make and shade including cleaning the surface.	200	Sq.M		
3	Painting the windows/ doors/ ventilators with two coats of synthetic enamel paint of approved make and shade including cleaning the surface.	10	Sq.M		
4	Block work in CM 1:6 with CC blocks of 40/30x20x15 cm or AAC blocks for superstructure	15	Cu.m		
5	Plastering including patch plastering with cement mortar 1:5 (1cement 5 sand) 12mm thick, one coat floated hard and travelled smooth for the wall surfaces including all staging works, watering ,curing etc. complete.	250	Sq.M		
6	Cement Concrete 1:2:4 for lintel including shuttering, curing,cost of reinforcement etc complete as directed	2.00	Cu.m		
7	Providing and laying anti- skid vitrified floor tiles of size 1200 x 600 mm (thickness to be specified by the manufacturer) (minimum basic value should be @ Rs. 600/m ²) of first quality conforming to IS:15622, of approved make, in all colours, shades, size as specified by Engineer in charge , laid over 20 mm thick bed of cement mortar 1:4, including epoxy grouting & pointing the joints with epoxy matching with tiles etc. complete for flooring.	60	Sq.M		
8	Flooring with Italian marble finish vitrified tiles of superior quality and approved colour and 9 mm thick or as per manufacture's specifications, 800x800 mm or higher size with basic price of Rs.1100/m ² and fixing the tiles to correct line and levels (The make of vitrified tiles is of Cera/Asian/ RAK/ bell. Shades, size as specified by Engineer in charge , laid over 20 mm thick bed of cement mortar 1:4, including epoxy grouting & pointing the joints with epoxy matching with tiles etc. complete for flooring.	230	Sq.M		
9	Providing and fixing steel door of size 90 x210 cms for ups and record rooms with necessary frame work and all other fixtures including painting with enamel paint of approved make over a coat of primer	3	Sq.M		
10	Providing and laying RCC M20 including cost of all form work watering, curing etc complete but excluding cost of reinforcement for floor and walls and ceiling of strong room etc. Complete but excluding reinforcement.	25	Cu M		

11	Providing and laying PCC 1:2:4 using by metal over the existing floor , levelling the surface upto 100 mm thickness etc complete.	2	Cu M		
12	Providing steel reinforcement of 12 mm dia for RCC works including bending, tying and placing in position [for strong room walls and floors, 12mm dia bars shall be placed vertically and horizontally at 15cm centre to centre in two rows, staggered centrally and placed along both faces of the walls with a clear cover of 40mm on either side of the walls/ floor]. Thermo-Mechanically Treated Bars	2750	Kg		
TOTAL					-

GST at applicable rates will be extra