

**INTERIOR FURNISHING WORKS AT NEW PREMISES OF
GUNTUPALLI BRANCH, STATE BANK OF INDIA ,
VIJAYAWADA, ANDHRA PRADESH.**

**BILL OF QUANTITY
PRICE BID**

**SCHEDULE OF QUANTITIES FOR INTERIOR FURNISHING WORKS AT NEW PREMISES OF
GUNTUPALLI BRANCH**

All rates of items are excluding G.S.T. The Contractor should quote the rates exclusive of G.S.T.

| S.N | DESCRIPTION OF ITEM | Unit | Quantity | Unit Rate | Amount |
|------|--|-----------|----------|-----------|--------|
| 1.00 | <p>GYPSUM BOARD CEILING Providing and fixing 12.5mm thick Gypsum Ceiling Board False Ceiling in horizontal, vertical surfaces moulded corners & offsets as per architectural drawing which shall include providing and fixing roll formed G.I. perimeter channels of sizes 27x.5mm thick having one flange of 30mm along the perimeter of the ceiling fixed to the brick wall or partition with help of rawl plug or screw including ending of G.I.intermediate channels of size 45x9mm thick with two flanges of 15mm thick each from the soffit @1200mm c/c with steel /G.I.hanger of width 25mm & 0.5mm thickness fixed to soffit with G.I.cleat & steel expansion fasteners of 0.5mm thickness having knurled wedge of 51.5mm, two flanges of 26mm each with tips of 10.5 mm fixed to the intermediate channel with the help of converting clips in a direction perpendicular to the intermediate channel of 350mm c/c 12.5mm taper edge gypsum plaster board conforming to I.S.: 2095,1982 shall be screwed at 230mm c/c with screw fixing done mechanically with suitable attachment of the tapered & squared edges of the boards as recommended by the manufacturer finished with two or more coats over a coat of primer. Item includes extra frame work for necessary hatch doors/ opening upto 600mmx600mm or as per requirement with 19mm commercial board wherever required including necessary brass hinges, screws & finish smooth as directed The rate shall include the cost of extra frames for A.C openings light fixtures, speakers & coves etc.complete to the satisfaction of Architect/ Bank's Engineer. Note: Only horizontal base area shall be measurement for payments. Make - Gypsum Board- Saint Gobain, Boral, Sakrani, Paint - Berger/ Asian/ Nerolac, GI Channel - Gyp steel/IGL/Diamond/Ultra.</p> | SQ . M | 103.07 | | |
| 2.00 | <p>Grid false ceiling: Providing & Fixing of Mineral Fibre Acoustical Suspended Ceiling System with 15mm Tiles and Exposed GRID. The tiles should have Humidity Resistance (RH) of 90% - 99%, NRC 0.5, Light Reflectance $\geq 87\%$, Thermal Conductivity $k = 0.052 - 0.057$ w/m K, Colour White, Fire Performance UK Class 0 / Class 1 (BS 476 pt - 6 & 7) in module size of 600 x 600 x 16mm , suitable for Green Building application, with Recycled content of 30% - 45% . The tile shall be laid on Microline / Silhouette profile grid system with 15mm - 16mm white flanges incorporating a 6mm central reveal in white/black colour and with a web height of 38mm and a load carrying capacity of minimum 8 Kgs/M² & minimum pull out strength of 100 Kgs. Microline / Silhouette, Main Runners & Cross Tees to have mitred ends & "birdsmouth" notches to provide mitred cruciform junctions. The T Sections have a Galvanizing of 90 grams per M² and need to be installed with Suspension system as per manufacturers details. The Instalation to comprise main runner spaced at 1200mm centres securely fixed to the structural soffit using US Boral / Gyproc / Armstrong suspension system</p> | SQ . M | 46.55 | | |

| | | | | | |
|--------------------|--|------------|-------------|--|--|
| | <p>(specifications below) at 1200mm maximum centre. The First/Last suspension system at the end of each main runner should not be greater than 450mm from the adjacent wall. Flush fitting 1200mm long cross tees to be interlocked between main runners at 600mm centre to form 1200 x 600 mm module. Cut cross tees longer than 600mm require independent support. 600 x 600mm module to be formed by fitting 600mm long flush fitting cross tees centrally between the 1200 mm cross tees. Perimeter trim to be Wall angles of size 3000mm x 19mm x 19mm, secured to walls at 450 mm maximum centres.</p> | | | | |
| <p>3.00</p> | <p>Cash Officer Table with Side Unit: Providing & fixing in position 1750mm to 1500mm (L) x 750mm (H)x750mm (W) + 1050mm x 450mm x 750mm with the following specifications:</p> <p>(i) Main Table and side Table top to be made in 25 mm block board with 1mm thick laminate. The front side of the table to have a inverted "U" made with 2x18 mm thick MR Plywood cladded with 1mm laminate on the front and the verticals towards the modesty panel. The modesty panel to have 18mm MR Plywood cladded with 1mm Glossy Laminate (for vertical exposed faces) and 1mm Laminate (Table Top) as specified.</p> <p>(ii) The " L " shaped table top along with side table to have 49mm edge beading all-round, which is to be achieved by adding a 75mm piece of 18mm MR Plywood to the table top from bottom and this vertical edge is to be cladded with 12mm thick teak wood lipping finished with minimum two coats of LOW VOC or NOW VOC duco paint.</p> <p>(iii) All other members to be with 18mm MR Plywood and all exposed faces of the table to have 1mm Laminate as specified above to be used.</p> <p>(iv) All edges to be provided & fixed with teak wood lipping patti finished with melamine polish/ Paint as directed by Engineer – in-charge.</p> <p>(v) Foot rest of 75 mm X 38 mm (3" x 1.5") in Teak wood and CPU stand of 18 mm ply finished with 1 mm thick laminate of size 400 mm X 375 mm. Key board tray of approved make of size 450 mm X 375 mm to be fixed..All the unexposed faces to have 0.8mm Laminate. All wood work shall be laquer polished to a smooth and uniform finish of choice colour and shade.</p> <p>(vi) One Three Drawer Unit made with 18mm MR Plywood and 12mm MR Plywood Exterior Grade Board. The unit to have one vertical filing drawer at bottom and two equal drawers on top. The rate to include all necessary hardware viz., heavy duty telescopic drawer channels, handles, locks, etc., and 18mm x 12mm teak wood edge lipping etc.,</p> <p>(vii) Side Table with shutter unit of 600mm with 25mm block board, with 2 drawers and two openable shutters made with 18mm MR Plywood Exterior Grade Board with necessary hardware viz., ' W ' hinges, handles, locks, tower bolts, etc., and 18mm x 12mm teakwood edge lipping etc.</p> <p>(viii) All table Tops are to be provided with 12m thick clear float glass with beveled edges and wire manager.</p> <p>(ix) All the unexposed faces to have 0.8mm Laminate. The cost to include all materials, automatic locks labour etc., for a finished item of work as per drawings and directions etc., complete.</p> | <p>Nos</p> | <p>1.00</p> | | |

| | | | | | |
|--------------------|---|------------|-------------|--|--|
| <p>4.00</p> | <p>Single Window Officer Counters with Side Unit: Providing, fixing in position 1500mm to 1800mm(w) x 900mm - 975mm(d) x 750mm (h) Single Window Counters (including heavy cash counter) along with side unit of size 1050mmx 450mmx 750mm made up of 18mm thick MR Plywood with specifications as mentioned below:</p> <p>(i) Counter top and side unit top to have 25mm Block Board with double thickness at edges with 1mm thick laminate on all horizontal surfaces (such as counter top, etc.,) and the front facia and remaining all exposed vertical faces to have 1mm Glossy Laminate as specified.</p> <p>(ii) Front facia of the counter should be provided with and 1mm thick blue glossy laminate. All other members to be with 18mm MR Plywood and 2 Nos. of 6mm Flexi Plywood in curvature (which should be achieved with a frame work of 50mm x 50mm Sal wood frame to be fixed from the front modesty panel / apron and the bottom of this niche to have provision of cove lighting with LED strips</p> <p>(iii) The unit to have one vertical filing drawer at bottom and two equal drawers on top.</p> <p>(iv) The rate to include all necessary hardware viz., telescopic drawer channels, handles, automatic locks, night latch etc., and 18mm x 12mm teak wood edge lipping etc.,</p> <p>(v) One Side Unit with shutters made with 25mm block board top and 18mm MR Plywood Exterior Grade Board for all other members with necessary hardware viz., ' W ' hinges, 100 SS handles, locks, SS tower bolts, etc., and 18mm x 12mm teak wood lipping etc.,</p> <p>(vi) Foot rest of 75 mm X 38 mm (3" x 1.5") in Teak wood and CPU stand of 18 mm ply finished with 1 mm thick laminate of size 400 mm X 375 mm. Key board tray of approved make of size 450 mm X 375 mm to be fixed..All the unexposed faces to have 0.8mm Laminate. All wood work shall be laquer polished to a smooth and uniform finish of choice colour and shade.</p> <p>(vii) Providing and fixing 12 mm thick Toughened float glass with polished edges to be fixed with necessary S.S Brush finish brackets & support on wooden partition as directed with necessary cut out in glass. A cutouts to be made one half round of 150mm dia . All edges of glass shall have Diamond cut polished edges as directed. There should be another 12mm thick toughnned glass of width 300mm to be fixed horizontally along the edge of vertical .</p> <p>(viii) The cost to include the "L " shaped Single Window Counter and to include all materials, hardware, automatic locks, night latch as per drawings and directions etc., complete.</p> | <p>Nos</p> | <p>3.00</p> | | |
|--------------------|---|------------|-------------|--|--|

| | | | | | |
|--------------------|--|-------------|--------------|--|--|
| <p>5.00</p> | <p>Branch Manager's Table with Side Unit: Providing, making and placing in position Executive Table and Side Table of approximate size 2100mm -1800mm x 900mm x 750mm + 1200mm - 1050mm x 450mm x 750mm with following specifications. (i) Main Table and side Table top and to be made in 25mm block board with 1.0mm thick laminate as specified.. The front side of the table to have made with 2 x 18mm thick MR Plywood cladded with 1 to 1.0mm thick laminate on the front and the verticals towards the modesty panel. The modesty panel to have 18mm MR Plywood cladded with 1.0MM Thk as specified. (Please refer drawing) (ii) The " L " shaped table top on the seating side to have 50mm edge all-round and to be cladded with 12mm MR Plywood finished with minimum two caots of LOW VOC or NOW VOC duco paint. (iii) All other members to be with 18mm MR Plywood and all exposed faces of the table to 1.0 MM THK Lam . All the edges of 18mm MR Plywood to have 18mm x 12mm teak wood edge lipping. One readymade CPU mobile pedestal. One Key Board Tray made with BWR Plywood BOARD and laminate with channels ,Ready Made Modular Foot Rest - 400mm x 350mm x 65mm. etc., (iv) One Three Drawer Unit made with 18mm MR Plywood and 12mm MR Plywood . The unit to have one vertical filing drawer at bottom and two equal drawers on top. The rate to include all necessary hardware viz., telescopic drawer channels, handles, locks, etc., and 18mm x 12mm MR Plywood edge lipping etc., (v) One Side Table with shutters made with 25mm block board top and 18mm MR Plywood for all other members with necessary hardware viz., ' W ' hinges, SS handles, locks, SS tower bolts, etc., and 18mm x 12mm beech wood edge lipping etc., All edges of 18mm thick Plywood to have 18mm x 12mm MDF edge lipping finished with 3mm edge banding (vi) All the unexposed faces to have 0.8mm Laminate. Table top should be provided with 12mm glass with edge beveling and wire manager. (vii) Taple top should be provided with 12mm glass with edge beveling and wire manager. (viii) The cost to include the "L " shaped Single Window Counter and to include all materials, hardware, labour for a neat and finish job as per drawings and directions etc., complete</p> | <p>Nos</p> | <p>1.00</p> | | |
| <p>6.00</p> | <p>Wall Mounted Writing Desk: Writing Desk Size 900 mm (3'-0") L x 380 mm (1'-3") depth x (900 mm + 150 mm) (3' + 6") ht. Vertical Sides and bottom shall be made out of 36mm (2X18) thick MR grade plywood and back side 12 mm thick ply wood with 1 mm Laminate on Top and Edges on all sides including inside divisions. Top shall be made from 12 mm thick toughend glass with polished edges, making different divisions by 12 mm thick glass and edges with 18 mm thick plywood with laminate on both side for slips or forms as per detail drawing and instruction complete. Laminate to be provided on all visible surface</p> | <p>Nos</p> | <p>1.00</p> | | |
| <p>7.00</p> | <p>Full height solid partitions (Plywood): Providing & fixing in position metal stud dry wall partition with the following specifications: a) Framing shall consist of only aluminium Section 50 mm*50mm (Wall thickness 1.2 mm) @ 2'0" C/C Both ways Horizontally and</p> | <p>Sq.M</p> | <p>11.43</p> | | |

| | | | | | |
|--------------------|---|-------------|--------------|--|--|
| | <p>Vertically, quality of workmanship top class tracks at floor, middle, door and ceiling level with joints staggered. The verticals should touch the ceiling with horizontal ceiling channel at slab/beam bottom. The rate should include necessary strengthening with studs/tracks or channel at doors and other openings.</p> <p>b) 06 mm MR grade ISI ply fixed on both sides with 25 mm dry wall screws.</p> <p>c) 01mm laminate of make ISI branch Sunmica Century, green or equivalent finish as per the layout joint free at front and top potation on both sides (dark for bands, light for body) up to false ceiling level.</p> <p>d) All beech wood members to have melamine polish finish. Length X height up to false ceiling will be measured for payment complete to the satisfaction of Architect/ Bank's Engineer.</p> <p>Make - Aluminium Section - Jindal, Indal, Balco, Plywood & MDF - Century /Green ply/Sylvan or Approved Equivalent, Laminate - Century/Merino/Greenlam/Aica.</p> | | | | |
| <p>8.00</p> | <p>Full height partly solid partly glazed wooden partition with both sides laminate:</p> <p>Providing & fixing in position 70mm thick +/- 2mm partly solid / opaque partly glazed full height wooden partitions with 1200 mm high glass middle panles finished with laminate on both sides comprising as under:-</p> <p>(i) Framing- Made out of 50mm x 50mm, 1.2 mm thick hollow aluminium sections not exceeding 600 mm c/c bothways (horizontal and vertical) except in glazed portion of partition, fixed rigidly on floor, wall / column & ceiling. Spacing of frame members may vary to the nearest possible extent as per site conditions.</p> <p>(ii) Plywood skin:- Providing & fixing 9 mm thick MR plywood on both sides of the framework.</p> <p>(iii) Finishing:- Providing 1.00 mm thick, approved quality and shade laminate, on both sides of partitions in approved design & pattern including making grooves as per Architectural drawing or as directed by the Engineer-incharge using approve qulaity adhesive complete.</p> <p>(iv) Providing and fixing 12mm thick approved make 1200 mm high toughened Glass panels in the middle panles of partitions using second class seasoned teak wood moulding of finished sectional size 75mmx12/15 mm alround, complete as per drawing and as directed at site. Making suitable cutouts/openings/channels for Doors, electrical conduits, cables & switch boards, AC ducts etc including providing necessary wooden supports wherever required and directed at site.</p> <p>(v) Providing and making suitable door frame with rebate for door shutters using approved quality seasoned full length Teak Wood having finished sectional size 75mm x 20mm to the door perimeter complete as per detailed Architectural drawing and as directed at site. Applying 2 or more coats of approved matching shade and finish, melamine polish to all exposed edges of partitions including those in door openings, cutouts etc. complete. The rate shall include cost of required hardware, necessary transportation, execution of work at all heights and locations including all lead, lift, wastage, statutory liabilities etc. complete.</p> <p>(vi) The glass to be finished with designer film with elipse design as per the given design. The designer film is of Harmony/ 3M or equivalent approved make</p> | <p>SQ.M</p> | <p>14.10</p> | | |

| | | | | | |
|-------|--|------|-------|--|--|
| 9.00 | Same as above but one side of partition is to be finished with one side laminate and other side with 4mm thick Veneer of basic cost 1000/Sq.M | SQ.M | 5.30 | | |
| 10.00 | <p>Low Height Glazed Partition: Providing & fixing in position 70 mm +/- 2mm thick Low height wooden partitions with 450mm high glass panel finished with laminate on both sides comprising as under:-</p> <p>(i) Total Height of the partitions shall be from 1200 mm to be 1450 mm including 300 to 450 mm high 12 mm clear glass panel as per approved drawing.</p> <p>(ii) Framing : Made out of 50mm x 50mm, 1.2 mm thick hollow aluminum sections placed both ways (horizontal and vertical) not exceeding 450 mm c/c rigidly fixed to floor, wall / columns etc including extending end/intermediate vertical members not exceeding 1500 mm c/c for total finished height of LHP.</p> <p>(iii) Plywood skin : Providing & fixing 9mm thick MR plywood IS 303 on both sides of the framework and all-round vertical posts extending up to total height of LHP.</p> <p>(iv) Finishing :- Providing and fixing 1.00mm thick approved quality and shade laminates using approved quality adhesive, over ply as per approved design & pattern including providing grooves as per Architectural drawing and as directed by the Engineer-in-charge.</p> <p>(v) Glazing :- Providing and fixing 12mm thick approved make clear float glass panels (not exceeding 1.50 m in length) with polished edges on all sides, fixed using suitable CP Brass /SS 'D' brackets placed not exceeding 450mm c/c on horizontal surface of partition and at both ends on vertical posts to rigidly hold the glass panels.</p> <p>(vi) Providing finished section size 70/75 x 8mm thick seasoned second class Teak wood moulding to all exposed edges of partition including applying 2 or more coats of melamine polish / Duco paint including necessary preparatory work for surface preparation with putty, priming coat, sealer coat etc. complete as per sample approved by the Bank.</p> <p>(vii) Making necessary cutouts for electrical conduits / cables & switch boards etc., including providing additional supports wherever required complete as per drawings and as directed by Engineer</p> <p>(viii) The rate shall include cost of required hardware, necessary transportation, execution of work at all heights and locations including all lead, lift, wastage, statutory liabilities etc. complete.</p> <p>(ix) The glass to be finished with designer film with elipse design as per the given design. The designer film is of Harmony/ 3M or equivalent approved make.</p> | SQ.M | 12.26 | | |
| 11.00 | <p>Doors in Partition: Providing & fixing 35 mm Flush doors with 1.0mm laminate on both sides as per design.</p> <p>(i) Door frame:- Providing and fixing door frames using teakwood members of size 100mm x 50mm and finished with melamine polish.</p> <p>(ii) Shutter:- Providing and fixing block board shutters of 35mm thick .</p> <p>(iii) Skin:- The shutters shall be finished with 1mm thick laminate of approved quality and make.</p> <p>(iv) The Doors to have all hardware such as 125mm SS hinges, 450 m long SS handles, SS tower bolts, Mortice Locks (Dorma/ Godrej).</p> | Nos | 5.00 | | |

| | | | | | |
|--------------|---|------|-------|--|--|
| | <p>(v) 8mm clear float glass with 3M privacy film fixed as per drawing with 50mm x 18mm teak wood jamb around the glass opening and 12mm x 12mm teak wood button beading for fixing of glass on both sides.</p> <p>(vi) Exposed edges of shutter shall be provided with teakwood beading of 30mm width and finished with melamine polish.</p> | | | | |
| 12.00 | <p>Column/wall paneling(Laminate Finish) Laminated Columns/Wall Panelling Providing and fixing in position wooden paneling to column / walls finished with laminate comprising as under:-</p> <p>(i) Framework:- Made out of 50 mm x 25 mm x 1.2mm thick extruded Aluminium hollow sections, placed not exceeding 600 mm centre to centre, bothways (horizontal and vertical), fixed rigidly on wall / columns in perfect line, level and plumb.</p> <p>(ii) Panel Finishing:- Providing & fixing 9 mm thick approved make MR plywood to Aluminum framework finished with 1.00 mm thick approved quality and shade laminate, using approved adhesive, in approved pattern & design, including providing grooves, decorative mouldings etc. as per Architectural drawings and as directed at site by the Engineer-in-charge.</p> <p>(iii) Providing approved quality, seasoned, full length, Teak Wood moulding 15 mm thick with adequate width as required at site, to all openings, cutouts etc duly polished with melamine polish complete as directed by the Engineer-in-charge at site.</p> <p>(iv) The rate should include cost of necessary hardware, making cutouts / openings for electrical conduits / cables, Switch boards, AC ducts etc., including providing necessary wooden/aluminum section members support at cutouts, doors/windows openings etc. complete as per drawings and as directed by the Engineer-in-charge at site.</p> <p>(v) Applying 2 or more coats of melamine polish to exposed edges of panelling, moulded beadings etc. including preparation of surface, sealer coats etc. complete including wastage of material, if any, scaffolding for execution of work at all heights and locations etc. complete</p> | SQ.M | 51.54 | | |
| 13.00 | <p>Column / Wall Panelling (Veneer): Same as above but with 4mm thick veneer is to be used instead of laminate</p> | SQ.M | 8.55 | | |
| 14.00 | <p>Roller blinds: Providing and fixing in position of block out roller blinds roller blinds of make Vista or equivalent (Basic cost of fabric is Rs1200/- per Sq.Mt)</p> | SQ.M | 2.97 | | |
| 15.00 | <p>CUPBOARDS / STORAGE UNITS OF 2.5 FT. (0.75 mtrs) HT. Providing & fixing Low Height Storage Cupboard of 750-1200 mm height and 450mm deep Outer exposed structure with to be made with 18mm MR ply as per IS 303 and back side using 8mm MR grade ply. All shutters and shelves to be made with 18 mm thk.MR ply. All internal and external surfaces to be finished with 4mm thk Veneer and internal surfaces to be finished with 1mm laminate of approved shade and make. All edges of the cupboard should be edge banded using PVC edge banding tape of approved shade. Shutters to be provided with S.S. 200mm handles, magnetic catchers, self closing SS hinges, locks (Godrej/ Hettich/ Haffele), SS tower bolts etc. All shutters to be made overlapping the frame Only front elevation will be considered for area calculation..</p> | SQ.M | 2.21 | | |
| 16.00 | <p>CUPBOARDS / STORAGE UNITS OF 8 FT. (2.44 mtrs) HT.</p> | | 13.01 | | |

| | | | | | |
|--------------|--|------|-------|--|--|
| | Providing & fixing Low Height Storage Cupboard of 1500-2400 mm height and 450mm deep Outer exposed structure with to be made with 18mm MR ply as per IS 303 and back side using 8mm MR grade ply. All shutters and shelves to be made with 18 mm thk.MR ply. All internal and external surfaces to be finished with 1mm laminate of approved shade and make. All edges of the cupboard should be edge banded using PVC edge banding tape of approved shade. Shutters to be provided with S.S. 200mm handles, magnetic catchers, self closing SS hinges, locks (Godrej/ Hettich/ Haffele), SS tower bolts etc. All shutters to to be made overlapping the frame Only front elevation will be considered for area calculation.. | SQ.M | | | |
| 17.00 | Glazed Door :- Providing, fixing in position 12mm thick toughened glass door with patch fitting of approved make. The Door to consist of Heavy Duty Floor spring, Upper Patch, Bottom Patch, Lock Keeper Plate, Euro Profile Cylinder (EPC), "H" Type Handle 32 x 600mm, Corner Lock and the side fixed glass to have 2 Nos. Bottom Patch and 2 Nos. Upper Patch for each door to a neat finish etc., complete as per drawing. The work includes cost of all materials, approved hardware, making necessary template before toughening of glass and fixing the same as per site conditions to a neat finished work as per drawings and directions etc., complete. The glass to be finished with designer film with elipse design as per the given design. The designer film is of Harmony/ 3M or equivalent approved make. | Nos | 3.00 | | |
| 18.00 | Full Height Fully Glazed Partitions: Providing & fixing in position 12MM TOUGHENED GLASS with approved brand patch fittings including fixing in position as directed by Engineer-in-charge. Glass should be up to false or roof height (single piece) fixed using Patch Fittings. No wooden or plywood cantles runners to be used for fixing the glass up to false ceiling height. Suitable supporting structure if required may be build with best quality wooden members above false ceiling level. (The rate quoted should be inclusive of this supporting system) | SQ.M | 7.06 | | |
| 19.00 | Acrylic Letters Providing and fixing wall mounted LED backlit acrylic letters using 3mm thick acrylic sheet in given colors and design. The letters to be protruded out 50 to 60mm from wall. Rear side of letters also to be made of acrylic sheet. Rate quoted should be inclusive LED lights: Rate quoted should be per letter : Letter SZE : 710mm x 710mm. | Nos | 1.00 | | |
| | Same as above but for letters of size 710mm x 460mm | Nos | 3.00 | | |
| | Same as above but for letters of size 165 mm x 165mm | Nos | 10.00 | | |
| 20.00 | Suggestion Box : Providing and fixing suggestion Box of size 450mm (H)x450mm (w) x 150mm (D) (Inner Dimensions) with 19mm thick MR grade Plywood board laminated with 1mm thick glossy laminate on one side and 0.8mm thick backer laminate inside. The Box should have locking facility. Front Side of Box should have 6mm thick clear glass vision panel of size 150mmx 150mm fixed with necessary beadings. | Nos | 2.00 | | |
| 21.00 | PIN-UP BOARDS Providing and fixing pinup boards. It consist ½” soft boards of good density to be mounted over ½” ply. The soft board will be covered with a plain fabric approved blue color (approx Rs.150 /Rmts.) from front and edges. Suitable laminated border (as directed by architect) will be fixed on all four sides an. Note : Only soft boards provided on other than the partitions will be measured | SQM | 1.86 | | |

| | | | | | |
|--------------|--|------|-------|--|--|
| | and soft board made in the partitions will be the part of the partition measurement (rate) and not consider separately. | | | | |
| 22.00 | Fluted Panel Providing and fixing of fluted panel of basic cost ₹ 1250/Sq.mt with necessary fixing arrangements. | SQ.M | 8.18 | | |
| 23.00 | ACP CLADDING Supplying and fixing aluminium composite cladding with skin material 0.5mm thick aluminum sheet cover material natural polyethylene aluminum cladding panel fixed with extruded aluminum basis frame (50x25x1.5mm) angle cleats, weather sealants, rivets, GI brackets all as approved, using suitable bolts on structural steel work including necessary accessories complete in all respects including all labour charges etc., complete for finished item of work but excluding cost of structural steel fabrication, scaffolding charges, if any, ACP Cladding - 4 mm thick | SQ.M | 30.98 | | |
| | Total | | | | |
| | DISCOUNT IF ANY | | | | |
| | GRAND TOTAL AMOUNT AFTER DISCOUNT | | | | |