

BOQ FOR INTERIOR & FURNITURE WORK WITH ALLIED CIVIL WORK AT DHUBRI BRANCH					
SI.No	Description of items	Unit	Qty	Rate(Rs.)	Amount(Rs.)
SECTION A : E-CORNER WORK					
1	Fabricating and fixing full height solid partition , made of 6 mm ply approved brand both side and to be finished with not less than 0.8 mm thick laminate of approved brand, colour and shade over 50 mm x 50 mm (thickness not less than 1.5 mm) aluminium section framework of approved brand at spacing not exceeding 600 mm both ways (horizontal and vertical). Frame should be firmly fixed to the ceiling. All exposed edge shall be covered with wood bidding/lipping of required size with polishing complete in all respect. Payment will be made for the area upto false ceiling only. Ply/Block Board Make: MR Grade of Century/ Green/Archidply/Gattani/kitply or equivalent. Laminate Make: Greenlam/Centurylam/Merinolam/Archidlam or equivalent.	SQM	9.3		
2	Providing & fixing in position Aluminium Composite Panel (ACP) / Shutter boxing Panelling with framing in 600 mm C/C both ways. Minimum 3 mm thick ACP to be fixed over the freamwork with 3M or equivalent adhesive and mirror screw in 600 width panels or distributed equally. Joints to be finished with Silicon based sealant. The shade /colour will be as per the direction of bank. Make: Alubond, Eurobond, Fujibond, Alcobond or equivalent ISO certified or approved brands to be used.	SQM	40.08		
3	False ceiling : Providing and fixing suspended false ceiling with 600x600 mm size & 12mm thick mineral fiber ceiling files of Armstrong dune or approved make. Suspender, frame work as per manufacturer's specifications. The item to include cost of making necessary cut-outs for lights/air-conditioning grills as per design direction by bank.	SQM	22		
4	Gypsum board false ceiling : Providing and fixing suspended 12mm thick Gypsum board false ceiling with GI framework of standard gauge and as per the specifications of India Gypsum Co. The rate to include painting with lustre paint and making necessary design,pattern & cut outs for light fittings, cove light etc. complete as per design direction by bank.	SQM	10		
5	Providing and fixing toughen doors made of 12 mm thick with frost film fixed in between top & bottom rail .The rate is inclusive of all necessary hinges required to installed. The rate will also includes locks and necessary hardwares such as hinge, stopper, tower bolt etc. all exposed edge sahll be covered with bidding as directed by EIC.	sqm	2.1		
6	Providing,Fixing and installation of toughen glass of 12 mm thick with frosted film as per direction by EIC.The bottom part of the toughen should be fixed on 4" height teak wood and 4" height from the top of the ceiling complete in all respect. The rate will also includes locks and necessary hardwares such as hinge, stopper etc. as directed by EIC.	sqm	31.5		
7	within 50 metres lead. For thickness of tiles 10 mm to 25 mm	sqm	27.9		
8	P.C.C WORK for creation of ramp at the entry side of the e-corner: Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:3:6 (1 Cement : 3 coarse sand (zone-III) : 6 graded stone aggregate 20 mm nominal size)	cum	7500		
10	Providing and laying checkered tiles in floor in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS:15622, of approved brand & manufacturer, in all colours and shade, laid on 20 mm thick cement mortar 1:4 (1 cement: 4 coarse sand) jointing with grey cement slurry @3.3 kg/sqm including grouting the joints with white cement and matching pigments etc. The tiles must be cut with the zero chipping diamond cutter only . Laying of tiles will be done with the notch trowel, plier, wedge, clips of required thickness, leveling system and rubber mallet for placing the tiles gently and easily.(Nitco/Kajaria/Johnson or equivalent) Glazed Vitrified tiles Matt/Antiskid finish of size Size of Tile 300 x 300 mm	sqm	21		
11	Finishing wall with two coats of acrylic emulsion exterior coatings of Unicem "Rakshak" brand of required shade by thinning 1ltr. of paint with 750ml of water to give an even shade after thoroughly brooming the surfaces to remove all dirt and remains of loose powdered materials as specified and directed by the department.The rate includes primer applied @ 2.2 Kg/10 sqm.The rate also includes applying of wall putty wherever necessary and as instructed by Bank/EIC.	sqm	250		
SECTION A : SUB-TOTAL					

SECTION B : ALLIED CIVIL WORKS

1	Dismantling tile work in floors/wall tiles etc laid in cement mortar including stacking material within 50 metres lead. For thickness of tiles 10 mm to 25 mm	sqm	150		
2	P.C.C WORK:Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:3:6 (1 Cement : 3 coarse sand (zone-III) : 6 graded stone aggregate 20 mm nominal size)	cum	3		
3	Centering and shuttering including strutting, propping etc. and removal of form for slab casting work	sqm	3.75		
4	Providing and laying in position ready mixed or site batched design mix cement concrete for reinforced cement concrete work; using coarse aggregate and fine aggregate derived from natural sources, Portland Pozzolana / Ordinary Portland /Portland Slag cement, admixtures in recommended proportions as per IS: 9103 to accelerate / retard setting of concrete, to improve durability and workability without impairing strength; including pumping of concrete to site of laying, curing, carriage for all leads; but excluding the cost of centering, shuttering, finishing and reinforcement as per direction of the engineer-in-charge; for the following grades of concrete.	cum	3		
5	Providing and laying checkered tiles in floor in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS:15622, of approved brand & manufacturer, in all colours and shade, laid on 20 mm thick cement mortar 1:4 (1 cement: 4 coarse sand) jointing with grey cement slurry @3.3 kg/sqm including grouting the joints with white cement and matching pigments etc. The tiles must be cut with the zero chipping diamond cutter only . Laying of tiles will be done with the notch trowel, plier, wedge, clips of required thickness, leveling system and rubber mallet for placing the tiles gently and easily.(Nitco/Kajaria/Johnson or equivalent)	sqm	50		
6	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto all levels. Thermo-Mechanically Treated bars of grade Fe-500D or more.	kg	120		
7	Providing and laying of inter locking concrete block pavement (ICBP) with cement concrete paver blocks as per IS 15658-2006 of thickness 80mm and 28 days compressive strength not less than 30 N/m over a layer of bedding sand of compacted thickness 30mm, laid either in stretcher/ running/ herringbone pattern of bonds as directed by the engineer and in proper level and grade and compacted with appropriate equipment such as plat vibrator along with spreading of a thin layer of joint filling sand to fill up the gaps between blocks including construction of edge restraint wherever required complete as per drawings and Technical specification clause 1504 of MORD.The rate is inclusive of dismantling/excavation of soil/P.C.C etc and making the surface with proper dressing ,complete in all respect	sqm	400		
SECTION B: SUB-TOTAL					
TOTAL AMOUNT: SECTION A +SECTION B (EXCLUSIVE OF GST)					