

PROPOSED INTERIOR WORK FOR STATE BANK OF INDIA, NIMMADA BRANCH, ANDHRA PRADESH.					
SCHEDULE OF QUANTITIES AND DETAILED SPECIFICATIONS: (INTERIOR WORKS)					
PRICE BID					
S.No.	Item. / Particulars.	Quantity.	Rate.	Unit. Amount.	
1.1	<b>FULL HEIGHT PARTITIONS: (ONE SIDE LAMINATE ONE SIDE VENEER FINISH):</b> Providing and fixing metal stud dry wall partition with following specifications: The Partition will be fully opaque OR partly glazed as per specific site conditions and drawings. (a) Supporting system comprising of 51mm / 50mm x 35mm / 34mm x 0.5mm metal studs at 600mm c/c and 51mm / 50mm x 32mm x 0.5mm metal tracks at floor, middle, door and ceiling level with joints staggered to avoid through joints. The vertical members should touch the ceiling with horizontal ceiling channel at slab / beam bottom. The rate should also include necessary strengthening with studs / tracks or channels at doors and other openings. (b) 12mm Plywood /Fiber Cement Board (UPS, Electrical room, record and stationary room only) / Calcium Silicate Board (UPS, Electrical room, record and stationary room only)/ Reinforced Magnesium Silicate Board (UPS, Electrical room, record and stationary room only) fixed on both sides with 25mm dry wall screws for the entire height of the partition. (c) Partition from floor level upto 2350mm level to have 8mm x 100mm Fiber Cement Board / Calcium Silicate Board / Reinforced Magnesium Silicate Board as Skirting clad with 1mm glossy Laminate (blue color) at bottom + from 100mm to 300mm level to have 1mm Glossy Laminate (blue color) + from 300mm level to 950mm level to have 1mm Glossy Laminate (white color) + from 950mm level to 1100mm level 1mm Glossy Laminate (blue color) + from 1100mm level to 2250mm level to have 1mm Textured Glossy Laminate (white color) + from 2250mm level to 2350mm level 1mm Glossy Laminate (blue color) on both sides as shown in drawing. (d) Partition to have 8mm clear float glass instead of 1mm Textured Glossy Laminate fixed with 85mm x 18mm alround MDF Exterior Grade jamb and 12mm x 12mm MDF Exterior Grade button beading on both sides of the glass, to a neat finish as per drawings and directions etc., complete. (e) Partition to have 1mm Laminate / NO VOC or LOW VOC plastic emulsion paint finish on both sides as shown in drawing. (f) All exposed surfaces of MDF Exterior Grade members to have minimum two coats of LOW VOC or NO VOC duco paint finish. (g) All sections used should adhere to the manufacturers guidelines and the contractor has to submit certificate from the manufacturer on usage of their specified sections. : Same as item 1.1 above to be clad with 4mm Veneer (Veneer Base Rate Rs - 1,500/- Sq.M.) from one side and 1mm Laminate from other side, (Laminate Base Rate RS. 500/- per Sq.M.) to a neat finish as per drawings and directions etc., complete.	5		Sq.M.	
1.1.2	<b>FULL HEIGHT PARTITIONS: (BOTH SIDES LAMINATE FINISH):</b> Same as item 1.1 above to be clad with 1mm Laminate ( <b>Laminate Base Rate Rs - 500/- Sq.M.</b> ) from both sides to a neat finish as per drawings and directions etc., complete.	25		Sq.M.	
1.2.1	<b>35MM THICK FLUSH DOORS IN PARTITIONS: (BOTH SIDE LAMINATE FINISH):</b> Providing and fixing 35mm thick solid core flush shutter with Fiber Cement Board / Calcium Silicate Board / Reinforced Magnesium Silicate Board with 1mm Laminate (Base Rate RS. 500/- Sq.M.) from both sides with 100mm x 15mm beech wood jamb around the opening of the partition and 12mm x 12mm button beading on one side of the partition and 8mm clear float glass with 3M privacy film fixed as per drawing with 65mm x 15mm beech wood jamb around the glass opening and 12mm x 12mm beech wood beading for fixing of glass on both sides. The rate to include necessary hardware viz., door stopper, door buffer, pair of " H " type handles, Mortise Dead Lock and Euro Profile Cylinder - Key and Knob 70mm SS, 4 Nos. SS 2 ball-bearing hinges - (127mm x 76mm x 2.5mm), door closer (all of approved make and quality), all exposed faces of Veneer and beech wood beading to have minimum three coats of melamine spray polish finish etc., complete as directed.	15		Sq.M.	
1.3	<b>HALF HEIGHT PARTITIONS: (LAMINATE FINISH):</b> Same as item 1.1.1 above, but for height of 1200mm from finished floor level, to a neat finish as per drawings and directions etc., complete and the following: (a) 6mm thick acrylic solid surface capping of 75mm on top, 50mm bands of 6mm acrylic solid surface on both sides of the partitions horizontally and vertically upto skirting as per drawings and directions etc., complete. (b) Partition from floor level upto 1100mm level on both sides to have 8mm x 100mm Fiber Cement Board / Calcium Silicate Board / Reinforced Magnesium Silicate Board as Skirting clad with 1mm glossy Laminate (blue color) at bottom + from 100mm to 300mm level to have 1mm Glossy Laminate (blue color) + from 300mm level to 950mm level to have 1mm Glossy Laminate (white color) + from 950mm level to 1050mm level 1mm Glossy Laminate (blue color) + from 1050mm level to 1100mm level to have 6mm thick acrylic solid surface on both sides as shown in drawing. (c) The cost to include all materials and hardware required etc., as per site conditions. The rate is for a finished item of work etc., complete as directed.	20		Sq.M.	
1.4	<b>FIXED GLASS WORKS: (12MM TOUGHENED GLASS WORK WITH MAIN ENTRANCE DOOR AND GLASS PARTITION DOORS) :</b> Providing, making and fixing in position Fixed 12mm / 10mm toughened glass as fixed glass from Floor to available Ceiling level along with Main Entrance Door and for Partitions. The glass is to be fixed with patch fittings and all the edges of the glass have to be polished for a smooth finish. The work includes cost of all materials, approved hardware, making necessary template before toughening of glass and fixing the same as per site conditions to a neat finished work as per drawings and directions etc., complete.	20		Sq.M.	
1.5	<b>12MM TOUGHENED GLASS MAIN ENTRANCE DOOR AND PARTITION DOORS:</b> Providing, making and fixing in position Fixed 12mm / 10mm toughened glass openable shutters work as per specifications given below and for the openings mentioned. Main Entrance Glass Work comprising of Door opening of approximate size 1800mm x 2250mm - 2400mm in two pieces, and Partition Doors of approximate size 900 - 1000mm x 2250mm - 2400mm. The entire work to be done as per site conditions with following specifications etc., complete as directed. (a) Entrance door - Providing, fixing in position glazed entrance Double door and Single door with patch fitting or approved make (Double Door approx. Size: 1800mm - 1500mm x 2400mm - 2250mm and Single Door approx. Size: 900mm - 1200mm x 2400mm - 2250mm) using 12mm / 10mm toughened glass edge polished. The Door to consist of Heavy Duty Floor spring, Upper Patch, Bottom Patch, Lock Keeper Plate, Euro Profile Cylinder (EPC), "H" Type Handle 32 x 600mm, Corner Lock and the side fixed glass to have 2 Nos. Bottom Patch and 2 Nos. Upper Patch for each door to a neat finish etc., complete as per drawing. (b) The work includes cost of all materials, approved hardware, making necessary template before toughening of glass and fixing the same as per site conditions to a neat finished work as per drawings and directions etc., complete	8		Sq.M.	
1.6.1	<b>WALL PANNELLING: (VENEER FINISH)</b> Providing and fixing metal stud Wall Paneling with following specifications: Same as item 1.1.1 above, but for Wall Panelling. The basic frame work to comprise all cladding specified only from one side to a neat job as per drawings and directions etc., complete. b) 12mm Plywood fixed with 25mm dry wall screws for the entire height of the paneling. c) Wall Panelling to have either 4mm thick Veneer (Veneer Base Rate Rs - 1,500/- Sq.M.) OR 1mm thick Laminate (Laminate Base Rate Rs - 500/- Sq.M.) and texture paint OR 1mm texture Laminate finish on both side as shown in drawing. d) Providing 15mm thick jamb for door and window openings of suitable depth as per site conditions. e) All beech wood members and faces of veneer to have melamine spray polish finish.Same as item 1.6 above to be clad with 4mm Veneer (Veneer Base Rate Rs - 1500/- Sq.M.) from one side to a neat finish as per drawings and directions etc., complete.	10		Sq.M.	
1.6.2	<b>COLUMN PANNELLING: (VENEER FINISH)</b> Same as item 1.6 above to be clad with 4mm Veneer (Veneer Base Rate Rs - 1500/- Sq.M.) from one side to a neat finish as per drawings and directions etc., complete.	2		Sq.M.	
1.6.3	<b>COLUMN PANNELLING: (LAMINATE FINISH) :</b> Same as item 1.6 above to be clad with 1mm Laminate (Laminate Base Rate Rs - 500/- Sq.M.) from one side to a neat finish as per drawings and directions etc., complete.	2		Sq.M.	

S.No.	Item. / Particulars.	Quantity.	Rate.	Unit.	Amount.
1.7.1	<b>STORAGE UNITS: (VENEER FINISH)</b> Providing, making and placing in position Storage Units with horizontal partitions of 1100mm abutting wall / abutting partition / 750mm as back credenza height made in 19mm plywood for all other members and 25mm block board for table top. The Storage Unit top of 25mm Block Board and to be clad with 6mm thick acrylic solid surface OR 1mm Laminate and the front facia and sides of the top to have 6mm thick acrylic solid surface double thickness at edges around OR 1mm Laminate / edge binding tape. All other exposed faces of the unit to have either 4mm Veneer OR 1mm Laminate as specified and 0.8mm Laminate finish on all unexposed faces and all necessary hardware viz., 'W' or wing hinges, locks, handles, tower bolts etc., etc., complete. (a) All the edges of 19mm plywood to have 20mm x 6mm beech wood edge lipping. (b) All wooden members and faces of veneer to have melamine spray polish finish. Melamine Spray Polishing to be done as per specifications given in item 2.6 below but with top 6mm thick acrylic solid surface and all other 4mm Veneer on exposed faces (Veneer Base Rate Rs - 1,500/- Sq.M.) on all exposed faces with minimum three coats of melamine spray polish finish to a finished item of work as per drawings and directions etc., complete as directed.	4		Sq.M.	
1.7.2	<b>STORAGE UNITS: (LAMINATE FINISH):</b> Same as item 1.7.1 above but with top 6mm thick acrylic solid surface and all other 1mm Laminate (Laminate Base Rate Rs - 500/- Sq.M.) from one side to a neat finish as per drawings and directions etc., complete	8		Sq.M.	
1.8.1	<b>GRID FALSE CEILING:</b> Providing & Fixing of Mineral Fibre Acoustical Suspended Ceiling System with 15mm thick Tiles and Exposed GRID. The tiles should have Humidity Resistance (RH) of 90% - 99%, NRC 0.5, Light Reflectance ≥87%, Thermal Conductivity k = 0.052 - 0.057 w/m K, Colour White, Fire Performance UK Class 0 / Class 1 (BS 476 pt - 6 &7) in module size of 600 x 600 x 16mm, suitable for Green Building application, with Recycled content of 30% - 45%. The tile shall be laid on Microline / Silhouette profile grid system with 15mm - 16mm white flanges incorporating a 6mm central reveal in white/black colour and with a web height of 38mm and a load carrying capacity of minimum 8 Kgs/M2 & minimum pull out strength of 100 Kgs. Microline / Silhouette, Main Runners & Cross Tees to have mitred ends & "birdsmouth" notches to provide mitred cruciform junctions. The T Sections have a Galvanizing of 90 grams per M2 and need to be installed with Suspension system as per manufacturers details. The Installation to comprise main runner spaced at 1200mm centres securely fixed to the structural soffit using US Boral / Gyproc / Armstrong suspension system (specifications below) at 1200mm maximum centre. The First/Last suspension system at the end of each main runner should not be greater than 450mm from the adjacent wall. Flush fitting 1200mm long cross tees to be interlocked between main runners at 600mm centre to form 1200 x 600 mm module. Cut cross tees longer than 600mm require independent support. 600 x 600mm module to be formed by fitting 600mm long flush fitting cross tees centrally between the 1200 mm cross tees. Perimeter trim to be Wall angles of size 3000mm x 19mm x 19mm, secured to walls at 450 mm maximum centres.	70		Sq.M.	
1.8.2	<b>PLAIN FALSE CEILING:</b> Note: (No separate measurements will be considered for the vertical up to 300mm height surfaces and cove lighting areas only plan are will be considered for the measurements ) Providing and fixing Concealed Grid suspended ceiling system of 12.5mm Gypsum Boards / Standard Plaster Boards fixed to ceiling Frame Work as per manufacturers instructions and details for a concealed grid key lock suspended ceiling system consisting of following: (a) 27 x 37 x 1.6mm Soffit Clip, 5mm suspension rod / 25 x 10 x 0.5mm Ceiling Angle, adjustable spring loaded suspension clip / 2.64mm dia Connecting Clip, 20 x 28 x 30 x 0.5mm Perimeter Channel, Top Cross Rail of 3000mm long of 0.55BMT Furring Channel / 15 x 45 x 15 x 0.9mm Intermediate Channel and 4000mm long made of 0.5mm BMT the Top Cross Rail / 80 x 26 x 0.5mm Ceiling Section to be suspended from ceiling at every 1200mm and Furring / Intermediate Channel to be fixed to Top Cross Rail / Ceiling Section at every 600mm to make a grid of 1200 x 600mm. (b) All sections used should adhere to the manufacturers guidelines and the contractor has to submit certificate from the manufacturer on usage of their specified sections. (c) Further the rates to include cutouts for lighting fixtures / AC grilles / Fire Alarm Detectors etc., along with necessary strengthening and supports for fixing of these. The board joints are to be flush finished with jointing compound and paper tape etc., complete as directed. The cost including 2 coats of wall care putty and one coat of primer and two coats of emulsion paint.	120		Sq.M.	
1.8.3	<b>PLYWOOD FALSE CEILING:</b> Providing and making plywood ceiling with Trap Doors in Ceiling of approximate size 1800mm x 750mm made with 50mm x 50mm hard wood frame and shutter with hard wood frame of 35mm x 35mm with 19mm marine quality plywood / block board, the exposed surface of the ceiling to be clad with 1mm thick laminate of approved shade and painted with enamel paint internally with necessary hardware viz., hinges, safety chain, lock, handle etc., complete as per drawings and directions.	15		Sq.M.	
1.9	<b>SELF WATERING FLOWER POTS WITH NATURAL PLANTS:</b> Providing and placing in position PVC Flower Post with self watering arrangement with water absorption granules and red earth etc., of base 300mm - 400mm and 600mm - 750mm tall with Indoor Plant viz., Lady Palm (Raphis Excelsa) / Peace Lily (Spathiphyllum Wallisii) / Spider Plant (Cholorophytum Comosum) / Gerbera Daisy (Ferbera Jamesonii) etc., complete as directed	6		Each.	
1.10.1	<b>BRANCH MANAGER'S EXECUTIVE TABLE AND SIDE TABLE:</b> (2100mm x 900mm x 750mm + 1200mm x 450mm x 750mm): Providing, making and placing in position Executive Table and Side Table with following specifications and per dimensions specified. (a) Tabletop and the front around facia of the table to be made in 25mm block board with 6mm thick acrylic solid surface and double thickness at edges around OR 1mm thick Laminate and all the exposed edges of the table to have 1mm Laminate or edge binding tape. (b) All other members 19mm plywood and all exposed faces of the table to have 4mm Veneer (Veneer Base Rate Rs - 1,500/- Sq.M.) OR 1mm Laminate (Laminate Base Rate Rs - 500/- Sq.M.) as specified above to be used. (c) All the edges of 19mm plywood to have 20mm x 6mm beech wood edge lipping. (d) One ready made key board tray. (Eco - KTE1 - 35 - Ebco make.) (e) One ready made hanging type pedestal for keeping CPU. (CPUSL, Ebco make.) (g) One Three Drawer Unit made with 19mm plywood and 12mm plywood. The unit to have one vertical filing drawer at bottom and two equal drawers on top. The rate to include all necessary hardware viz., telescopic drawer channels, handles, locks, etc., and 20mm x 6mm beech wood edge lipping etc., (h) All the exposed faces to have either 6mm thick acrylic solid surface OR 4mm Veneer (Veneer Base Rate Rs - 1,500/- Sq.M.) OR 1mm Laminate (Laminate Base Rate Rs - 500/- Sq.M.) of approved shade and make as specified above. (i) All the unexposed faces to have 0.8mm thick Laminate OR minimum two coats of enamel paint with putty finish. (j) A loose Ready Made Modular Foot Rest (FR2 - Ebco make.) to be provided for each table / work station. (k) All wooden members and faces of veneer to have melamine spray polish finish.Same as item 1.10 above but for Executive Table and Side Table for the Officer's of approximate size - 2400mm x 900mm x 750mm + 1200mm x 450mm x 750mm as per drawings and directions etc., complete for a finished item of work. The cost to include 6mm thick acrylic solid surface AND 4mm Veneer (Veneer Base Rate Rs - 1500/- Sq.M.) of approved shade and make as specified above for a finished item of work as per drawings and directions etc., complete.	1		Each.	
1.10.2	<b>MANGER'S TABLES:</b> (1650mm x 750mm x 750mm + 1050mm x 450mm x 750mm): Same as item 1.10.1 above but for Table and Side Table for the Officer's of approximate size - 1650mm x 750mm x 750mm + 1050mm x 450mm x 750mm as per drawings and directions etc., complete for a finished item of work. The cost to include 6mm thick acrylic solid surface AND 1mm Laminate (Laminate Base Rate Rs - 500/- Sq.M.) of approved shade and make as specified above for a finished item of work as per drawings and directions etc., complete.	2		Each.	

S.No.	Item. / Particulars.	Quantity.	Rate.	Unit.	Amount.
1.10.3	<p><b>CUSTOMER TRANSACTION COUNTERS:</b> Providing, making and placing in position Single Customer Transaction Counters along with necessary partitions as per item 1.3 above (The partitions will be measured and paid as per item 1.3 i.e., Half Height Partitions) with following specifications and per dimensions specified. The front side of the Customer Transaction Counter to have 100mm Aluminium Skirting of bottomline make, expression series, two part skirting with retainer along with curved top edge (blue color) at bottom.</p> <p>(a) The overall size of each Single Window Counter to be 1650mm - 1500mm x 900mm - 975mm x 750mm + 1050mm x 450mm x 750mm.</p> <p>(b) Tabletop of main table and side table to have 25mm Block Board to have extra thickening with 19mm x 50mm plywood and front vertical facia to have 12mm x 43mm plywood lipping clad with 6mm thick acrylic solid surface for the entire table top and the front facia and remaining all exposed faces to have 1mm Glossy Laminate as specified. The acrylic solid surface to continue in the front side with curvature from the front table top to the modesty panel in front with cove lighting provision.</p> <p>(c) All other members to be with 19mmplywood / 2 Nos. of 6mm Flexi Plywood in curvature (which should be achieved with a frame work of 50mm x 50mm sal wood frame to be fixed from the front modesty panel / apron and the bottom of this niche to have provision of cove lighting with LED strips) and all exposed faces of the table to have 6mm thick acrylic solid surface as specified in the drawing to be used.</p> <p>(d) All the edges of 19mm plywood to have 18mm x 12mm plywood lipping.</p> <p>(e) One ready made key board tray. (Eco - KTE1 - 35 - Ebco make.)</p> <p>(f) One ready made hanging type pedestal for keeping CPU. (CPUSL, Ebco make.)</p> <p>(g) One Three Drawer Unit made with 18mm plywood and plywood. The unit to have one vertical filing drawer at bottom and two equal drawers on top. The rate to include all necessary hardware viz., telescopic drawer channels, handles, locks, etc., and 20mm x 6mm beech wood edge lipping etc.,</p> <p>(i) All the unexposed faces to have 0.8mm Laminate OR minimum two coats of NO VOC or LOW VOC enamel paint with putty finish.</p> <p>(j) Ready Made Modular Foot Rest - 400mm x 350mm x 65mm.</p> <p>(k) All wooden members to have minimum two coats of NO VOC or LOW VOC duco paint finish.</p> <p>The cost to include the " L " shaped Single Window Counter and to include all materials, hardware, labour for a neat and finish job as per drawings and directions etc., complete.</p>	2		Each.	
1.10.4	<p><b>12MM TOUGHENED GLASS DIVIDERS FOR CUSTOMER TRANSACTION COUNTERS:</b> Providing, making and fixing in position 12mm thick toughened clear float glass in the half height partitions of Single Window Counters of approximate size 1150mm x 400mm - 100mm in tapered shape. All the edges of the glass to be polished for a smooth finish and the glass is to be fixed with " D " brackets. The cost to include all materials, labour, hardware etc., for a neat finished job as per drawings and directions etc., complete.</p>	1		Each.	
1.10.4	<p><b>12MM TOUGHENED GLASS IN FRONT OF CUSTOMER AND TRANSACTION COUNTERS:</b> Providing, making and fixing in position 12mm thick clear toughened glass in the front side of approximate size 1650mm x 450mm with a central cut out of 200mm x 175mm. All the edges of the glass to be polished for a smooth finish and the glass is to be fixed with " D " brackets. The cost to include all materials, labour, hardware etc., for a neat finished job as per drawings and directions etc., complete.</p>	2		Each.	
1.10.5	<p><b>PANTRY UNIT:</b> Providing, making and placing in position Pantry Unit of overall size 3000 to 3450mm x 2650mm. The bottom of the unit from FFL to 800mm level to 600mm depth and the top portion of the unit from 1400mm level to have depth of 450mm. The unit to be made with following specifications and as per drawings to a neat finish including cost all materials, hardware etc., complete.</p> <p>Storage units with horizontal partitions at not more than 900mm and the pantry unit top at 750mm level to have 19mm block board with 15mm granite and provision for 510mm x 510mm kitchen sink with pillar cock, angle cock, bottle trap and waste coupling (all of Jaguar or approved equivalent make) and all necessary hardware etc., The Storage units below and above to have all necessary hardware viz., "W" hinges, handles, locks, magnetic ball catchers etc., The back of the unit to have 9mm plywood and the central 750mm portion to have cladding with glazed tiles of 200mm x 300mm. All the vertical partitions and the shutters of the storage to have 19mm plywood. All the exposed areas of plywood to have 1mm Laminate (Base Rate of Laminate Rs. 500/- Sq.M.) of approved shade and all the internal areas to have enamel painting with putty finish on all unexposed faces including melamine spray polish finish for all wooden members and all necessary hardware viz., "W" or wing hinges, locks, handles, tower bolts etc., and beech wood edge lipping 20mm x 6mm etc., complete as per drawings and directions.</p>	1		Each.	
1.10.6	<p><b>WICKET GATE:</b> Same as item 1.1 above, but for height of 1200mm from finished floor level, to a neat finish as per drawings and directions etc.,</p>	3		Sq.M.	
1.10.7	<p><b>NIGHT LATCH:</b> Providing and fixing night latch with three lock keys for wicket gate, to a neat finish as per drawings and directions etc.,</p>	3		Each.	
2.1.1	<p><b>PLASTIC EMULSION PAINTING:</b> Cleaning the surface of the wall / ceiling and then applying one coat of Wall Care putty followed by one coat of primer &amp; then applying second coat of putty to give smooth finish exactly in line and level &amp; then finally applying a minimum of two coats of NO VOC or LOW VOC Plastic Emulsion Paint of approved shade to give a neat finish including cost of all materials necessary scaffolding etc., complete for walls &amp; ceiling.</p>	10		Sq.M.	
2.1.2	<p><b>LOW VOC OR NO VOC OIL BOUND DISTEMPER PAINTING:</b> Painting to new walls with 2 coats of ready mixed oil bound washable distemper of approved brand and shade over a base coat of appropriate primer of approved brand, making 3 coats in all to give an even shade after thoroughly brushing the surface to remove all dirt and remains of loose powdered materials, including cost and conveyance of all materials to work site and all operational, incidental, labour charges etc. complete for finished item of work.</p>	10		Sq.M.	
2.2.1	<p><b>VITRIFIED FLOORING:</b> Providing &amp; laying flooring with Full Body Vitrified Tiles (Double Charged) of approved make, shade and colour of 800mm x 800mm size of 10 / 12mm thickness laid over a flooring bed of 50mm to 75mm thick or more in CM 1:8 proportion including neat cement slurry of honey like consistency spread at the rate of 3.3 Kgs cement per Sq.M. before laying tiles on base coat and filling the joints with white cement or colour cement to match the shade of tiles including cost of base coat, cement slurry, jointing material and cost and conveyance of all materials viz., cement, sand, water, vitrified tiles, white or coloured cement etc., to site, cost of seigniorage charges on materials, labour charges for all operations etc., complete as directed, curing etc., complete for finished item of work. Alternatively approved make Tile adhesive and jointing compound can be used without any extra cost. (Base Rate for body tiles - 750/Sq.M. and Base rate for dark tiles - 850/Sq.M.)</p>	170		Sq.M.	
2.2.2	<p><b>VITRIFIED TILES SKIRTING:</b> Same as item 2.4 above but for Skirting as directions by Architect/Bank etc., complete for a finished item of work.</p>	6		Sq.M.	
2.3	<p><b>ENGINEERED WOOD FLOORING:</b> Providing, fixing and placing in position Engineered Wooden Flooring 14mm thick - Jatoba 1 Strip and Merabau 1 Strip - Natural Wood - Solid and Engineered Wood Flooring of Ego Wooden Floor or approved equivalent make to be used in ratio of 50% : 50%. The Flooring to have tongue and groove joints and to be finished with a minimum of three coats of polyurethane polish finish as directed etc., complete for a finished item of work.</p>	15		Sq.M.	

<b>S.No.</b>	<b>Item. / Particulars.</b>	<b>Quantity.</b>	<b>Rate.</b>	<b>Unit.</b>	<b>Amount.</b>
2.3	<b>ACP CLADDING:</b> Supplying and fixing aluminium composite cladding with skin material 0.5 mm thick aluminium sheet cover material natural polyethylene aluminium cladding panel fixed with extruded aluminium basis frame (50x25x1.5mm) angle cleats, weather sealants, rivets, GI brackets all as approved, using suitable bolts on structural steel work including necessary accessories complete in all respects including all labour charges etc., complete for finished item of work but excluding cost of structural steel fabrication, scaffolding charges, if any, ACP Cladding - 4 mm thick.	40		Sq.M.	
2.4	<b>ROLLER BLINDS:</b> Providing and fixing in position of Roller Blinds of approved Fabric (Fabric Cost - RS. 1,000/- per Meter) of Hunter Douglas / Mac / Vista make or approved equivalent of approved shade etc., as directed. Note: (Window opening only considered for measurement. Roller blind should cover entire window opening without any gap on all sides)	5		Sq.M.	
2.5	<b>DESIGNER FILM WORK:</b> Providing and fixing in position Designer Film with elipse design on all glasses as per draswings and heights mentioned. The Designer Film is of Harmony / 3M or equivalent approved make. The rate is for a finished item of work etc., complete as directed.	23		Sq.M.	
2.6	<b>DEEP CLEANING OF THE PREMISES :</b> Cleaning of the premises on a day to day basis and disposing the debris out of the premises to the Contractor's Yard / Landfill before the commencement of the Bank every day. The scope includes cleaning of the premises and removing the debris created by the different Contractors viz., Interiors, Electrical, Civil, AC works and disposing of the debris as mentioned. The job also includes deep / fine cleaning of the exsting premises daily and also handing over the site on day of inauguration and maintanaing the premises till that time etc., complete as directed.	1		Lot.	
<b>TOTAL FOR INTERIOR WORKS:</b>					
DISCOUNT IF ANY ( EXPRESS INTERMS OF PERCENTAGE)					
<b>NET TOTAL</b>					

Signature of Contractors