

**PRICE BID FOR INTERIOR DECORATION AND FURNISHING WORK OF SBI VRM OFFICE AT BISCOUMAN BHAWAN, PATNA**

Sl. No.	Description	Unit	Quantity	Rate	Amount
<b>1</b>	<b>CLUSTER WORK STATION</b>				
	Providing, fabricating and fixing of work station as per approved design / drawing / size (3000mm (L) approx. variable as per site condition x 750mm H x 600 D) and made with necessary 19mm Plywood (BWP) (of approved make) frame work having one side 400mm wide 3 nos of sliding drawer units (opposite to side unit) of which two are of 75mm height and the remaining height for the third drawer with telescopic channels and locking arrangement. Work top to be made with 1 mm Laminat of approved brand and shade. Arrangement for CPU stand in next end of work station., One Moulded Key Board Tray with channels, foot rest and cable manager to be provided. All visible surfaces such as front, sides, top, back, drawer outside etc. shall be laminated with 1 mm thick of approved shade and make. All invisible surfaces such as drawer inside, drawer supporting cabinet etc. shall be of 0.75mm white laminate or of approved shade.All exposed edges of plywood shall be fixed with steam beach wood beading finished with melamine polish and a footrest of 100x40mm saal wood section shall be provided with dully polished. Cost of drawer locks, brush steel finished handles and other necessary hardwares should be considered. Cost should also inclusive of paneling, lapping of edges with plywood to achieve 40mm thickness and 40mm steam beach beading and melamine polish as per design and approval of Engineer in-charges. DETAIL DRAWNG MAY REFER FOR DESIGN	Nos	72		
<b>2</b>	<b>LOW HEIGHT PARTLY GLAZED(12MM GLASS) PARTITION</b>				
	Providing, fabricating and fixing 1200mm height partitions for work station/counter with specifications as detailed in (partly glazed full ht. partition) and with following specification. 1.The supporting system comprising of gypsteel/Boral make 51mmx35mmx0.55mm at 600mm c/c and 51mmx32mmx0.55mm metal tracks at floor, middle, door and ceiling level with joints staggered to avoid through joints.The rate should also include necessary strengthening with studs/tracks or channels at doors and other openings. 2.All exposed edges of the partition shall be fixed with 12mm thick steam beach wood beading finished with melamine polish. 3.The frame work upto 900mm height from floor level be fixed with 12mm Plywood (BWP) on both sides and laminated on both sides with approved make laminate of 1mm thickness with fixing adhesive etc. Above 900mm 6mm ply (BWP) over which 6mm soft board with covered with valvet cloth of approved shade have to fix as per detail drawing as directed by engineer. 4.Partition shall be glazed partially up to 1200mm ht.(as per design drawing) above the 900mm ht. from floor level. Glazed portion of partition to be done with 12 mm plain float glass of approved make. Glass is to be fixed in steam beach wood beading and melamine polished. Vertical and horizontal groves as per drawing /site conditions to be provided. Design / pattern of partition to be as per approval of engineer-in-charge.	Sqm	230		
<b>3</b>	<b>FULLY GLAZED ENTRANCE DOOR &amp; FIXED GLAZING</b>				
	Providing and fixing 12 mm thick toughened glass for door and fixed glazing with best quality patch fittings of standard bottom aluminium profile, standard topp rofile, standard over panel patch with 15mm dia. pivot, standard patch fitting for overhauled and sidelight connector without pivot, standard lock with strike plate & EPC, H type pull handle (25x300mm) for door. Floor spring for glass door, standard corner fitting, standard side connector, SS U channel etc to be provided. Etching shall be done as per banks required pattern. The top of the glass shall be held in position in ply boxing/metal section channel of required size. Blue colour bank Logos shall be fixed on the glass as directed.	Sqm	8.15		
<b>4</b>	<b>ENTRANCE FIXED GLAZING:</b>				
	As per above specification but for fixed glazing	Sqm	33.5		
<b>5</b>	<b>FULL HEIGHT SOLID PARTITION</b>				
<b>a</b>	Providing, fabricating and fixing partitions with the following specifications in approved design/ drawing. 1.The supporting system comprising of GI sections of gypsteel/Boral make 51mmx35mmx0.55mm metal studs at 600mm c/c and 51mmx32mmx0.55mm metal tracks at floor, middle, door and ceiling level with joints staggered to avoid through joints. The vertical member should touch with horizontal ceiling/channel at slab/beam bottom. The rate should also include necessary strengthening with studs/tracks or channels at doors and other openings. 2.The height upto the false ceiling will be measured for payment but the frame work has to be raised up to the concrete ceiling/beam as support for which no extra payment will be made. 3.Fixing 9mm ply with 1mm laminate on both sides of frame up to roof/ceiling level with grooves in laminates as directed at site. Provision for suitable door frame in the partition for fixing shutter to be made and finished with French polish	Sqm	150		
<b>b</b>	Providing, fabricating and fixing partitions with the following specifications in approved design/ drawing. 1.The supporting system comprising of GI sections of gypsteel/Boral make 51mmx35mmx0.55mm metal studs at 600mm c/c and 51mmx32mmx0.55mm metal tracks at floor, middle, door and ceiling level with joints staggered to avoid through joints. The vertical member should touch with horizontal ceiling/channel at slab/beam bottom. The rate should also include necessary strengthening with studs/tracks or channels at doors and other openings. 2.The height upto the false ceiling will be measured for payment but the frame work has to be raised up to the concrete ceiling/beam as support for which no extra payment will be made. 3.Fixing 12mm calcium silicate with 1mm laminate on one sides and putty paint after joint filling with compound of frame up to roof/ceiling level	SQm	40		
<b>6</b>	<b>FULL HEIGHT PARTIALY GLAZED PARTITION</b>				

**PRICE BID FOR INTERIOR DECORATION AND FURNISHING WORK OF SBI VRM OFFICE AT BISCOUMAN BHAWAN, PATNA**

Sl. No.	Description	Unit	Quantity	Rate	Amount
	<p>Providing, fabricating and fixing partitions with the following specifications in approved design/ drawing.</p> <p>1).The supporting system comprising of gypsteel/Boral make 51mmx35mmx0.55mm metal studs at 600mm c/c and 51mmx32mmx0.55mm metal tracks at floor, middle, door and ceiling level with joints staggered to avoid through joints. The vertical member should touch with horizontal ceiling/channel at slab/beam bottom. The rate should also include necessary strengthening with studs/tracks or channels at doors and other openings.</p> <p>2).The height upto the false ceiling will be measured for payment but the frame work has to be raised up to the concrete ceiling/beam as support for which no extra payment will be made.</p> <p>3).Fixing 9mm ply (BWP) and 1mm laminate on both sides of frame up to 900mm and above 2100mm level with grooves in laminates as directed at site.</p> <p>4).8mm thick clear float glass with etching(Etching cost considered ) as directed with necessary 12mm tk. steam beach wood beading with melamine polish for heights between 900mm and 2100mm.</p>	Sqm	65		
<b>7</b>	<b>DOOR WITH DOOR CLOSER</b>				
	<p>Providing, fabricating and fixing door frame in 50mmx75m steam beach wood and fixing of 30 mm thick solid core door shutter of approved make and laminated with 1mm laminates of approved shade and make on both sides. The door shall be glazed with 8 mm float glass fixed with beach wood beading of 12mm thick and having etching work (Etching cost considered @ 500/sqm). Glazing portion of door shall be done in the same line / pattern as of the partition to which it is fixed. All open edges of door shall be leaped with beach wood beading and all wood to be finished with melamine polish. The door shall be fitted with door closer of approved make, 3 nos of heavy brass hinges, brush steel finish 6 lever mortise lock (set of three keys) and heavy door stopper and all other fittings and fixture etc. complete and as per design and approval of Engineer-in-charge. Cylindrical night latch lock at cash enclosure doors.(Godrej) or approved make)</p>	Sqm	19.5		
<b>8</b>	<b>TABLES WORK STATION</b>				
	<p>Providing, fabricating and fixing CM work station consists of Table (2400mmx900mmx750mm), side unit (1350mmx450mmx750mm) made with 19mm Plywood (BWP of approved make) as detailed below.</p> <p>1).Table should have one side 400 wide and 600mm deep storage unit consisting of Three equal height sliding drawers and arrangement for CPU stand, One Moulded Key Board Tray with channels, cable manager and foot rest of 100mmx40mm Saal wood section shall be provided and the three edges of front fascia shall be 40mm thick with additional ply and leaped with necessary steam beach wood beading dully melamine polished. The table top to be provided with 12mm plain float glass with beveling and opening for cable manager and all edges should have crystal polishing fixed with metal stud.</p> <p>2).The side unit should have 150mm ht. two equal drawers on upper side in the lengthwise and below to drawers, the cupboard unit shall be provided with openable door shutters &amp; adjustable shelf all along the full length. All drawers shall be fitted with telescopic channels and automatic push type locking arrangement and cupboards shall have locking arrangement &amp; brush steel fin. handle.</p> <p>3).All exposed edges of plywood shall be fitted with steam beach wood beading dully melamine polished. All visible surfaces such as front, sides, top, back, drawer outside etc. shall be laminated with 1 mm thick of approved shade and make. All invisible surfaces such as drawer inside, drawer supporting cabinet, inside cupboard etc. shall be of 0.75 mm white laminate of approved brand. The rates should include locking arrangement for all drawers and cupboard alongwith best quality 100mm brush steel handles, sliding telescopic channel, roller+ ball bearing arrangements etc. complete. Cost should also inclusive of paneling, lapping of edges with ply to achieve 40mm thick as per Engineer-in-charges design</p>	Nos	1		
<b>9</b>	<b>WORK STATION</b>				
<b>a</b>	<p>Providing, fabricating and fixing officers work station consists of Table (1500mmx750mmx750mm), as detailed in item no.8.</p>	Nos	4		
<b>b</b>	<p>Providing, fabricating and fixing reception counter as per detail drg. of (1500mmx750mmx750mm), as detailed in item no.8</p>	Nos	1		
<b>9</b>	<b>FALSE CEILING(GYPSUM BOARD)</b>				
	<p>Providing and fixing of false ceiling made of 12mm thick gypsum board (flat type) with necessary opening for light fittings as shown in the drawing. False ceiling shall be fitted to GI frame as detailed below.</p> <p>Ceiling channel (MF5) of size 80mm x 26mm x 0.5mm at every 457mm c/c. Intermediate channel (MF7) 15mm x 45mm x 0.9mm at every 1220mm c/c. Perimeter channel (MF6A) 20mm x 26mm all along wall.</p> <p>Strap hanger (MF8) on suspending the frame work 25mmx0.5mm with nuts and bolts(PS26) 6.4mmx 12.7mm. Connecting clip (MF9) of 2.64mm thick.</p> <p>Dry walls screw of 25mm long</p> <p>Dash fastener12.5mm diax35mm long with 6mm dia bolt. The gypsum boards are to be jointed and finished so as to have a flush look which includes finishing the edges of the board with jointing compound, paper tape etc. The rate should include painting one coat of primer and putty and two coats of Asian Interior Plastic Emulsion of white shade.(measurement will be on area only for all types of width</p>	Sqm	600		
<b>10</b>	<b>ARMSTRONG/ NITTOBO GRID FALSE CEILING</b>				

**PRICE BID FOR INTERIOR DECORATION AND FURNISHING WORK OF SBI VRM OFFICE AT BISCOUMAN BHAWAN, PATNA**

Sl. No.	Description	Unit	Quantity	Rate	Amount
	Providing & Fixing of Armstrong Mineral Fibre Acoustical Suspended Ceiling System as per the design including all necessary fixtures, fasteners, additional stiffening members for the light fixtures panel, all complete with MINATUFF TEGULAR TILES WITH ARMSTRONG SILHOUETTE SUS. EXPOSED GRID as per manufacturer's specification. The tiles should be white Colour and in the size of 600 X 600 X14 mm with Bio Block coating on the face of the tile. The tile shall be laid on Armstrong Silhouette profile grid system with 15mm white flanges incorporating a 6mm central reveal in white colour and with a web height of 45mm and a load carrying capacity of minimum 15.68 Kgs/M2. Silhouette, Main Runners & Cross Tees to have mitred ends & "birds mouth" notches to provide mitred cruciform junctions. Installation: To comprise main runner spaced at 1200mm centers securely fixed to the structural soffit using Armstrong suspension system (specifications below) at 1200mm maximum centre & not more than 150mm from spliced joints. The First/Last Armstrong suspension system at the end of each main runner should not be greater than 600mm from the adjacent wall. 1200mm long cross tees to be interlocked between main runners at 600mm centre to form 1200 x 600 mm module. Cut cross tees longer than 600mm require independent support. 600 x 600mm modules to be formed by fitting 600mm long cross tees centrally between the 1200 mm	Sqm	400		
11	<b>Wooden ceiling framing as per item no. 8, finish with 1 mm laminate over 10mm BWP ply</b>	Sqm	50		
12	<b>WALL/ COLUMN PANELLING:</b>				
	Providing, and fixing of wall/column paneling made with 9mm plywood glued with 1mm thick lamination over Gypsteel / Boral makes 51mm x 35mm metal studs as detailed in (Full height partition) above. The rate should be inclusive of providing cove texture painting in between and covered with 10mm float glass of required size and providing steam beach cornice between paneling and The necessary provision in framework for running of Electrical conduit has to be made.(contractor should ensure that pipes are laid before proceeding)	Sqm	160		
13	<b>STORAGE UNITS:</b>				
	Manufacturing & fixing in position all height storage wardrobes as per design as detailed at site by the Bank. The storage unit is to be made out of 8mm plywood on the back side and 18mm plywood on the remaining sides including shelves. The exposed edges of the plywood are to be topped with 1mm laminate while the back and inner surfaces are to be finished with .8mm laminate with. Rates quoted to include all necessary hardwares like hinges, locks, tower bolts, powder coated handles etc. all complete. The exposed edges of the ply to be fitted with teakwood lippings duly finished with melamine polish	Sqm	22		
14	<b>ROLLER BLINDS</b>				
	Supplying and fixing of Roller blinds in position at all levels with louver made of approved fabric. The louvers are to be treated with Scotch Guard. The blinds should be provided with head channel, end control unit, installation bracket etc., complete as per manufacturer's specs and approved Brand as per the direction of Engineer-in-charge.(D Decor, or equivalent	Sqm	130		
15	<b>Conference hall table</b>				
	Providing, fabricating and fixing conference hall table (7000mmx1500mmx750mm), made with 19mm Plywood Maranie Grade (of approved make) as detailed below. All exposed edges of plywood shall be fitted with steam beach wood beading duly melamine polished. All visible surfaces such as front, sides, top, back,etc. shall be finished with 4mm thick veneer of approved shade. Rate is inclusive of fixing cable manager, cabling arrangements, foortrest etc as per detail drawing. All invisible surfaces shall be of 0.75 mm laminate of approved brand and matching with veneer (As per detailed drawing ).	EACH	1		
16	<b>MISC. Items</b>				
a	Providing and fixing SS letters Grade of steel used to make letters 202/304 Grade. Customize design of stainless steel letters .size from 300mm (top to bottom) ss letters thickness 40mm. Gloss/ Mirror Finish Steel. (Letter to be writtten SBI with logo and name of Branch)	LS	1		
b	Providing and fixing in position ecosolvent 3D digital printed 3M film of approved design. Rate is inclusive of fixing with adhesive of approved brand and quality.	Sqm	60		
c	Providing and applying 2mm thick Granules trowel finish combination of specific coated stones or sand in a 4-coat system- 1 coat of base primer (50µm-60 µm) of required colour as approved by the architect/engineer in charge by Brush/Roller, 1 coat of Granules (0.8mm to 1.2mm) thickness(with steel trowel, 1 coat of clear matt/gloss finish top coat(30µm-40µm).Above application is to be carried out on the single/double coat smooth mala plaster	Sqm	60		
d	Providing and fixing PVC LOUVERS TEXTURE of approved pattern and design	Sqm	40		
e	Poviding and fixing Artificial Grass Wall Panel, Boxwood Hedge Wall Panels UV Protected Suitable for Artificial Green Wall Décor as per approved make and design.For Ceiling	Sqm	20		
17	Providing and applying plaster of paris putty of 2 mm thickness over plastered surface to prepare the surface even and smooth complete.	Sqm	615		
18	Wall painting with premium acrylic emulsion paint of interior grade, having VOC (Volatile Organic Compound ) content less than 50 grams/ litre of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour.Two coat	Sqm	665		
<b>TOTAL (Excluding GST)</b>					