

PRICE BID FOR ELECTRICAL WORK OF STATE BANK OF INDIA, BRANCH AT BABA BAKALA					
BILL OF QUANTITIES (ELECTRICAL INSTALLATION)					
S. No.	Item	Quantity	Units	Rate	Amount
1	SUB HEAD 1 (COMPUTER POINTS AND DISTRIBUTION)				
1	Supply all materials, receiving, storing, handling, fixing and laying 3 x 2.5 sq.mm PVC insulated copper conductor armoured cable and fixing of cable on wall with suitable size of clamps/saddles or laid in floor or recessed wall including cutting of floor/wall for computer points with suitable size GI Box with modular plate and cover in front including providing and fixing 3 no. 5 amp 5 pin modular sockets controlled by 1 no. 5Amp switch with indicator, connection end terminations with suitable size of glands etc. complete as required. (Only two points can be connected in series with single cable)	24.00	Each		
	3 points for BM Cabin , 2 points for Networking Equipment's in Banking Hall and 2 per SWC				
2	As per item 1 above but with 2 no. 16 amp 6 pin modular sockets controlled by 1 no. 16 amp modular switch and 6 amp indicator Lamp including the cover plate.	4.00	Each		
	As per item 1 above but with 1 no. 16 amp 6 pin modular sockets controlled by 1 no. 16 amp modular switch and 6 amp indicator Lamp including the cover plate.	1.00	Each		
3	Wiring for lightpoints/ceiling points/ Exhaust Fans point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable in surface recessed medium class pvc conduit with modular switch, modular plate suitable gi box and earthing the point with 1.5 sq mm FRLS PVC insulated copper conductor single core cable etc. including circuit wiring with 2 X 2.5 sq. mm +1 x 1.5 sq. mm earth wire as required (HT upto 4.5 m from floor)				
(a)	1 no light controlled by 1 no switch	25.00	Each		
(b)	2 no light controlled by 1 no switch	35.00	Each		
(c)	5/6 pin 6 amp plug point with 6 amp switch	14.00	Each		
4	Extension of wall fans:				
	Extension of existing points with 2x1.5 sq.mm. PVC insulated copper conductor cable in suitable dia MS conduit in recess conduit wiring system for wall fan points with modular switches of 6 amp and 5 amp 5 pin modular sockets as per requirement and filling chassis etc complete as reqd. socket to be fixed 1.5 foot below false ceiling and switch to be fixed at Normal Height.	22.00	no.		
5	Providing & laying following sizes of PVC insulated copper conductor cable of 1100 V in flexible/PVC conduit with accessories such as glands, bends etc.(as per requirement) including making necessary Inter connection etc complete as reqd.				
	2 x 6 sq.mm with 1 no. suitable PVC insulated earth wire	20.00	mtr.		
6	Supply Installation, testing & commissioning of factory fabricated distribution board rust inhibited, powder coated Sheet sheet fabricated comprising of incoming & outgoing isolator & MCB's neutral link or neutral bus,top and bottom detachable entry earthing bolts Interconnection and grouting bolts etc complete as require as per details below:-				
a)	12 way MCBDB comprising of 1 no. 63 amp DPMCB "C"Series and 10 no. 6/10amp SPMCB's "C" SERIES. (for the UPS points each DB to be connected to 12 UPS points i.e only two points shall be connected with one MCB)	2.00	each		
b)	6 way MCBDB comprising of 1 no. 63 amp DPMCB "C"Series and 4 no. 6/10amp SPMCB's "C" SERIES. (for the UPS points each DB to be connected to 12 UPS points i.e only two points shall be connected with one MCB)	2.00	each		
c)	4 way TPDB comprising of 1 no. 100 amp 4 pole isolator and 6 no. 16/25 amp DPMCB (for Ac's). To be fixed in Banking Hall. DPMCB must be of C Series.	1.00	Each		
d)	4 way TPDB comprising of 1 no. 100 amp 4 pole isolator and 12 no. 16/25 amp SP MCB. To be fixed in Banking Hall. DPMCB must be of C Series. Power circuit	3.00	Each		
e)	4 way DB comprising of 1 no. 63 amp 4 pole TPNMCB (for UPS I/C).	1.00	Each		
f)	4 way DB comprising of 2 no. 32 amp DPMCB (for UPS) "C " Series	3.00	Each		
g)	4 way(8+12 module) TPDB comprising of 1 no. Four pole 63Amp, 30mA ELCB, 1 no. 63Amp TPN MCB C series and 12 nos. 6/10 amp SPMCB C Series. (For the lighting circuit)	1.00	each		
7.1	Providing and fixing, testing and commissioning of Heavy Duty modular air-conditioning plug & socket arrangement:				
a	16 amp air-conditioning point modular type socket { to be fixed 1.5 foot below false ceiling } with 16 amp SPMCB C SERIES { to be fixed at Normal Height }.	6.00	each		
	As per the Plan provided by the Architect for Split A.C.				
7.2	Supply, installation, testing and commissioning of following capacity 3 pin metal clad industrial type plug and socket arrangement with plug top, cap and chain controlled by under noted capacity: (Make: Havells/Standard/Legrand/L&T)				
a	25 Amp with 25 Amp. DP MCB for A.Cs (for 2.0 TR Cassette AC's)	2.00	each		
7.3	Supply, fixing and testing of following 3 pin metal clad industrial type plug & socket arrangement with plug top cap & chain controlled by 1 No. MCB				
a)	20/25 amp with 20/25 amp SPMCB (one for making the plug socket arrangement for the record room so that the supply is connected only when the plug is inserted in the socket outside the record room/locker room/stationary room for fire safety)	3.00	no.		
8	Providing & fixing suitable size of MS box fabricated with 16 S.W.G.M.S. sheet either In recess wall or on surface to accommodate dedicated earth from earth electrode and further distribution of earth to computer points including providing 5mm backalite sheet on base connector strip and painting of box etc complete as reqd.	1.00	job		

S. No.	Item	Quantity	Units	Rate	Amount
9	Supply and Installation of power plug point (Raw Power Point) 16A, 6pin with 2 x 2.5 sq.mm + 1 x 1.5sq.mm copper conductors , including the modular switches, sockets and plates Including the cost of 2mm thick PVC conduits. (Switches : Make: Crabtree/North-West/ MK) (Wires Make: Polycab / Havells /Finolex {one points to be provided per circuit.})	12.00	each		
10	Supply and Installation of power plug point (Raw Power Point) 6A, 6pin with 2 x 1.5 sq.mm + 1 x 1.0sq.mm copper conductors , including the modular switches, sockets and plates Including the cost of 2mm thick PVC conduits. (to be provided on top of table) (Switches : Make: Crabtree/North-West/ MK) (Wires Make: Polycab / Havells /Finolex {Two points to be provided per circuit.})	12.00	each		
	TOTAL SUB-HEAD -1				
	SUB HEAD 2(PANELS & CABLES)				
1	Providing & fixing 3 No.200 amp kit-kats (fuse carrier & base) with 1 no. neutral link on suitable size of bakelite sheet of thickness not less than 6 mm etc. complete as reqd.	1.00	job		
	MAIN PANEL				
2a)	Supply at site installation, testing & commissioning of panel fabricated with 16 S.W.G.M.S. sheet. The panel shall be free standing type totally enclosed dust & vermin proof construction with rubber gaskets. The floor mounting panel shall have ISMC mounting channels, G.1. earth bus bar, bus bar chamber cable alleys interconnections with solid bar/PVC insulated copper conductor as per requirement, and suitable supports of bus bars. The panel shall be painted with 2 coats of enamel paint (grey shade)over the primer and shall also be provided with designation of incoming & outgoing feeder as per details below-				
	INCOMING				
a)	160 amp MCCB 4 pole with 36 KA breaking capacity at 415 Volts/ HIGHEST AVAILABLE.				
b)	1 set of 200 amp TPN aluminium bus-bar chamber				
c)	1 no. 0-500 V Voltmeter with selector switch in a separate compartment and amp meter with selector switch and one set of CT's (3 no.) with CT ratio 200/5 with LED type indication lamps with protection fuses in a separate compartment				
	OUTGOING				
a)	2 nos 63 AMP 3 pole MCCB (MCCB'S WITH 25KA BREAKING CAPACITY at 415 Volts. / HIGHEST AVAILABLE).	1.00	set		
b)	2 nos 100 AMP 3 pole MCCB (MCCB'S WITH 25KA BREAKING CAPACITY at 415 Volts. / HIGHEST AVAILABLE).				
c)	1 nos 125 AMP 4 pole MCCB (MCCB'S WITH 36KA BREAKING CAPACITY at 415 Volts. / HIGHEST AVAILABLE).				
3	Supply, installation, testing & commissioning of PVC insulated PVC sheathed armored cable of 1100 V (IS-1554 part I) and fixing of cable on wall with suitable size of clamps/ saddles or laid in floor/recess wall including cutting of floor/wall and making good the damages etc. complete as reqd. of following sizes:-				
a)	3.5 x 70 sq.mm. aluminium conductor with 2 no. 8S.WG.G.1. wire (from the Meter to kit-kat to the Main panel)	40.00	per mtr.		
b)	3.5 x 50 sq.mm. aluminium conductor with 2 no. 8S.WG.G.1. wire (from the Genset to the Change over and from change over to the essential panel, from the main panel to the essential panel.)	60.00	per mtr.		
c)	3.5 x 25 sq.mm. aluminium conductor with 2 no. 8S.WG.G.1. wire (essential panel to UPS I/C)	120.00	per mtr.		
d)	4 x 10 sq.mm. aluminium conductor with 1 no. 8 S.WG. G.1. wire (from the essential panel to the Lighting DB)	90.00	per mtr.		
e)	3 x 6 sq.mm copper conductor (for UPS DB)	110.00	per mtr.		
f)	4 x 4 sq.mm copper conductor (for AC)	70.00	per mtr.		
4	End termination with Brass compression glands including providing lugs/ferruls and making necessary connections etc. complete as reqd. of following sizes:-				
a)	3.5 x 70sq.mm. aluminium conductor	2.00	each		
b)	3.5 x 50sq.mm. aluminium conductor	4.00	each		
b)	3 x 2.5 sq.mm. copper conductor	22.00	each		
c)	3.5 x 25 sq.mm. aluminium conductor with 2 no. 8S.WG.G.1. wire	4.00	each		
d)	4 x 10sq.mm. aluminium conductor	4.00	each		
e)	3 x 6/ 4 X 4 sq.mm copper conductor	4.00	each		
5	Providing & fixing suitable size of angle iron frame suitable for installation on wall/floor including grouting of frame & painting etc. complete as reqd. comprising of the following:				
a)	1 NO.4 pole 200 amp capacity changeover switch	1.00	job		
6	Providing & fixing 16 S.W.G. M.S. Sheet adapter box, and also base frame for installation of M.C.B. D.B.'s plug & socket arrangement and to cover cables in system room including painting etc. complete	1.00	sqmt.		
	ESSENTIAL MAIN PANEL (EMP)				
2b)	Supply at site installation, testing & commissioning of panel fabricated with 16 S.W.G.M.S. sheet. The panel shall be free standing type totally enclosed dust & vermin proof construction with rubber gaskets. The floor mounting panel shall have ISMC mounting channels, G.1. earth bus bar, bus bar chamber cable alleys interconnections with solid bar/PVC insulated copper conductor as per requirement, and suitable supports of bus bars. The panel shall be painted with 2 coats of enamel paint (grey shade)over the primer and shall also be provided with designation of incoming & outgoing feeder as per details below-				
	INCOMING				
a)	125 amp MCCB 4 pole WITH 36 KA breaking capacity AT 415 VOLTS.				
b)	1 set of 200 amp TPN aluminium bus-bar chamber				

S. No.	Item	Quantity	Units	Rate	Amount
c)	1 no. 0-500 V Voltmeter with selector switch in a separate compartment and amp meter with selector switch and one set of CT's (3 no.) with CT ratio 200/5 A with LED type indication lamps with protection fuses in a separate compartment				
	OUTGOING				
a)	1 NO. 100 amp 3 pole MCCB , 4 -63 AMP 3 pole MCCB and 1 No. Space for 100amp switch with separate neutral link. (MCCB'S WITH 25KA BREAKING CAPACITY at 415 Volts.)	1.00	set		
	TOTAL SUB -HEAD 2				
	SUB-HEAD 3 (EARTHING)				
1.1	Supply & fix copper plate earth station with 600x600x3mm thick copper plate including all accessories such as watering pipe & funnel and providing masonry enclosure at top with cover plate i/c excavation of pit supplying & filling of salt charcoal, refilling of pit etc complete as reqd as per IS 3043-1987. The voltage between neutral & earth must be below 1 volt.	1.00	set		
1.2	Supply & fix G.I. plate earth station with 600x600x6mm thick G.I. plate including all accessories such as watering pipe & funnel and providing masonry enclosure at top with cover plate i/c excavation of pit, supplying & filling of charcoal, refilling of pit etc complete as reqd as per IS 3043-1987 (for the neutral earthing from the point of neutral link beside the fuse connection and second for the body earthing connected to both panel body and the ups base panel)	2.00	set		
	NOTE: chamber for the earthing shall be available at site without it the earthing cost shall not be paid for all the Earthing You are also required to provide picture of earthing taken at the time of execution of the same.				
2	Supplying and laying 20 mm X 3 mm copper strip at 0.50 meter below ground as strip earth electrode, including connection/ terminating with nut, bolt, spring, washer etc. as required	3.00	mtr.		
3	Supplying, fixing & termination of 32 mm X 6 mm GI strip with earth station below ground level and on wall saddle etc complete as reqd.	6.00	mtr.		
4	Providing & fixing 8 S.W.G. Cu earth wire on surface or in recess for loop earthing etc. as reqd.	25.00	mtr.		
5	Providing & fixing 6 S.W.G.G.I. earth wire on surface or in recess for loop earthing etc. as reqd.	60.00	mtr.		
6	Supply & laying following dia 2 mm in thickness PVC pipe under floor or in recessed walls from earth electrode to UPS room for computer dedicated earthing, for data cabling, electrical cabling etc. including providing 1 no. G.I. pull wire for data cabling making good the damages etc. wherever reqd.				
a)	25mm	90.00	mtr.		
	TOTAL SUB-HEAD -3				
	SUB HEAD 4 (NETWORKING)				
1	Wiring for computer networking starting from mounting rack with UTP CAT-6 cable in 2 mm thick 25mm dia ISI mark PVC conduit with accessories such as bends, junction boxes including providing and fixing I/O plates and SMB complete with all networking accessories etc complete as reqd.	26.00	no.		
2	Installation, testing and commissioning of 24-port unmanaged switch 10/100 full duplex complete as reqd. (to be supplied by the bank)	0.00	no.		
3	Supply, installation, testing and commissioning of 24-port Patch Panel	2.00	no.		
4	Supply installation. testing and commissioning of mounted rack 15" height made of powder coated MS sheet.	1.00	no.		
5	Supply, fixing and commissioning of patch cable Cat-6 complete with 2 no. connectors etc. complete as reqd.				
a)	1m long	26.00	no.		
b)	2m long	14.00	no.		
c)	Supply, fixing and commissioning of cable Cat-6 complete with 2 no. connectors or as required etc. complete as reqd including upvc 19mm dia. pipe conduit of heavy duty.	50.00	mtr.		
6	Wiring for telephone points with 0.6 mm dia 2 pair insulated annealed tinned electrolatic copper conductor in 2 mm thick 25 mm dia ISI marked PVC conduit complete with accessories such as bends, junction boxes etc. with suitable size of G.I. box modular plate and cover in front on surface or in recess including providing and fixing modular type telephone socket outlet and making necessary connections etc. complete as reqd.	12.00	no.		
7	Supply, fixing and commissioning of 20 pair tag block for telephone points. (box and strips Krone make)	1.00	no.		
	TOTAL SUB -HEAD 4				
	SUB-HEAD 5 (AIR CONDITIONING PIPING WORK)				
1	Supplying & Laying of following COPPER REFRIGERANT PIPING Thickness 22 SWG For Hi-wall Split AC complete with fittings Suction / Discharge line insulated with 12 mm SUPERLON / ARMAFLEX suction line, with wall cutting including making good the damages etc. Complete as required.. Multi-runs between Indoor & Outdoor units shall be considered as ONE length for the purpose of measurement.				
a	1/4" + 1/2" Refrigerant piping - For 1/ 1.5 ton Hi wall Split AC's	140.00	per mtr.		
b	5/8 " + 3/8" for 2 /3 ton HWS / Cassette AC	60.00	per mtr.		
2.1	Supply and laying following 25mm (confirming to ASTM D1785 standard) in thickness, heavy duty PVC pipe under floor or recessed in walls for AC drains, { To nearest To including bends, Tees etc as required complete in all respect	110.00	per mtr.		
2.2	Supply and laying following 32mm (confirming to ASTM D1785 standard) in thickness, heavy duty PVC pipe under floor or recessed in walls for AC drains, { To nearest To including bends, Tees etc as required complete in all respect	75.00	per mtr.		

S. No.	Item	Quantity	Units	Rate	Amount
2.3	Supply & fixing of 4mm insulation on drain pipe to be laid above the false ceiling	100.00	per feet		
3	Electrical flexible cable of 3 x 2.5sq.mm FRLS Cu cable multi strand suitable for 2 Tr H.W Split & 1.5 Tr H.W Split. (Make: Polycab/Havells/Finolex) (for power supply to indoor unit)	100.00	per mtr.		
4	Electrical flexible cable of 4 x 2.5 sq.mm FRLS Cu cable multi strand suitable for 2 Tr H.W Split & 1.5 Tr H.W Split. .(Make: Polycab/Havells/Finolex)(indoor to outdoor unit connection)	200.00	per mtr.		
	TOTAL SUB-HEAD 5				
	<u>SUB HEAD 6 (SUPPLY OF FANS & FIXTURES)</u>				
1	Supply and Installation of 36 watt. LED fitting crompton greaves (or equivalent) LCTLRN-36-FO-CDL complete as required	30.00	no.		
2	Supply and Installation of 15 watt. LED fitting crompton greaves (or equivalent) LSDRMN-15 W-CDL complete as required	36.00	no.		
3	SITC of 5 watt LED fixtures /dowlighters with essential driver in trophy case including making necessary arrangement for mounting the fixtures and connection with 2 x 1.5 sq.mm insulated copper cable from adjacent point in PVC flexible pipe etc complete as reqd. Make Phillips or equivalent of Wipro / Havells.	15.00	no.		
4	Supply and Installation of 400/450 mm sweep metal body and metal blades Turbo 180, USHA make or equilaent Crompton/Havells	22.00	no.		
5	Supply and Installation 4.5/5 Watt LED strip light for cove with Driver (M/s. Philips Wipro / Crompton) Complete in all respects required shade warm white/ blue as per requirement.	40.00	MTR.		
6	Supply and Installation of Batten type LED fitting 18 watt LCTL-18-CDL OF CROMPTON OR EQUIVALENT OF PHILIPS/WIPRO	15.00	no.		
7	Supply and Installation of 48", 35 watt BLDC sweep ceiling fans complete with regulator, hanging shackle & suitable down rod as per site conditioning complete as reqd. (M/s Crompton high breeze or equivalent of USHA / Atomberg)	4.00	no.		
8	Supply and Installation of 250 mm (sweep) metal body exhaust fans complete with self opening louvers/shutters etc. complete as reqd. (M/s Crompton or equivalent of USHA / Havells)	6.00	no.		
9	SITC of 30 watt street light/flood light for lighting the front side of the branch(M/s Crompton Cat No. LSTS-30-CDL or equivalent of Philips/Wipro.	3.00	no.		
10	TEMPORARY CONNECTION OR WIRING FOR SMOOTH RUNNING OF BRANCH	1.00	JOB		
11	BUY BACK (All the old DB, wires, cables, light fixtures, Wall Fan, ceiling fan , Exhaust fan and LED Lights are to be included in Buy back) . Bank's decision will be final for giving/not giving of material in buy back.	-1.00	JOB		
12	Buy back of 1.5Ton Split Ac. Bank's decision will be final forgiving/not giving of material in buy back.	-5.00	no.		
	TOTAL SUB - HEAD 6				
	TOTAL SUB-HEAD-1				
	TOTAL SUB-HEAD-2				
	TOTAL SUB-HEAD-3				
	TOTAL SUB-HEAD-4				
	TOTAL SUB-HEAD-5				
	TOTAL SUB-HEAD-6				
	TOTAL OF THE SUB-HEADS-(1-5) A				
	TOTAL OF THE SUB-HEADS-(6) B				
	SUB TOTAL(A+B)				
	NOTE: GST SHALL BE PAID EXTRA				