

PRICE BID FOR AIR CONDITIONING WORK OF STATE BANK OF INDIA FOR CHHATRAL BRANCH.					
Sr.No.	Description	Quantity	Unit	RATE	AMOUNT
[A]	<b>AIR CONDITIONING WORK</b>				
[I]	<b>MACHINE PART</b>				
[a]	<b>AC EQUIPMENT WITH - INVERTER COMPRESSOR</b>				
1	Supply & providing of <b>4 way Inverter Cassette Type AC</b> ceiling mounted cassette unit with indoor and out door having <b>eco friendly</b> refrigerant (R32/ R410A). Including indoor unit outdoor unit. decorative grille and cordless remote Machine shall have <b>copper condensor</b> Unit, Make: Daikin/ Mitsubishi Heavy Industries/Toshiba/ . [Mini 5 Star rating as per BEE Guide Line 2022] <b>(Non Inverter will be strictly rejected)</b>				
a	Inverter 4-way Cassette of 4.0 TR.( 3 Phase Compressor Only.) [For Banking Hall]	1	NO		
a	Inverter 4-way Cassette of 3.0 TR.( 3 Phase Compressor Only.) [For Banking Hall]	1	NO		
2	Supplying & providing of <b>Hi-wall Inverter Split Type AC</b> with high wall mounted indoor and out door unit. having <b>eco friendly</b> refrigerant. Including indoor unit outdoor unit. and cordless remote Machine shall have <b>copper condensor</b> Unit , Make: Daikin/ Mitsubishi Heavy Industries/Toshiba/Hitachi/Voltas/blue star/Carrier <b>[Mini 5 Star rating as</b>				
2.a	Inverter Hi-wall Split AC of 1.00 TR [Manager Cabin]	1	NO		
<b>TOTAL FOR PART- I</b>				<b>Rs.</b>	
[II]	<b>LOW SIDE WORK</b>				
1	Installation of IDU & ODU of 4.00 TR/3.00/2.00 TR ceiling mounted cassatte unit with first oil & gas charge & commissioning etc. Rate including ceiling mounted suspension Kit etc complete	2	NO		
2	Installation charges for above 2.0TR/1.50TR/ 1.00 TR Split A/C including installation of 5.0 Rmt copper tubing and electrical wiring connection etc. complete.	1	NO		
3	Referigerant piping - insulated 0.80mm wall thicknees copper tube of Mandav/ Totalline make between indoor to out door unit of 4.00/3.00/2.00 TR ceiling mounted cassette unit with 4.0 Sqmm 4 Core copper flexible cable of Finolex / R R Kable/Havells/CEI make. The copper piping shall be insulated with 13mm thick Nitrite rubber insulated of 'O' Class of K Flax/Armaflex/ Superlon Make	20	RMT		
3[a]	Referigerant piping - insulated 0.80mm wall thicknees copper tube of Mandav/ Totalline make between indoor to out door unit beyong 5 Rmt dist. Of 1.0 TR/1.50TR/2.00 TR Hiwall split unit with 1.5 Sqmm 3 Core copper flexible cable of Finolex/R R Kable/Havells/CEI make. The copper piping shall be insulated with 9 mm thick Nitrite rubber insulated of 'O' Class of K Flax/Armaflex/ Superlon Make (copper pipe concealed in inside wall)	4	RMT		
4	25/32 mm Dia UPVC drain pipe with insulation of Dutron/Supreme/Astral make - schedule 40 pipe, white in colour, joint properly glued with UPVC adhesive for water outlet from indoor unit. (drain pipe concealed in inside wall)	20	RMT		
5	Providing ,Fabricate and Fixing M.S stand Plateform for keeping outdoor unit of Cassette for Cassette A/C. including painting [Drawing should be prepared by the vendor and approved by the Architects]	65	KG		
6	Misc Civil Work for entire AC work of Branch (including jari in wall and jari filling , hole filling with cement mortar and finishing with core cutting putty. This also include Removing of Flooring Tiles and Providing Drain pipe during shifting of Ac and refixing of same color tiles properly) This work is for entire Branch Air Conditionoing System.	1	Lot		
<b>TOTAL FOR PART- II</b>				<b>Rs.</b>	
<b>TOTAL AMOUNT ( I + II )</b>				<b>Rs.</b>	
<b>+ GST AS APPLICABLE</b>					

**Tender Amount(In Words) Rupees:**

Sr.No.	Description	Quantity	Unit	RATE	AMOUNT

(SIGNATURE OF TENDERER/FIRM)

NAME OF TENDERER

(SEAL OF FIRM)

PLACE:

DATE: