

PROPOSED INTERIOR AND FURNISHING WORKS AT NEW PREMISES OF BIRSINGHPUR BRANCH UNDER RBO-7 SATNA

| S.No. | Description of Item | Unit | Qty | Rate | Amount |
|-------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------|---------|------|--------|
| | Interior Works : | | | | |
| | Mode of Measurements : Area of exposed and finished surfaces will be measured. | | | | |
| | False Ceilings : | | | | |
| 1 | Gypsum Board False Ceiling : | | | | |
| | Providing, making and fixing Gypsum Board False Ceiling :- 12.5 mm thick G.I. Perimeter Channels of size 0.55mm thick. G.I. intermediate channels of size 45mm from the soffit at 900mm centres with ceiling angle of width 25mm X 10mm X 0.55mm thick intermediate channel at 450-600 mm c/c Two coats of primer + two or more coats of plastic emulsion paint Note - Including all fittings,material, labour,cut outs required for light fixtures, Speakers, screws and joint paper/fibre tape etc. complete. (make saint Gobian, Gypboard or EQ) | Sq.ft | 780.00 | | |
| 2 | Cove in ceiling : | | | | |
| | Same as above but providing, making and fixing Gypsum cove (inside height 150 - 200 mm and border 75 mm) to hide strip/cove light in ceiling or to act as pelmet for roller blinds on windows or for projector screen, etc. | Rft | 250.00 | | |
| 3 | Mineral Fibre Grid Tile Ceiling : | | | | |
| | Mineral Fibre Acoustic Ceiling Tiles : Providing, making & Fixing at all heights & in spirit level, Acoustical Ceiling System @ Office areas with Armstrong, mineral fibre acoustical suspended ceiling system as per Manufacturer's specification with pin- hole tiles, tegular edge with 24 mm exposed grid. The tiles should have Colour White, in module size of 600mm x 600mm x 15mm. with providing and fixing Hot dipped galvanised Steel suspension system Grid frame with butterfly clips, for laying of Acoustical Ceiling Tiles as per manufacturer's specifications. The grid should be laid on Armstrong/Gyproc or equivalent stitched True lock 24 TL exposed grid systems with 24 mm wide T-section flanges color white, the tile will be laid on frame work made of Armstrong Prelude 32 with 24 mm wide T-section flanges or of equivalent make, colour white having rotary stitching on all T sections i.e. the Main Runner, 1200 mm & 600 mm Cross Tees with a web height of 32 mm and 27mm ,25 mm respectively. The cost shall include all fittings and materials complete including proper installation and provisioning etc. The work is to be completed as per manufacturer's specification . | Sq.ft. | 1100.00 | | |
| | Partitions : | | | | |
| | Rate to be included of all kinds of planes/levels, profiles and cut outs, etc. required for light fixtures, trap doors and ACs, boards, provision for light fittings and diffusers have to be made at no extra cost supported with metallic section etc. suitably fixed all complete as per drawing and direction. ii) The contractor must co-ordinate with electrical & AC Works for cabling, AC pipe works, etc. | | | | |
| 4 | Full Height Partly Glazed/ Solid Wooden Partitions (Including Door) : | | | | |

| | | | | | |
|---|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------|--------|--|--|
| | Providing and fixing full height partly wooden, partly glazed/ Solid partitions- specifications (Measurement shall be taken up to finished partition level & not of frame work and sal wood member shall go up to slab/beam soffit) Aluminium Frame Size -50mm X 50mm X 1.60 mm thick 450/600 mm c/c both ways 8 mm thk. HDEM R Termite & Borer proof from both the sides 1.0mm thick approved shades of laminate 5 mm thick float glass (for Partly Glazed Partitions) Etching as per approved design including 32mm partly glazed/ fluse door with teak wood Beading 1 mm lamination on both sides 8 mm plain glass, (for partly Glazed Doors) with Frame of 100mm x 50 mm, Note -Including all fittings,material, screw, labour etc. Complete. (Note- Make- Infra Marketing, Century, Green Ply & Duro.) | Sq.ft. | 260.00 | | |
| 5 | 12.0 mm TOUGHENED GLASS partition with bottom 8" solid partition /Boxing with Framing. Toughened Glass Fixed Glazing with itching as instructed by the Engineer | | | | |
| | Providing and fixing at site wooden boxing/partition over toughened glass Boton and Top portion to be made up of 18.0mm MR board to be hanged from the existing RCC ceiling with help of metallic anchor fasteners to be placed at 450mm c/c as per the space available, the exposed portion of the solid partition shall have approved shade of textured finished 1.0mm thick laminate of approved shade to be fixed in combination of two colors, the solid boxing is to be fixed such that to align the same with the fixed toughened glass below, the cost shall include all materials, labour, ne cessary staging work contingencies etc complete. | Sq.ft. | 90.00 | | |
| 6 | Low Height partitions With / Without Glass : | | | | |
| | Providing and fixing Half Height (approx-1200 mm ht.) partitions. Aluminium Frame Size -50mm X 50mm X 1.60 mm thick 450/600 mm c/c both ways(Horizontal/Vertical) 8 mm thk. HDEM R Termite & Borer Proof from both the sides 1.0mm thick approved shades of laminate, 12.00 mm thick float glass Etching as per approved design wicket gate wherever required with Godrej Night latch Note -Including all fittings,material, SS hinges, SS tower bolts screw, labour etc. Complete. (Making provision for items like softboards, white boards,etc. as & where required. (Note- Make- Archid, Century, Green Ply & Duro.) | Sq.ft. | 280.00 | | |
| | Panelling Works (Walls , Columns, etc): | | | | |
| | Rate to be included of all kinds of levels/planes, profiles and cut outs required for elevation and fixing of light fixtures, trap doors and ACs, provision for light fittings, boards and diffusers have to be made at no extra cost supported metallic sections, etc. suitably fixed all complete as per drawing and direction. ii) The contractor must co-ordinate with electrical & AC contractor for cabling, AC pipe works, etc. | | | | |
| 7 | Wall/Column Panelling | | | | |
| | Providing, making and fixing single skin paneling (Using 8 mm thick HDEM R), plain and/or curved in profile, on walls, front facia, boxing for rolling shutter, and/or columns and/or glazing soffits at various parts of the premises, upto 3 mt height and boxing of 0.10 – 0.45 mt. ht., as required, made out of 50 x 25 x 1.0 mm thk weighing 0.467 kg/Rft aluminum frame, vertical and horizontal sections placed at 450 mm c/c both ways or less as per site condition and finished with 6 mm thick HDEM R shall be fixed over the frame (either in one plane or at different levels) finished with 1mm thick decorative laminate of approved made and shade (in one or multi colour) shall be fixed with proper adhesive as directed. Top of the paneling edges / is to be provided with laminate or teak wood decorative beeding of 35mm x 20 mm finished with polish/painting as directed. | Sq.ft. | 900.00 | | |
| 8 | Cabinet for Electric Panel : | | | | |

| | | | | | |
|---------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------|--------|--|--|
| | Providing, making and placing in position cabinet with openable shutter around the electric panel. Cabinet and shutter made of 18mm thk HDEM. All visible surfaces shall be laminated with 1 mm thick Laminate on external surfaces of approved make and shades & painting the internal surfaces with 2 or more coats of synthetic enamel paint, including providing teakwood lipping of size 20 x 6 mm on edges. Rate to include for necessary hardware fixture like providing with 3 nos. of 75mm long SS hinges for each shutter, two nos of 75 mm tower bolt (one top and bottom), SS handles to shutters, magnetic catchers for each shutter and multipurpose Godrej or ebco lock. (Measurement area = Measurement to be taken for the front surface area of the cabinet). | Sq.ft. | 70.00 | | |
| | Providing, making and fixing Toughend Glass Door:- 12mm thk single/double shutter toughened glass doors, <u>Including Floor springs</u> <u>make Hardwvn/Dorma</u> set, Upper patch, lower patch, lock key plate, provision of locking system(Godrej Only), etc. One set of 25 mm dia S. S. brush finish pull handles (approx. 300mm length) "C" shaped, of approved make Including Etching pattern, Note- Including, labour, transport, material, delivered and placed in position at site of work. Toughened Glass Fixed Glazing with itching as instructed by the Engineer | Sq.ft. | 100.00 | | |
| 9 | Toughened Glass Fixed Glazing with itching as instructed by the Engineer | Sq.ft | 50.00 | | |
| 10 | Providing & fixing at site notice board of size 8' x 6' to be made up of kail/pine wood frame of size 2" x1" wooden section with 5.0mm plain glass The Notice board shall have 19.0mm soft board lining at back with approved shade of cloth, and lockable shutter strictly as per the design & drawing etc complete. | Sqft | 50.00 | | |
| Furnishing Works : | | | | | |
| Tables :- | | | | | |
| | Providing and supplying table detailed below : 1.- 18 mm thick HDEM 2.- 1 mm thick laminate on external surfaces and 0.8 mm thick lamination on internal surfaces of approved make 3.- TW half round beading of sect 20 x 12 mm duly polished 4.- Drawer unit of width 350mm (clear internal), consisting of set of 3 nos. of drawer. 5.-Drawer made of 18 mm thk. MR Ply wood for the front and rear 12 mm HDEM for sides and 6mm thk MR ply for the bottom sliding & teak wood beading of sect. 20 x 6 mm 6- EBCO Sliding Telescopic Rail +M S powder coated keyboard tray with mouse tray. Note all fittings, fixtures, locking arrangement, handles, etc. Complete. (Note- Make- Infra Marketing, Century, Green Ply & Duro.) | | | | |
| 11 | same as above but providing and supplying Executives Branch Manager of size 6' x 3' x 2.6' ht. | No. | 1.00 | | |
| 12 | same as item above but providing and supplying Officer / Relationship Manager/ Auditor Tables of size 5' x 2.6' x 2.6' ht. | No. | 3.00 | | |
| 13 | GRAHAK MITRA | No. | 1.00 | | |
| 14 | WRITING TABLE | No. | 1.00 | | |

| | | | | | |
|----|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------|--------|--|--|
| 15 | Providing and fabrication of 5'-0" or as per site requirement SWO Counters with counter body of 18mm, 12mm & 6mm thk plywood. The counter top (the working top to be of 19mm thk block board 3'0" wide working top must be at 2'6"ht from the floor. A ready made metallic keyboard tray EBCO make and a drawer unit having 3nos of drawers provided with Godrej/Clik multi (automatic) lock. Top drawer to have cash separation arrangement. A round PVC cable crossing socket must be fixed on the table top for power/data cable crossing. A foot rest made of 19mm thk block board (box type) to be fixed and a ready made CPU carrier/ Trolley with wheels to be provided. All the exposed surfaces to be covered with 1 mm thick laminate. All inside/ hidden surfaces/ drawers must be finished with 0.8 mm thick white laminate. All the corners/ edges of plywood and block board to be protected with 6mm thick teak wood plain beads. The counter must be provided coloured (approved blue) 1mm thick laminate at front face of counter with cuts & slots to enable laying of electrical, telephone and data lines as per requirement. Complete as per bank's requirements. | No. | 4.00 | | |
| 16 | Storages / Credenza : STORAGE CABINETS: Providing & fixing storage cabinets upto required height & 600mm deep as per architects drawings. architects cabinets shall be made of 19mm thick MR Ply with approved laminate on Top and all exposed surfaces. The cabinets shall be 2mtr. High & shall have lockable shutters in the front duly laminated on front face and painted at the back face with superior quality synthetic enamel paint of approved shade & quality it shall have storage shelves at every 35cm gap. For vertical storage of files. All the skeleton work to be done with 19mm thick MR Ply of superior make and the back shall be 8mm thick MR ply of superior make good for pasting laminate. The shutters shall have locking arrangement with superior quality brass mortice lock Godrej or equivalent The shutter shall be fixed on sides of the cabinet with superior quality brass. All the exposed faces shall be same laminated and other faces duly painted with superior quality synthetic enamel paint (Asian, J&N, Dulux or Berger). The cost includes cost of all Hings, Hardware, Locks, Handles & fastners etc. | sqft | 120.00 | | |
| 17 | Officer Storage/Side Credenza/Back Credenza : Side unit with three drawers including locking arrangements (Godrej) for Officers, SWO & Asstt. 3'3" x 1'3" x 2'6" | No. | 8.00 | | |
| 18 | Corian Marble Surfaces on Furniture / Partitions : | | | | |
| | Supplying, Fabrication and Installation of Dupont/Corian of thickness as specified below, applied on table Top, Sides and any where wall, Logo etc in place of 1mm thick laminate, in plain or curved profile. To minimize material usage and facilitate installation a corner block of corian should be made square(Butt) rather than mitred. The edges to be joined should be straight, smooth and clean. Joints should only be made with joint Adhesive for Dupont Corian. All corners of a cutout must be rounded to 5mm radius and the edges smoothed, both on top & bottom, all around a cutout. "L" & "U" shaped corners need smooth 5mm radius inside corner. All works done to the satisfaction of the Architect/Project Manager. Note:- Work done including labour, material wastage, time limits, required hardware etc. Note:- Corian Sheet use in - Salt(Translucent series), Azure & Diamond Blue, preferably on BM's table, SWO counter, as directed. | Sq.ft. | 120.00 | | |
| 19 | Providing and fixing 35mm thick flush door openable /sliding with 1mm thick laminate on bath side cost shall be inclusive all accessories like ss hinges, mortise handle/lock(Godrej/Atomsberg/Plantex), latches, Door Closure(Godrej/Plantex) stopper, tower bolt etc. complete | Sqft | 70.00 | | |
| 20 | Wicket gate: Providing, fabrication and fixing of flush type wicket gate made 1mm thick laminate on bath side cost shall be inclusive all accessories like ss hinges, mortise handle/lock(Godrej/Atomsberg/Plantex), latches, Door Closure(Godrej/Plantex) stopper, tower bolt etc. complete | Sqft | 75.00 | | |
| 21 | Glass Works : | | | | |

| | | | | | |
|----|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------|--------|--|--|
| | Providing, making and fixing Plan Glass :- a. 12mm thick Plan glass b. Fixed with " D " brackets/ SS fittings as required. c. Etching film to be done as directed Note-The cost to include all materials, labour, hardware etc., Fixed Glazing with itching as instructed by the Engineer | Sq.ft. | 100.00 | | |
| 22 | Drop & Complaint Box : | | | | |
| | Providing & fixing at site drop & complaint box of size 300 mm x 400 mm to be made up of 1st class steam beach wood frame of size 25 mm x 25 mm wooden section, front 6 mm thk plain glass. The boxes shall have 12 mm py with approved shade of laminate and lockable shutter as per design 7 drawing, etc. complete. | Nos. | 1.00 | | |
| 23 | ACP Aluminium Composite Panel : | | | | |
| | Providing and fixing 3 mm thick ACP (Aluminium Composite Panel) panelling, aluminum foil thickness to be min. 0.20mm on both side , bright silver shade or by Bank's approval. with Aluminum Hallow section frame of 1.5'x 1' (medium weight) at 2'x2'/c both ways. ACP to be in full size panels fixed to the frame with 3M or equivalent adhesive. All joints to be filled/ finished with silicone based sealant. The provision for fixing AC units with extra frame to be fixed. (Eurobond, Fujibond, Alcobond, etc. or equivalent) complete work as directed. | Sq.ft | 700.00 | | |
| 24 | Glass shelf of size 2' x 1' WITH F-BRACKETS | No. | 6.00 | | |
| | Providing and Fixing 12 mm Toughned Glass of size 2' x 1' with F-Bracket including all fitting , labour etc complete. | | | | |
| | | | | | |
| | TOTAL AMOUNT FOR INTERIOR WORK (EXCL. GST) | | | | |