

STATE BANK OF INDIA
LOCAL HEAD OFFICE, GUWAHATI
PREMISES & ESTATE DEPARTMENT
GUWAHATI, ASSAM.

AO GUWAHATI

BOQ for Supply, Installation and Commissioning of Air conditioning units at Temporary Premises of AO Guwahati

Sl.No.	Description	UOM	Qty.	Rate (Rs.) (Exclusive of GST)	Amount (Rs.) (Exclusive of GST)
A	High Side work: Supply of Machines				
1	Supply of 2.0 TR Cassette type inverter air conditioners minimum 5 star rating with Copper Condensor Coil and refrigerant (R32 or R410A) Indoor unit ceiling hung comprising cooling coil, evaporator fan with motor, filters, insulated drain pan, drain pump, expansion valve, refrigerant filter drier with codeless remote control unit, etc. Outdoor unit comprising single phase hermetically sealed scroll / rotary compressors, condenser coil with fan & motor, starters / controls / cutouts / relays etc., mounted inside a powder coated sheet metal cabinet of 2mm thick, duly treated for corrosion protection complete, mounted on ribbed rubber pads. AC Make, Voltas/Blue Star/Daikin /LG/Hitachi)	No.	9		
	TOTAL-A (Excluding GST)				
B	Low Side Work:Supply and Installation of machines and auxiliaries				
2	Installation charges of the 2.0 TR Cassette Split AC including outdoor frame / stands to withstand the full load of outdoor units and making good all the damage.	No.	9		
3	For 2.0 TR Copper Cassette type inverter air conditioners: Supply and laying of copper pipes, drain pipes (covered with GI pipes wherever necessary), copper wiring in GI conduits neatly drawn in professional manner from power points to outdoor / indoor units complete with all necessaries and making good all the damages. Unit length of refrigerant pipe measurement consist unit length of each suction & discharge line	RM	150		
4	Additional Drain Pipe: supply and fixing of 25/32 mm UPVC drain pipe with insulation	Mtr.	160		
5	Supply and Installation of 5 KVA Stabilizer for 2.0 TR Cassette ACs	Nos.	9		
	TOTAL-B (Excluding GST)				
GST will be extra as applicable.		Total: A+B (In Rupees)			