

EXTERIOR FLOORING AT STATE BANK BHAVAN BUILDING, AO, THRISSUR					
Sl.No	Description	Qty	Unit	Rate(Rs)	Amount(Rs)
1	Concrete tile flooring Providing and laying cement concrete tiles of minimum thickness of 25 mm and of approved , colour, pattern and manufacturer, over a 20mm thick cement mortar bed in proper lines and levels including labour, material, curing etc complete.	350	Sq.M.		
2	Dismantling of existing vitrified tiles, including cement mortar bed by manual/ mechanical means without damaging the base concete and disposing the debris outside the premises as directed by the Engineer-in-charge	350	Sq.M		
3	Provide and fixing speed breaker made with heavyduty rubber and fixed with bolts	16	RM		
4	Provide and fixing FRP make 45 x 45 size 5T capacity man hole cover after cutting necessary hole on concrete slab	4	Nos		
5	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering :1:4:8(1 cement : 4 coarse sand (zone-III) derived from natural sources : 8 graded stone aggregate 20 mm nominal size derived from natural sources)	0.5	CuM		
GST as applicable will be paid extra					