

| BOQ FOR CONSTRUCTION OF BOUNDARY WALL AT BANKS OWN PLOT FOR PROPOSED AO AND SBILD JORHAT | | | | | |
|---|--|-------------|------------|------------------|--------------------|
| Sl.No | Description of items | Unit | Qty | Rate(Rs.) | Amount(Rs.) |
| 1 | Earthwork in excavation for foundation trnches of wall, retaining walls, footings of column, steps, septic tank etc. including refilling the quantity as necessary after completion of works, breaking clods in return filling, dressing, watering and ramming etc. and removal of surplus earth with all lead and lifts as directed and specified, including bailing out of water where necessary: Upto 2000 mm below EGL in all type of soil. | M3 | 200 | | |
| 2 | Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level : 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40 mm nominal size) | M3 | 10 | | |
| 3 | Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering and finishing but excluding the cost of reinforcement - All work in substructure and super structure: 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) | M3 | 95 | | |
| 4 | Centering and shuttering including strutting, propping etc. and removal of form for Foundations, footings, bases of columns, etc. for mass concrete | SQM | 850 | | |
| 5 | Brick work in Cement mortar 1:4 (1 cement : 4 coarse sand) with 1st class bricks including racking out joints and curing complete as directed in all levels. Half brick wall (112 mm). | SQM | 330 | | |
| 6 | 12 mm thcik cement plaster in single coat on fair/rough side of brick/concrete walls for interior/exterior plastering in all levels finished even and smooth including curing complete as directed: In cement mortar 1:4 (1 cement : 4 fine sand) | SQM | 1100 | | |
| 7 | Painting two coats on new steel with enemal paint of approved shade and colour including cleaning of surface of all dirt, dust etc. Make: Asian paint, Deulux | SQM | 200 | | |
| 8 | Applying & Finishing walls with 2 or more coat of OBD paint of required shade over a coat of primer. Rate including cost of primer coat. Make: Asian paint, Deulux | SQM | 1100 | | |
| 9 | Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Thermo-Mechanically Treated bars | KG | 6245 | | |

| | | | | | |
|---------------|--|----|------|--|--|
| 10 | Structural steel work for main gate in boundary wall, with 40x40 mm squar MS hollow section and 40x6 mm flat MS section riveted, bolted or welded in built up section and framed work, including cutting, hoisting, fixing in position and applying priming coat of approved steel primer all complete as per designe and drawings provided by bank. | KG | 1100 | | |
| 11 | Demolishing brick work/RCC coloumns beams manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge. In cement mortar. This rate including clearing of jungle trees etc for cleraing the site for propsoed work. | M3 | 40 | | |
| Total: | | | | | |