

**NAME OF WORK: INTERIOR WORKS FOR NEW PREMISES OF THIMMAREDDYPALLI BRANCH, KANDUKUR RBO,
GUNTUR AO, ANDHRA PRADESH**

Item No.	Description	QTY	UNIT	RATE	AMOUNT
1	<p>FULL HEIGHT PARTLY GLAZED PARTITIONS: Providing & fixing in position metal stud dry wall partition with the following specifications: A) supporting system comprising of best locally available make 51 X 35 X 0.55 mm thick metal studs @ 600 mm c/c and 51 X 32 mm metal tracks at floor, middle, door and ceiling level with joints staggered. The verticals should touch the ceiling with horizontal ceiling channel at slab/beam bottom. The rate should include necessary strengthening with studs/tracks or channel at doors and other openings. B) 11 mm MDF plywood of banks approved branch and varinet fixed on both sides with 25 mm dry wall screws. C) 1 mm laminate on both sides (Banks uniform color layout color scheme) up to false ceiling level. D) 6 mm thick clear float glass with etching design as directed between 1200 X 2000 mm level in specified areas fixed with 85 X 15 mm teak wood jamb and 12 X 12 mm teak wood beading. E) All teak wood members to have melamine polish finish. Doors in partitions wherever required to be provided with 35 mm thick solid core ISI approved around teak wood lipping, around fixed in a concealed door frame of best quality teak wood three sides of sections size of 75x75 mm or as advised by the engineer in charge. Flush door shutters to be fixed with 1 mm laminate (banks uniform layout color scheme) on both sides and 8 mm clear float glass with etching design as directed with 50 X 15 mm teak wood jamb around the glass opening and 12 X 12 mm teak wood beading for fixing of glass on both sides including necessary hardware viz: door stopper, door silencer, Door set lock, handles, brass hinges of approved make & quality, melamine spray polish finish to all teak wood members etc. complete as directed. F) Door Closer of heavy duty 'Godrej' make heavy duty or equivalent to be fixed. Length X height up to false ceiling will measured for payment. Plywood area all over to be sprayed with an ti termite solution before use in the work. Old and existing partitions to be dismantled and stacked at site and charges for the same to be included in the quoted rate.</p>	35.00	SMT		
2	<p>BISON PANAL DOOR WITH STEEL GRILL GATE FOR UPS ROOM (FIRST FLOOR)FULL HEIGHT PARTLY GLAZED PARTITIONS: Providing & fixing in position metal stud dry wall partition with the following specifications: A) supporting system comprising of best locally available make 51 X 35 X 0.55 mm thick metal studs @ 600 mm c/c and 51 X 32 mm metal tracks at floor, middle, door and ceiling level with joints staggered. The verticals should touch the ceiling with horizontal ceiling channel at slab/beam bottom. The rate should include necessary strengthening with studs/tracks or channel at doors and other openings. B) 11 / 12MM bison panels of banks approved branch and varinet fixed on both sides with 25 mm dry wall screws. C) 1 mm laminate on both sides (Banks uniform color layout color scheme) up to false ceiling level. E) Doors in partitions wherever required to be provided with MS grill using around frame of 25x25x5 mm angle, flats/ plate ornamental and covered with 0.8 mm thick sheet and welded with handles, aldropsm hingess etc complete. Chowkhat frame shall be of angle iron of size 35x35x6 mm with secured hold false, PRIMING AND TWO COATS OF PAINTING ETC COMPLTE.</p>	10.00	SMT		

3	<p>BM CABIN FULL HT PARTITIONS WITH ONE SIDE VENEERED PLY AND OTHER SIDE 1MM LAMIANTE Providing & fixing in position metal stud dry wall partition with the following specifications: A) supporting system comprising of best locally available make 51 X 35 X 0.55 mm thick metal studs @ 600 mm c/c and 51 X 32 mm metal tracks at floor, middle, door and ceiling level with joints staggered. The verticals should touch the ceiling with horizontal ceiling channel at slab/beam bottom. The rate should include necessary strengthening with studs/tracks or channel at doors and other openings.</p> <p>B) 11 mm MDF plywood of banks approved branch and varinet fixed on both sides with 25 mm dry wall screws. C) 1 mm laminate on OUT SIDE AND 4MM VENEERED PLY of natural teak OF BAKS APPROVED QUALITY on inside sides (Banks uniform color layout color scheme) up to false ceiling level.</p> <p>D) 6 mm thick clear float glass with etching design as directed between 1200 X 2000 mm level in specified areas fixed with 85 X 15 mm teak wood jamb and 12 X 12 mm teak wood beading.</p> <p>E) All teak wood members to have melamine polish finish. Doors in partitions wherever required to be provided with 35 mm thick solid core ISI approved around teak wood lipping, around fixed in a concealed door frame of best quality teak wood three sides of sections size of 75x75 mm or as advised by the engineer in charge. Flush door shutters to be fixed with 1 mm laminate (banks uniform layout color scheme) on both sides and 8 mm clear float glass with etching design as directed with 50 X 15 mm teak wood jamb around the glass opening and 12 X 12 mm teak wood beading for fixing of glass on both sides including necessary hardware viz: door stopper, door silencer, Door set lock, handles, brass hinges of approved make & quality, melamine spray polish finish to all teak wood members etc. complete as directed. F)Door Closer of heavy duty 'Godrej' make heavy duty or equivalent to be fixed. Length X height up to false ceiling will measured for payment. Plywood area all over to be sprayed with an ti termite solution before use in the work. Old and existing partitions to be dismantled and stacked at site and charges for the same to be included in the quoted rate.</p>	30.00	SMT		
4	<p>Low Height Partition: Providing & fixing metal stud low height partitions with following specifications. a) Supporting system comprising of best locally available make 51 X 35 mm metal studs at 600 mm c/c and 51 X 32 mm metal tracks at floor, middle and at 1200mm level with joints staggered. The rate should included necessary strengthening with studs/tracks or channels at openings. b) 11 mm plywood MDF of banks approved brand and varient grade with 1mm laminate (as per banks uniform colour scheme) on both sides. c) 85x15mm teak wood capping on top and sides of openings. d) 12mm glass of 12"height on top of low height partition (total height to be 4'6" to 5') with necessary teak wood beading and etching work wherever required also to be fixed. The teak wood members to have melamine polish finish. Anti termite solution to be sprayed before using the ply wood in the work. A pin up board of size about of 2' x18" vertical or vice versa to be made on low ht partician one sode (nearer to sitting stations), with soft board and lenin cloth of superior quality with elegant beading around, one for each work station. Wicket Gate consisting of same construction of low height partitions of approved shade on both sides with all necessary hardware such as hinges, tower bolt etc. complete. Each wicket gate must be provided with necessary hardware of cp brass aldorp, towerbolt, autom atic mortice latch of banks approved make and model . The edges shall be finished with teak wood beading polished. Its cost to be included in the quoted rate of low ht partition. Dismantling of old partitons (low or any height) to be included in the quoted rate.</p>	35.00	SMT		

5	Voucher Writing Table:- Supplying & fixing cheque writing table as per the standard design.(1) Floor mounter type-circular type with 12mm toughened glass on top and 8 pegionon hole racks, standing type,top dia 90cm, ht 36"-42" white/blue laminated over 18mm ply work as per banks stanrdard design. (2) Wall mounted type- 3' long, 1' width 6 nos of vouche racks, ht 36-42" ht. top with 12mm toughened glass as per banks stadards with white and blue laminataed over 18mm ply wood as per banks standards.(please quote average rate of circular and rectangular type. Ply wood to be MDF of banks approved brand and varient.	1.00	EACH		
6	Roller Blinds:- Supplying & fixing in position of Roller Blinds of "Vista" shade model- screen white 101 model etc complete. While making the blind sides and bottom, 3" to be extended on walls and ^ on top. The measurement for payment shall be the same as opening sizze of the window. Conracotrs to factors their rate accordingly.	12.00	SMT		
7	Suggestion box as per banks sandard size, model in blue/ green lamiant with locking arrangement.	1.00	EACH		
8	Wall Panelling with ply and 1mm laminate: Providing & fixing metal stud wall panelling with the following specification: a) Supporting system comprising of best locally available make 51 X 35 X 0.55 mm thick metal studs @ 600 mm c/c and 51 X 32 mm metal tracks at floor, middle, door level and ceiling level with joints staggered. The verticals should touch the ceiling with horizontal ceiling channel at slab/beam bottom. b) 11 mm MDF panels fixed on one side with 25 mm dry wall screws for the entire height of panelling. c) 1 mm laminate (dark for bands, light for body, indesigns) up to false ceiling level. e) All teak wood members to have melamine polish finish. Length X height up to false ceiling will be measured for payment. plywood to be used in the work to be sprayed with anti termite solution. banks uniform layout policy color scheme to be followed. Aspecail panal of size abut 8' long and 5' height to be made consisting of alround boarder 6" width and 3" projected from wall blue laminated, internal panel area plane while laminted, a SBI LOGO blue laminate of 3' dia projected 3" above and a write up of 'BANK TO EVERY INDIAN" as big size as possible with in the panel with vinyl cut/flex etc as directed by the engineer in charge. The extra costs of th same to be added in the quoted rate. Wall panelling should not be done behind the side units, back units, sides of tables if leaning against walls, since will not be paid. Dismantling the existing work to be done and the charges for the same to be included in the quoted rate.	125.00	SMT		
9	COLUMN PANELLING with PLY AND 1MM THICK LAMINATE: for Column Panelling with frame work, 9mm thck bison panels , lamiante as mentioned in wall panelling work above.	15.00	SMT		
10	Storage Units: A) Providing, making and placing in position low height storage units upto 750 mm height or height as directed and 450 mm deep made with 18/19 mm MDF front sides and middle shelf and back side with 9 mm MDFof banks approved brand and varient ply covered with 1 mm laminate (dark for bands and light for body) at all exposed surfaces. The top shall have 25 mm mdf board 'post-formed' edge with pf lamination, Inner/unexposed surfaces to painted with two or more coats of enamel paint with putty finish including melamine polish finish for all wooden members. The rate to include cost of all necessary hardware viz., cabinets hinges, locks, handles, tower bolts etc. The unit should have teak wood beading 25 X 40 mm at top and edge lipping 20 X 6 mm complete. All internal areas to be sprayed with anti termite solution and finished with 0.8 mm thick laminte of half white shaede. Dismantling the existing work to be done and the charges for the same to be included in the quoted rate.	12.00	SMT		

	<p>11 Storage Units: WITH 4MM OST PLY A) Providing, making and placing in position low height storage units upto 750 mm height or height as directed and 450 mm deep made with 18/19 mm MDF front sides and middle shelf and back side with 9 mm MDF of banks approved brand and varient ply covered with 4 MM OST NATURAL TEAK VENEERD PLY at all exposed surfaces. The top shall have 25 mm mdf board 'post-formed' edge with pf lamination, Inner/unexposed surfaces to painted with two or more coats of enamel paint with putty finish including melamine polish finish for all wooden members. The rate to include cost of all necessary hardware viz., cabinets hinges, locks, handles, tower bolts etc. The unit should have teak wood beading 25 X 40 mm at top and edge lipping 20 X 6 mm complete. All internal areas to be sprayed with anti termite solution and finished with 0.8 mm thick laminte of half white shaede.</p>	4.00	SMT		
	<p>12 Single Window Counters: Providing & fixing 5ft-5 1/2 ft wide Single Window Counters with table top to be made of 25 mm MDF + 1 mm lamination finish as per the layout and as per the standard design with, drawers, ready made keyboard tray and ready made MS CPU stand of heavy duty / high quality in ivory colour. The front glass shall be 12 mm thick up to 5 ft. height from the floor level and a 15" wide horizontal g side unit consist of 4' long, 16" wide and 30" height made out of 18mm ply and external laminate 1mm thick with shelve and drawer arrangement along with necessary hardware to be done. Glass of same thickness shall be provided at 3'-6" level. The rate to include for back doors with 'Godrej' night latch. Special locks to be fixed which can opened with single key. Cash counter will have dural make cash closing door(booking counter door closure). Side unit consisting of 4' long, width 16" and height 30" with top two drawers and bottom shelf arrangement to be fixed for each counter. Table and side unit all internal area of the drawers, leg rooms to be finished with 0.8 mm thick half white laminate. (Low height partitions shall be paid for separately). side unit, table should be separatable and laminated all over including leaning side of the partitions. A vertical glass 12mm toughened should be fixed as per the design between the counters on front with suitable beadings/supporting structures. The counters front curved part ply to be done using flexible plywood. One foot rest 100MMX40MM made of teak wood and polished fixed at appropriate location to full length of 3' long. Banks Uniform lay out policy scheme to be implemented strictly with out any deviation hence the contractors are requested to understand in detail before quoting the rate.(clear inside to nside the lenth of counter shall be measured). Complete structure to be done with 18/19 mm thick MDF of banks approved brand and varient. Chanrges for dismantling the old counters to be included in the quoted rate.</p>	5.00	RMT		
	<p>13 BRANCH MANAGER TABLE (Size 1800 X 900 X 750 mm, Side table 1200X450X750mm): Providing, making & placing in position executive table and side table with the following specifications: a) Table top and all over /other members to be made in 18/19 mm of banks approved MDF and 4 MM OST OF NATURAL TEAK VENEERED PLY , all edges to have 20 X 6 mm teak wood lipping. b) One drawer cum shutter unit with necessary hardware viz: drawer channels,handles, locks etc. c) One ready made mobile CPU pedestal, drawer channel, of heavy duty and ivory colour. d) One ready made heavyduty ivory coloured with channels to be provided e) One foot rest 100MMX40MM made of teak wood and polished fixed at appropriate location to full length of 3' long f) Side table made with 18 mm MDF of banks approved brand and 1mm laminate all over and other members with necessary hardware viz., cabinet hinges, handles, locks, tower bolts, etc. and 25 X 40 mm teak wood beading and 20 X 6 mm teak wood lipping etc. g) All the exposed surfaces to have 1 mm laminate to match with other parts of the cabin of approved shade and brand. 6mm thick laqerred glass for the modesty panel with specified itching with Blue color with studs. All wooden members to have melamine polish. All internal area of the drawers, leg rooms to be finished with 0.8 mm thick half white laminate. Special locks to be fixed which can opened with single key. Dismantling and shifting out/away the old tables/side tables in phased manner to be done and its charges to be included in the quoted rate.</p>	1.00	EACH		

14	SERVICE TABLES (OFFICERS TABLE WITH OUT SIDE UNIT) (Size 1500 X 900 X 750 mm, Side table 1200X450X750mm): Providing, making & placing in position executive table and side table with the following specifications: a) Table top and all over /other members to be made in 18/19 mm of banks approved MDF and 1MM LAMINATE, all edges to have 20 X 6 mm teak wood lipping. b) One drawer cum shutter unit with necessary hardware viz: drawer channels,handles, locks etc. c) One ready made mobile CPU pedestal, drawer channel, of heavy duty and ivory colour. d) One ready made heavyduty ivory coloured with channels to be provided e) One foot rest 100MMX40MM made of teak wood and polished fixed at aproppriate location to full length of 3' long f) NO SIDE UNIT TO BE DONE. g) All the exposed surfaces to have 1 mm laminate to match with other parts of the cabin of approved shade and brand. 6mm thick laqerred glass for the modesty panel with specified itching with Blue color with studs. All wooden members to have melamine polish. All internal area of the drawers, leg rooms to be finished with 0.8 mm thick half white laminate. Special locks to be fixed which can opened with single key. Dismantling and shifting out/away the old tables/side tables in phased manner to be done and its charges to be included in the quoted rate.	1.00	EACH		
15	OFFICERS TABLES (Size 1500 X 900 X 750 mm, Side table 1200X450X750mm): Providing, making & placing in position executive table and side table with the following specifications: a) Table top and all over /other members to be made in 18/19 mm of banks approved MDF and 1MM LAMINATE, all edges to have 20 X 6 mm teak wood lipping. b) One drawer cum shutter unit with necessary hardware viz: drawer channels,handles, locks etc. c) One ready made mobile CPU pedestal, drawer channel, of heavy duty and ivory colour. d) One ready made heavyduty ivory coloured with channels to be provided e) One foot rest 100MMX40MM made of teak wood and polished fixed at aproppriate location to full length of 3' long f) Side table made with 18 mm MDF of banks approved brand and 1mm laminate all over and other members with necessary hardware viz., cabinet hinges, handles, locks, tower bolts, etc. and 25 X 40 mm teak wood beading and 20 X 6 mm teak wood lipping etc. g) All the exposed surfaces to have 1 mm laminate to match with other parts of the cabin of approved shade and brand. 6mm thick laqerred glass for the modesty panel with specified itching with Blue color with studs. All wooden members to have melamine polish. All internal area of the drawers, leg rooms to be finished with 0.8 mm thick half white laminate. Special locks to be fixed which can opened with single key. Dismantling and shifting out/away the old tables/side tables in phased manner to be done and its charges to be included in the quoted rate.	3.00	EACH		
16	PLAIN FALSE CEILING: Providing and fixing Concealed Grid suspended ceiling system of 12.5mm La Gyp / Boral Plaster Boards fixed to Frame Work / Rondo / Boral Metal System concealed grid key lock suspended ceiling system consisting of 5mm suspension rod, adjustable spring loaded suspension clip, top cross rail of 3000mm long of 0.55BMT and furring channel 4000mm long made of 0.5mm BMT the top cross rail to be suspended from ceiling at every 1200mm and furring channel to be fixed to top cross rail at every 600mm to make a grid of 1200 x 600m. All the above components are to be made of galvanized steel. The rates to include cutouts for lighting fixtures / AC grilles / Fire Alarm Detectors etc., along with necessary strengthening and supports for fixing of these. The board joints are to be flush finished with jointing compound and paper tape etc., complete as directed. All legroom internal area and drawer internal area to be finished with 0.8 mm thick halfwhite laminate after spraying anti termite tsolution. Rate to be quoted should include charges for dismantling the existing false ceiling neatly and disposing off the unserviceable materails. Dismantling the existing work to be done and the charges for the same to be included in the quoted rate.	35.00	SMT		

17	SILHOUTE Grid False Ceiling:- Providing and fixing in true horizontal level false ceiling grid system (SILHOUTE) of Armstrong World Industries/ Daikin / CEPro etc. The suspension system shall be silhouete revealed profile grid system with 15mm wide flanges incorporating a 3mm or 6mm central recess color, black or white revealed. Silhouette main runners and cross tees to have mitered ends with "birds mouth " notches to provide mitered cruciform junctions. Main runners to be spaced at 120mm c/c fixed by using 2mm pre-straightened GI wire. Main tee, rotary stitched of size 15mm x 44mm x 3600mm at every 1200mm c/c maximum and 1200mm cross tee of size 15mm x 44mm x 1200mm at every 600mm c/c maximum and 600mm cross tee of size 15mm x 44mm x 600mm at every 1200mm c/c maximum and 19mm x 19mm x 3000mm wall angle all-round the wall to form grid size of 600mm x 600mm and suspending the grid using 2mm pre-straightened GI wire and 6mm nylon rawl plug at every 1200mm intervals at the main tee and laying of dunne premier micro look mineral fiber tiles manufactured by Armstrong World Industries of size 600mm x 600mm x 15mm over the formed grid etc., complete as directed. Rate to be quoted should include charges for dismantling the existing false ceiling neatly and disposing off the unserviceable materails. Dismantling the existing work to be done and the charges for the same to be included in the quoted rate.	125.00	SMT		
18	Table for 'Grahak & Tech. Mitra' :- Providing table for grahak Mitra in curve shape as per the standards. Size 1500X680X750 with a drawer unit.	1.00	Nos.		
19	Buy back of old furniture in the existing premises: including removing and stacking out side as advised by the branch. While removng and stacking at site, no damages to be caused to the walls, floors and furniture. Removal should be done in phased manner as advised by the branch.	-1.00	Job		
20	Closing the rolling shutter with 12mm ply and 1 mm laminate with suitable structure with ply / wood to support etc complete.	10.00	SMT		
21	Providing and fixing ACP cladding white or Blue suiting to Banks uniform colour policy including fixing with suitable frame etc complete of standard quality and brand as under in ATM / e-corners/ e-lobbies etc complete. Cost of Logo to be included wherever required. A partition inside the ATM room with same materials and aluminium box section frame work to create back office also shall be measured under this item.(size 10'2" 10" ht). Dismantling the existing work to be done and the charges for the same to be included in the quoted rate.	50.00	SMT		
22	12MM THICK TOUGHENED DOOR FOR MAIN ENTRANCE OF THE BANK/ E CORNER MAIN ENTRANCE DOOR:Providing and fixing Main door for the main entrance of the bank/facade for e-corner as per banks standard design , make and materials of standard manufacturers along all accessories, fittings etc and 3M privacy film to be pasted as per design and drawing. The rate is for a finished item of work etc., complete as directed.(same specifications as mentioned under main door of the branch above)	10.00	SMT		
				Note: GST EXTRA.	